



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Réception des soumissions - TPSGC / Bid Receiving -
PWGSC

1550, Avenue d'Estimauville
1550, D'Estimauville Avenue
Québec
Québec
G1J 0C7

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
TPSGC-PWGSC
601-1550, Avenue d'Estimauville
Québec
Québec
G1J 0C7

Title - Sujet Reconst Quai Carleton-Sur-Mer	
Solicitation No. - N° de l'invitation F3731-180084/A	Amendment No. - N° modif. 003
Client Reference No. - N° de référence du client R.721198	Date 2018-11-15
GETS Reference No. - N° de référence de SEAG PW-\$QCM-039-17525	
File No. - N° de dossier QCM-8-41171 (039)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2018-12-17	Time Zone Fuseau horaire Heure Normale du l'Est HNE
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Jean, Serge	Buyer Id - Id de l'acheteur qcm039
Telephone No. - N° de téléphone (418) 649-2882 ()	FAX No. - N° de FAX (418) 648-2209
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

AMENDMENT 003 RECONSTRUCTION OF WHARF CARLETON-SUR-MER

The purpose of Amendment 003 is to provide answers to the questions asked.

Please apply the following changes to the Invitation to tender (ITT):

1) Questions and Answers 7 to 20

1) Questions and Answers:

Number	Question	Answer
7	Drawing 02/36: Do items listed include all items to remove? For example, only (1) bollard is indicated to be removed, but we see that other shall be too.	Mooring bollard have not all been indicated to be removed in order to lighten the drawing. Consider that this text is typical. See also detail #100 regarding mooring bollards on B wharf face.
8	Drawing 04/36: Is it possible to have more information on scope: obstruct punctures in sheet pile prior to pour concrete.	For bidding purposes, consider information in tender documents, stating that sheet pile on A wharf face was installed in 1988 and is in good condition. We will add pictures for that wharf face for more information. Because there are many ways to proceed, we will not define a specific working method. Goal is to prevent self-leveling concrete loss while pouring. Let's remind that for a project of this size, contractors shall go onsite to gather all required information (ref. specification 01 11 00, art 1.6.1).
9	Specification item 23: Do surfaces indicated consider sheet pile surfaces (contour), or linear surface? Vertical plane.	We are in fact talking about surface in a plane for payment. For works purpose, contractor shall determine real surfaces, considering the shape contour for materials etc.
10	Do you have an idea on how surface preparation and painting on F wharf face can be done? A part of it is under tide level and painting will be impossible	Work shall be done considering tides and curing time of paint.
11	Surface preparation on F wharf face: is it required to clean sheet pile under marine bottom or visible surface?	Work shall be done over elevation +0.5m or over marine bottom (no excavation).
12	Question from a supplier: ASTM A615 is related to Gr 75; 150Ksi is under ASTM A 722. Which one is wanted	We will get back for this clarification in addenda.
13	On drawings, we see BC contaminated material, but in bid form, there is an item for AB only. In what item BC material is paid	For this point, refer to section 31 23 33, art. 2.2. Allowed reuse of excavated material is described there.
14	On drawing, there is cresoted timber shown. In what item should it be paid?	If you refer to spur wharf, disposition is included in item 3. Plans allow evaluation of quantities.
15	Are the quantities for armor rock stones will be clarified soon? For now, 1t is indicated in bid form.	Yes, you can find the new bid form on Buy and sell site.
16	Painting for parking space and pedestrian will be paid in what item?	To be included in concrete slab item 11.2.

17	Will landing light be installed by contractor or by client?	Refer to drawing 17 and item 4 in bid form. Tower, landing light and spot will be installed by others.
18	You mention that temporary support of existing wharf before and after spur wharf demolition. What needs to be supported?	Refer to drawing 8. We notice that existing sheet pile ends on spur wharf cribwork. When demolishing cribwork, a part of it must be kept in place to support backfill between older cribwork inside main wharf and existing sheet pile. Because condition of older structures is unknown, it must be considered that they will be unstable.
19	For armor rock stones from Cap Seize and Escuminac ,item 29.2 Stones provided by departmental Representative : A. Who is in charge of loading, weighting, snow removal, maintenance for access road, municipal fees and laboratory test (quality control)? B. Is there a scale onsite? C. Are there loading restrictions period to consider?	A. Item 29.2 is explicit about this: yes all items mentioned in the question are included in the unit cost. B. A valid scale must be provided by the Contractor as described in Section 35 31 25. Adequate certification must be provided to Departmental Representative in accordance with the terms in the specifications. C. It is the Contractor's responsibility to verify this information. Please note that the stones belong to DFO and are available at quarries without constraint. DFO must be informed sufficiently in advance of the work schedule for stone recovery.
20	We request that DFO review the compositional criteria for the stones retained for the breakwater. We believe that sandstone is a good material for the construction of the breakwater.	DFO is willing to accept sandstone in the rock composition retained for the breakwater stones. However the minimum density required for sandstone is 2.75. In addition, all tests indicated in Table 1 of Section 35 31 24 must be redone for each batch of 10 000 mt of quarried stone and results must meet the acceptance criteria. Section 35 31 24 of the specifications will be amended at the next addendum.

*** All other terms and conditions remain unchanged ***