



## RETURN BIDS TO:

## RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works & Government Services  
Canada/Réception des soumissions Travaux publics et  
Services gouvernementaux Canada

1713 Bedford Row

Halifax, N.S./Halifax, (N.E.)

Halifax

Nova Scotia

B3J 1T3

Bid Fax: (902) 496-5016

## SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise  
indicated, all other terms and conditions of the Solicitation  
remain the same.

Ce document est par la présente révisé; sauf indication contraire,  
les modalités de l'invitation demeurent les mêmes.

### Comments - Commentaires

### Vendor/Firm Name and Address

Raison sociale et adresse du  
fournisseur/de l'entrepreneur

### Issuing Office - Bureau de distribution

Atlantic Region Acquisitions/Région de l'Atlantique  
Acquisitions

1713 Bedford Row

Halifax, N.S./Halifax, (N.E.)

Halifax

Nova Scot

B3J 1T3

<b>Title - Sujet</b> Remedial Excavation Shannon Park	
<b>Solicitation No. - N° de l'invitation</b> EB218-191957/A	<b>Amendment No. - N° modif.</b> 002
<b>Client Reference No. - N° de référence du client</b> EB218-19-1957	<b>Date</b> 2018-11-16
<b>GETS Reference No. - N° de référence de SEAG</b> PW-\$PWA-110-5814	
<b>File No. - N° de dossier</b> PWA-8-80074 (110)	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin</b> <b>at - à 02:00 PM</b> <b>on - le 2018-11-29</b>	<b>Time Zone</b> <b>Fuseau horaire</b> Atlantic Standard Time AST
<b>F.O.B. - F.A.B.</b> <b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input checked="" type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> Collier (PWA), Susan	<b>Buyer Id - Id de l'acheteur</b> pwa110
<b>Telephone No. - N° de téléphone</b> (902) 401-3352 ( )	<b>FAX No. - N° de FAX</b> (902) 496-5016
<b>Destination - of Goods, Services, and Construction:</b> <b>Destination - des biens, services et construction:</b>	

Instructions: See Herein

Instructions: Voir aux présentes

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address</b> <b>Raison sociale et adresse du fournisseur/de l'entrepreneur</b>	
<b>Telephone No. - N° de téléphone</b> <b>Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm</b> <b>(type or print)</b> <b>Nom et titre de la personne autorisée à signer au nom du fournisseur/</b> <b>de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

Solicitation Amendment 002 is being raised to answer questions from potential bidders as follows and to extend the closing date:

**Delete in its entirety:**

Closing Date

**Insert:**

The solicitation closes on November 29<sup>th</sup>, 2018 at 02:00pm Atlantic Standard Time.

**Question 1:**

Section 02 50 00 1.2.10 Management of contaminated water generated during soil remediation work, including separation, recovery and elimination of free-phase hydrocarbons, if encountered.

Do you have a volume of water that may require onsite storage?

**Answer 1:**

No, volumes of groundwater expected are to be determined by the Contractor, because they depend on the methodology/staging/scheduling that the Contractor chooses.

**Question 2:**

Section 02 50 00 1.5.1.1.1 Water Handling, Storage and Disposal:

Sufficient storage available on-site to manage excavation dewatering, if sampling and analysis is required to determine disposal options. If direct off-site disposal is used, i.e., pumping directly into tanker trucks for transportation off-site, no on-site storage is required.

If Water is deemed contaminated is the disposal and handling extra to the original contract?

**Answer 2:**

No, there is no extra to the contract. As per Section 31 23 33.01, Clause 1.2.1, groundwater management is included in the unit rate price for excavated material.

**Question 3:**

Section 02 50 00 3.6.1.2 Contractor will be responsible to sample and analyze water samples to determine appropriate disposal options. Departmental Representative will authorize disposal methodology and/or location, prior to disposal.

What are the sampling requirements for the potentially contaminated water?

**Answer 3:**

Sampling requirements will depend on the method of disposal that is chosen by the Contractor, e.g., if the Contractor wanted to dispose of water into the municipal (HRM) sewer system, then it would have to meet the sewer use by-laws (and be permitted by HRM).

**Question 4:**

Where this excavation is in very close proximity to the harbour and in areas excavation is below the high water mark, there is potential for large quantities of potentially contaminated water.

**Answer 4:**

Answered in the above questions. Please also refer to the Cross section note on drawing MAP-02 which requires the contractor to leave a berm of undisturbed existing material in place to minimize influx of water into the excavation.

**Question 5:**

Are there any traffic restrictions associated with the access to the site?

**Answer 5:**

Spec Section 01 52 00, Clause 1.11 has traffic control requirements. A Traffic Control Plan is also a requirement of the Environmental Protection Plan (Section 01 35 43, Clause 1.4.6.7). It should be noted to the bidders that for clarification, with respect to traffic control:

Any traffic associated with the Work (trucks, private vehicles, etc.) should only use Nootka Avenue. Sioux Road and Iroquois Drive are not to be used.

If snow removal is required, snow is not to be placed on Canada Lands property.

The road access from Nootka Avenue initially is on Canada Lands property (at the security gate). Permission has been granted by Canada Lands to use this access point, only up to the ramp to the Former Parking Lot (identified on Map-02 and Drawing No. 300-1). Use or travel on any other parts of Canada Lands property is not permitted. For clarity, the 'site' as referenced in the specifications, does not include any portion of Canada Lands property, including the permitted access roadway to the Former Parking Lot.

**Question 6:**

What are the survey requirements for the project?

**Answer 6:**

The topographic survey that is required by the Contractor (Section 31 23 33.01, Clause 1.8.4), will include both the layout of the three excavation areas as per the coordinates provided on Map-02, and establishment of the property boundary between the site and the Canada Lands property from the security gate on Nootka Avenue to the cove northwest of remediation area SHPK 02.

**Question 7:**

Are there any security/access requirements for the project?

**Answer 7:**

Site security is the responsibility of the contractor. Per Section 01 52 00, clause 1.7 the contractor is responsible to provide and pay for responsible security personnel to guard site and contents of site after working hours and during holidays. See Amendment 1 for clarification regarding site access.

Amendment 1 – Section 01 56 00, Clause 1.5, add 1.5.2 – Access to the site is through the locked gate at Nootka Ave. The Contractor will be provided and be responsible for the key to the locked gate. The Contractor will be responsible to maintain the security of the gated entrance and ensure only personnel and equipment associated with the project are granted access through the gate to the project site.

ALL OTHER TERMS AND CONDITIONS REMAIN THE SAME.