




C01	2018/10/17	ISSUED FOR TENDER	D.K.	NS
No.	Date	Description	Drawn by Designé par	Approved Approuvé

	<p>Detail number</p> <p>Sheet number</p>	<p>A Numéro de détail</p> <p>B Numéro de la feuille</p>
	<p>Linear dimensions in millimètres</p>	<p>Dimensions linéaires en millimètres</p>
<p>Consultant's Name Nom de l'expert-conseil</p>		<p>Eng. Stamp Sceau de l'ingénieur</p>

Project Title/Titre du projet


TERRA NOVA VISITOR CENTRE
REHABILITATION UPGRADES

GLOVERTOWN, NL

Drawing title/Titre du dessin

MAIN FLOOR
FRAMING LAYOUT

Designed by/Concept par A.F.		Date 2018/04/02
Drawn by/Designé par J.O. / D.K.		Date 2018/04/02
Checked by/Vérifié par C.S.		Date 2018/04/02
Project No./No. du projet 1326	Scale/Echelle AS SHOWN	Sheet No./ Node la feuille
Drawing Set No./No. de série du dessin S-02		



MAIN FLOOR FRAMING PLAN

SHEARWALL SCHEDULE			
SHEARWALL	STUD	13mm PLY	PANEL EDGE NAILING ANCHORS TO FOUNDATION
SW1	38 x 140	O/S FACE	150 c/c 13# @ 800
SW2	38 x 140	BOTH	150 c/c 13# @ 800
SW3	38 x 184	O/S FACE	150 c/c 13# @ 800
SW4	38 x 184	BOTH	75 c/c 16# @ 600

- NOTES:
1. NAIL INTERMEDIATE SUPPORTS @ 300 c/c.
 2. SOLID BLOCKING AT ALL PLYWOOD JOINTS, NAIL AT PANEL EDGE SPACING.
 3. PROVIDE BLOCKING BETWEEN STUDS ABOVE & BELOW ALL SW PENETRATIONS, NAIL AT PANEL EDGE SPACING
 4. FOR NAIL GUN USE, DECREASE NAIL SPACING BY 1/3.