

**Unit Price Table**

**Breakwater Construction – Spirity Cove**

**Project Number: 722963**

**November 11, 2018**

<b>Item</b>	<b>Specification Reference</b>	<b>Class of Labour, Plant or Material</b>	<b>Unit of Measurement</b>	<b>Estimated Quantity</b>	<b>Price per Unit GST/HST extra</b>	<b>Estimated Total Price GST/HST extra</b>
1	35 31 24	Core Stone (0.1-400kg)	m <sup>3</sup>	500		
2	35 31 24	Filter Stone (400-800kg)	m <sup>3</sup>	470		
3	35 31 24	Armour Stone (2-4 tonne)	m <sup>3</sup>	460		
4	35 31 24	Armour Stone (4-6 tonne)	m <sup>3</sup>	1,870		
5	35 31 24	Armour Stone (6-8 tonne)	m <sup>3</sup>	650		
6		Lump Sum Portion	L.S.	1		
<b>Total :</b>						

**Note:**

Lump sum items include all items required to complete the project in accordance with the drawings and specifications (which are not measured for payment), including, but not limited to:

- Mobilization/Demobilization.
- Inspector's room and board.
- Excavation and side cast of beach.
- Geogrid.
- Insurance/bonds/unknowns.