

722614

Breakwater Construction
Mary's Harbour, NL

2018-06-29

PART 1 - GENERAL

- | | | |
|--|----|---|
| <u>1.1 SECTION
INCLUDES</u> | .1 | Barriers. |
| | .2 | Traffic Controls. |
| <u>1.2 INSTALLATION
AND REMOVAL</u> | .1 | Provide temporary controls in order to
execute work expeditiously. |
| | .2 | Remove from site all such work after use. |
| <u>1.3 HOARDING</u> | .1 | Erect temporary site enclosure using new
1.2 m high snow fence wired to rolled steel
"T" bar fence posts spaced at 2.4 m centres.
Provide one lockable truck gate. Maintain
fence in good repair. |
| <u>1.4 GUARD RAILS
AND BARRICADES</u> | .1 | Provide as required by governing authorities
and to approval of Departmental
Representative. |
| <u>1.5 ACCESS TO SITE</u> | .1 | Provide and maintain access to adjacent
facilities. |
| <u>1.6 PUBLIC
TRAFFIC FLOW</u> | .1 | Provide and maintain competent signal flag
operators, traffic signals, barricades and
flares, lights, or lanterns as required to
perform work and protect the public. |
| <u>1.7 FIRE ROUTES</u> | .1 | Maintain access to property including
overhead clearances for use by emergency
response vehicles. |
| <u>1.8 PROTECTION FOR
OFF-SITE AND PUBLIC
PROPERTY</u> | .1 | Protect surrounding private and public
property from damage during performance of
work. |
| | .2 | Be responsible for damage incurred. |