



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Réception des soumissions - TPSGC / Bid Receiving -
PWGSC

1550, Avenue d'Estimauville

1550, D'Estimauville Avenue

Québec

Québec

G1J 0C7

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address

Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution

TPSGC-PWGSC

601-1550, Avenue d'Estimauville

Québec

Québec

G1J 0C7

Title - Sujet Reconst Quai Carleton-Sur-Mer	
Solicitation No. - N° de l'invitation F3731-180084/A	Amendment No. - N° modif. 008
Client Reference No. - N° de référence du client R.721198	Date 2018-12-06
GETS Reference No. - N° de référence de SEAG PW-\$QCM-039-17525	
File No. - N° de dossier QCM-8-41171 (039)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2018-12-17	Time Zone Fuseau horaire Heure Normale du l'Est HNE
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Jean, Serge	Buyer Id - Id de l'acheteur qcm039
Telephone No. - N° de téléphone (418) 649-2882 ()	FAX No. - N° de FAX (418) 648-2209
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation
F3731-180084/A
Client Ref. No. - N° de réf. du client
F3731-180084

Amd. No. - N° de la modif.
008
File No. - N° du dossier
QCM-8-41171

Buyer ID - Id de l'acheteur
QCM039
CCC No./N° CCC - FMS No./N° VME

AMENDMENT 008 RECONSTRUCTION OF WHARF CARLETON-SUR-MER

The purpose of Amendment 008 is to modify the plans and specifications with Addenda #1.

Please apply the following changes to the Invitation to tender (ITT):

- 1) Insert ADDENDA #1 attached.
- 2) The plans modified are titled as follow in the attachments: *F3731-180084_Addenda 01_bilingue-bilingual*

***** All other terms and conditions remain unchanged *****

SPECIFICATION

No	Reference	Description of modification
1	01 11 00 - Work related general information; Article 1.7.5	Add: «In actual condition, wharf can not be used to stockpile excavated material. To do so, wharf faces shall be supported by rock armor embankment, or stockpiling shall be done on centerline of wharf, in a way that loads do not spread on existing sheet pile wharf faces. Contractor shall provide with working method prepared by an engineer to demonstrate security of stockpiling».
2	01 11 00 - Work related general information, Article 1.7.7	Add: «Contractor shall pay for snow removal on worksite and where needed».
3	01 29 00 – Payments procedures; Item 7	Add: «Actual item also includes construction of a concrete slab section at location of former landing light».
4	01 29 00 – Payment procedures; Item 8.6	Remove: « for elevation transition and cribworks».
5	01 29 00 - Work related general information; Item 11.2	Add : «Marking for parking space and pedestrian walkway»
6	01 29 00 - Work related general information; Item 14.1	Add: «Item also includes supply and installation of manhole».
7	01 29 00 - Work related general information; Item 17.10	Add: «Pavement base and sub base are also included in actual item. Pavement at the end of A wharf face to joint new slab will be paid in this item».
8	01 29 00 - Work related general information; Item 18	Clarification: «item 18.1 is paid by the m3 and item 18.2 is paid by the ton».
9	01 71 00 – Examination and preparation; Article 1.4.8	Add «Tolerances for installation are : Tie rod elevation : 50mm Slab elevation : 25mm Piping : 25mm Equipment position: 25mm».
10	05 50 00 – Metal fabrication; Article 1.2.4 Article 1.3	Add: « provide departmental Representative with written description of welding procedures, 2 weeks before works begin or when asked by departmental Representative». Add 1.3.3: «Welding company certification. Contractor or welding sub-contractor shall possess a division 2 certification, which means to hire a part time engineer.

		Contractor shall carry out a regular quality insurance follow up and provide with weekly follow up reports or when asked by departmental Representative if required».
11	31 53 13.01 – Timber cribwork; Article 2.1.2.2	«Lag bolts must be used with standard ASTM F436 washers and be hot dip galvanized».
12	31 62 16.13; Steel sheet piles; Article 2.1.5.1 Article 3.2.7.2	Tie rods: «replace grade 150 by grade 75». Note: see plans for diameter modifications. Add: «An inspection with a camera done at Contractor's own expenses will be asked if there is a doubt with installation of rock anchors».
13	Appendix 1 mod.	Pictures taken on November 27 th were added.

PLAN MODIFICATION LIST

Modification identified by number 2 in a triangle and / or a with cloud around.

Modification number	Date / issuance #/ addendum #	Drawing number – Drawing title
1	2018-12-05 /2/ 1	C2- EXISTING CONDITIONS AND DEMOLITION PRELIMINARY WORKS PLAN VIEW
2	2018-12-05 /2/ 1	C4 - A WHARF FACE - EXISTING CONDITIONS AND PRELIMINARY WORKS
3	2018-12-05 /2/ 1	C5- F WHARF FACE - EXISTING CONDITIONS AND PRELIMINARY WORKS
4	2018-12-05 /2/ 1	C7 – C WHARF FACE AREA - EXISTING CONDITIONS SECTIONS AND DETAILS
5	2018-12-05 /2/ 1	C17 - PROPOSED WORKS PLAN VIEW
6	2018-12-05 /2/ 1	C18 - PROPOSED WORKS - LAYOUT PLAN VIEW
7	2018-12-05 /2/ 1	C19 - A WHARF FACE PLANNED ELEVATION VIEW AND DETAILS
8	2018-12-05 /2/ 1	C20 - A WHARF FACE DETAILS - F WHARF FACE PROPOSED CONDITIONS
9	2018-12-05 /2/ 1	C21 - B & C WHARF FACES NEW STEEL SHEET PILING PLAN & ELEVATION VIEWS
10	2018-12-05 /2/ 1	C22 - B AND C WHARF FACES - PLANNED SECTIONS
11	2018-12-05 /2/ 1	C24 - B & C WHARF FACES NEW STEEL SHEET PILING DETAILS
12	2018-12-05 /2/ 1	C25 - B & C WHARF FACES NEW STEEL SHEET PILING DETAILS
13	2018-12-05 /2/ 1	C26 - B & C WHARF FACES NEW STEEL SHEET PILING DETAILS
14	2018-12-05 /2/ 1	C27 - B & C WHARF FACES SECTIONS & DETAILS ANCHOR WALL, LADDERS, CAP, CLEATS & FENDERS
15	2018-12-05 /2/ 1	C28 - C WHARF FACE- REMOVABLE WHEELGUARD SECTIONS
16	2018-12-05 /2/ 1	C30 - WOODEN FLOATING DOCKS
17	2018-12-05 /2/ 1	C34 - E WHARF FACE- PLANNED WOODEN CRIBWORK
18	2018-12-05 /2/ 1	C35 - E WHARF FACE- PLANNED WOODEN CRIBWORK DETAIL
19	2018-12-05 /2/ 1	C36 - FINAL DETAILS
20	2018-12-05 /2/ 1	M01 - DOMESTIC WATER SUPPLY
21	2018-12-05 /2/ 1	M03 - DOMESTIC WATER SUPPLY