

QUESTIONS AND ANSWERS

- Q1. Aren't there concerns with the ice and the Lake being frozen?
- A1. The project completion period is through the winter months. Ice and the frozen lake will be factors to address during this construction time period.
- Q2. What is the purpose of the Turbidity curtain, if the water is frozen?
- A2. The turbidity curtain is eliminated as a requirement of the work when the lake is frozen.
- Q3. Another point of concern would be the frozen ground. Placing and compacting the 300mm of granular A will be more costly if the substrate and material being placed is frozen. Are you looking to heat and hoard the area?
- A3. Please refer to Specification Section 03 30 00, Paragraph 3.2 and Section 31 23 11, Paragraph 3.5. The contractor must address whatever means are necessary to construct the work as shown and specified.