

- 1 HR FIRE SEPARATION
NEW DECKING
NEW PLANTING BY PCA

- SHEET A2.1 NOTES
- 1 REMOVE AND DISPOSE OF EX. CONSTRUCTION SHOWN DASHED
2 REMOVE EX. GUARD RAIL
3 REMOVE EX. DOORS / FRAMES 106A & 111A. EX. SIGNAGE, WOOD DECKING & SLEEPERS.
4 REMOVE EX. WALL TO EXPAND KITCHEN ENCLOSURE.
5 PROVIDE NEW DOOR OPENING. REFER TO DOOR SCHEDULE.
6 CUT BACK EX. MILLWORK TO ACCOMMODATE NEW DOOR & REMOVE EX. SINK & FAUCET. EX. UPPER CABINETS TO REMAIN.
7 EX. DRINKING FOUNTAIN TO BE RELOCATED (COORDINATE CLEARANCE DURING DD).
8 EX. BASEBOARD HEATER TO BE REMAIN. REFER TO ELEC.
9 ITEMIZED PRICE NO. 2: REMOVE EX. LITES & FRAME.
10 EXISTING ELEC. PANEL TO BE RELOCATED. REFER TO ELECTRICAL.
11 REMOVE EX. PARTITION WALL & CEILING. MAKE GOOD EX. WALL.
12 REMOVE & DISPOSE OF EX. DESK
13 REMOVE & DISPOSE OF EX. DOOR. INFILL OPENING TO MATCH EX. WALL
14 REMOVE EX. WALL ASSEMBLY AS REQUIRED TO REINSTATE SHEAR WALL EFFECTIVENESS. REFER TO STRUCTURAL.
15 CUT AS SHOWN AND TEMPORARILY REMOVE EX. WOOD DECK & SLEEPER. CONSTRUCTION AS REQUIRED TO PROVIDE ACCESS DURING SLAB EXTENSION AT DOOR 106A. REINSTATE DECKING & SLEEPERS.
16 REMOVE EX. CONC. SLAB TO ACCOMMODATE RELOCATED DRINKING FOUNTAIN. TRENCH & MAKE GOOD CONCRETE SLAB. COORDINATE WITH MECH DWG. PREPARE TO RECEIVE FLOOR FINISH.
17 REMOVE EX. CONC. SLAB TO ACCOMMODATE SALT WATER PIPE RELOCATION. TRENCH & REINSTATE CONC. SLAB TO RECEIVE FLOOR FINISH. REFER TO MECH. DWG. FOR LOCATION. SALVAGE MILLWORK FOR REUSE & TO BE REINSTATED.
18 REMOVE EX. PLYWOOD UNDER TANK
19 REMOVE AND DISPOSE OF EXISTING MILLWORK AND COUNTERTOP. REFER TO DRAWING A11.2 TO COORDINATE EXTENTS OF REMOVAL. COORDINATE WITH NEW MILLWORK FRAMING BULKHEAD.
20 REMOVE AND SALVAGE FOR REUSE FOR EX. DECK PLANKS.
21 EX. MURAL TO REMAIN & MAINTAINED DURING DEMO AND CONSTRUCTION
23 CUT BACK / RE-FRAME OPENING. MATCH FINISH FACE TO EDGE OF FLOOR GRATE. MAINTAIN EX. HEIGHT.
24 EX. PENDANT LIGHT TO BE REMOVED. WIRING TO REMAIN. REFER TO ELEC.
25 EX. CEILING FANS TO REMAIN
26 EX. ST. STL SINK TO BE RELOCATED
27 REMOVE EX. CONC. SLAB TO ACCOMMODATE RELOCATED SS SINK AND NEW FLOOR DRAINS. TRENCH & MAKE GOOD CONCRETE SLAB. COORDINATE WITH MECH DWG.

PRELIMINARY—
NOT FOR CONSTRUCTION

3	NOV 28, 2018	ADDENDA #3			
2	NOV 9, 2018	ISSUED FOR TENDER			
1	OCT 15, 2018	ISSUED FOR TENDER REVIEW			

No.	Date	Description	Drawn By Dessiné Par	Approved Approuvé
Revision / Revision				

A	Detail number Sheet number	A Numéro de détail B Numéro de la feuille
B	Linear dimensions in millimetres	Dimensions linéaires en millimètres

Consultant's Name Nom de l'expert-conseil	Arch. Stamp Sceau de l'architecte
DSRA Architecture in association with Baird Sampson Neuert 5495 Spring Garden Road, Ste 400 Halifax, Nova Scotia, B3J 1G2 t. 902.420.9990 www.dsra.ca	

Project title/Titre du projet


TERRA NOVA VISITOR
CENTRE UPGRADES

Trans-Canada Hwy
Terra Nova National Park, NL A0G 4K0
Canada


Drawing title/Titre du dessin

DEMO PLAN

Designed by/Concept par J. NEUERT	Date NOV 28, 2018
Drawn by/Dessiné par J. KAN, A. CHUM	Date NOV 28, 2018
Checked by/Vérifié par P. CONNELL	Date NOV 9, 2018
Project No./No. du projet 1708	Scale/Echelle 1 : 100
Drawing Set No./No. de série du dessin	Sheet No./ Node la feuille A2.1



1 GROUND FLOOR DEMOLITION PLAN
1:100



2 DEMO INTERIOR ELEVATION
1:100

