


2 HEATING REVISIONS
M2.6 SCALE: 1:100

1 MEETING ROOM HEATING REVISIONS
M2.6 SCALE: 1:100

DRAWING NOTES:

- ③ REPLACE EXISTING CONTROL VALVE WITH NEW MODULATING ELECTRONIC CONTROL VALVE.
- ④ EXTEND EXISTING HEATING WATER SUPPLY AND RETURN PIPES TO SERVE NEW VAV HEATING COIL.
- ⑤ NEW MODULATING ELECTRONIC CONTROL VALVE.

PLOTTED ON 2018-12-14 BY MICHAEL REIMER
DOCUMENT SAVED IN H: \11800\11838\00\00 DRAWINGS\03 MECH\11838_M2.6.DWG

11838-01  MCW / AGE <i>Consulting Professional Engineers</i> 210-1821 Wellington Avenue Winnipeg, Manitoba, R3H 0G4 Phone - (204) 779-7900 Fax - (204) 779-1119 E-Mail: mcw_wpg@mcw.com	PROJECT:		ACTIVITY BASED WORKPLACE FIT-UP 269 MAIN STREET		REF. DWG. NO.	M2.6
	DESCRIPTION:		FIFTH FLOOR HEATING PIPE REVISIONS		DWG. NO.	RM-7
	DATE:	DRAWN BY:	SCALE:		ISSUED WITH:	
	2018-12-14	MR	AS NOTED		ADD#04M	



Addendum

Date: December 14, 2018

210-1821 Wellington Avenue
Winnipeg, Manitoba
R3H 0G4

Phone (204) 779-7900
Fax (204) 779-1119
www.mcw.com

Project Name: Victory Building Activity Based
Workplace Fit Up

Client: Verne Reimer Architecture

To: Verne Reimer Architecture

Attention: Richard Baronins

Email: rbaronins@vernereimer.com

Distribution: Verne Reimer Architecture Kevin Siddall

Project No.: 11838

ADD No.: 04M

Page No.: 1 of 1 (+attach)

Office: Winnipeg

From: Michael Reimer

ksiddall@vernereimer.com

Rodych Integrated Design Inc. Lindsay Nesbitt l.nesbitt@ridi.ca

Rodych Integrated Design Inc. Cindy Rodych c.rodych@ridi.ca

MCW/AGE – Steve Reaburn

In accordance with the drawings and specifications, provide in the tender all costs required to complete the work including items as listed below:

MECHANICAL

RE: HEATING CLARIFICATION

1. All existing pneumatic control valves to be replaced with new modulating electronic control valves.
2. Refer to RM-7 for fifth floor heating revisions.

MR/kam