

1 - GENERAL

1.01 DESCRIPTION

- .1 This section specifies requirements for the entire demolishing of various items designated to be removed at Chocolate Cove Wharf.

1.02 Measurement For Payment

- .1 The following items will be paid in a Lump Sum price and will consist of, but not necessarily be limited to, the following:
 - .1 Supply of Departmental Representative's site office.
 - .2 All non-hazardous material demolished, that is not creosote timber, is to be transported to a Registered, New Brunswick disposal site.
 - .3 Mobilization and Demobilization of all necessary equipment to make work progress during the entire contract.
 - .4 Construction, maintenance of temporary roads, complete removal once the deconstruction is completed.
- .2 All creosote timber removal, transportation and disposed of will be paid in tonnes weighed at the registered disposal facility. Note: some timber sections are pressure treated, but will be disposed of with the creosote timber.
 - .1 Disposal slips are to be submitted with each progress claim.

1.03 GENERAL REQUIREMENTS

- .1 A Notice to Shipping is to be issued prior to commencement and upon completion of work.
Email: notshipssyd@dfo-mpo.gc.ca
- .2 During construction, any vessels or barges utilized must be marked in accordance with the provisions of the Canada Shipping Act Collision Regulations.
- .3 Upon completion of the project, a written Notice to Mariners must be issued.

2 - PRODUCTS

NOT APPLICABLE

3 - EXECUTION

3.01 EXECUTION

- .1 Inspect site and verify with Departmental Representative objects designated for removal.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.

3.02 REMOVAL

- .1 Remove in their entirety all materials and objects specified for removal.
- .2 Do not disturb adjacent work designated to remain in place.

3.03 EXISTING STRUCTURES

- .1 Wharf Structure
 - .1 The Wharf structure to be demolished is in an advanced state of deterioration and is not considered safe for use as a working platform.
 - .1 The existing deck structure was not designed to accommodate surcharge loading that could result from heavy equipment operation or storage of materials as may be required for possible construction operations that may be undertaken to execute the work.
 - .2 If the contractor intends to operate equipment, machinery or load the Maces Bay Wharf structure in any manner, assessments of the structure with respect to the intended loading must be undertaken.
 - .3 Assessments of the Maces Bay Wharf structure with respect to the intended loading must be undertaken by a qualified professional engineer, registered in the Province of New Brunswick.
 - .4 Submit copies of such assessments to the Departmental Representative at least 4 weeks prior to beginning any work for his review and record. All assessment reports, drawings or other information provided shall be sealed and signed by the Professional Engineer responsible for the assessments.

3.04 DISPOSAL OF MATERIAL

- .1 All demolished materials, except materials designated to be reused, will become property of contractor and will be removed from site and disposed of to satisfaction of Departmental Representative and in accordance with environmental guidelines. It is the sole responsibility of the contractor to dispose of all demolished materials at an approved disposal site. Ensure that disposal site is approved and willing to accommodate any materials disposed of from work site.
- .2 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.

3.05 RESTORATION

- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.

- .2 Reinstall areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.

END OF SECTION