

## **1 GENERAL**

### **1.01 REFERENCES**

- .2 U.S. Environmental Protection Agency (EPA)/Office of Water
- .1 EPA 832/R-92-005, Storm Water Management for Construction Activities:  
Developing Pollution Prevention Plans and Best Management Practices.

### **1.02 ACTION AND INFORMATIONAL SUBMITTALS**

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Sustainable Design Submittals:
  - .1 Erosion and Sedimentation Control: submit erosion and sedimentation control plan in accordance with EPA 832/R92-005 authorities having jurisdiction.

### **1.03 DELIVERY, STORAGE AND HANDLING**

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements.

## **2 PRODUCTS**

### **2.01 MATERIALS**

- .1 Water: in accordance with Departmental Representative's approval.

## **3 EXECUTION**

### **3.01 PREPARATION**

- .1 Temporary Erosion and Sedimentation Control:
  - .1 Provide temporary erosion and sedimentation control measures to prevent soil erosion and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways, according to requirements of authorities having jurisdiction.

### **3.02 APPLICATION**

- .1 Apply water with distributors equipped with means of shut-off and with spray system to ensure uniform application.

### **3.03 CLEANING**

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
  - .1 Leave Work area clean at end of each day.

---

PWGSC

ROADWAY DUST CONTROL

SECTION 32 15 60

WHARF REMOVAL AND

PAGE 2

DISPOSAL

CHOCOLATE COVE WHARF

DEER ISLAND, N.B.

PROJECT NO. R.101030.001

---

- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
  - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.
  - .2 Place materials defined as hazardous or toxic in designated containers.

**END OF SECTION**