

PART 1 - GENERAL

1.1 DESCRIPTION

- .1 This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed.
- .2 Demolition and removal will consist of, but not necessarily be limited to, the following:
  - .1 Demolition, removal, and disposal of existing timber crib wharf with concrete deck.
  - .2 Removal and disposal of existing jib crane.
  - .3 Removal and disposal of wooden guiderail and posts.
  - .4 Removal and disposal of portion of existing asphalt.
  - .5 Removal and disposal of dredged material to an approved site.
  - .6 Removal and storage of existing sheds for re-use.
  - .7 Relocation of existing storage container to allow for demolition of wharf.
  - .8 Removal and storage of portion of existing armour stone for re-use, to allow for demolition of wharf.

1.2 GENERAL REQUIREMENTS

- .1 A Notice to Shipping is to be issued prior to commencement and upon completion of Work.
- .2 During construction, any vessels or barges utilized must be marked in accordance with the provisions of the Canada Shipping Act Collision Regulations.
- .3 Upon completion of the project, a written Notice to Mariners must be issued.

1.3 PROTECTION

- .1 Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Canada.
- .2 Place a floating boom around entire demolition site to prevent loss of any materials.
- .3 Remove all floating debris from water on a routine and timely basis.

1.4 MEASUREMENT FOR PAYMENT

- .1 Demolition and Removal: to be included in a lump sum amount and includes the cost of all plant, labour, and materials required to complete the Work as specified and indicated on the drawings.

PART 2 - PRODUCTS

NOT APPLICABLE

PART 3 - EXECUTION

3.1 EXECUTION

- .1 Inspect site and verify with Departmental Representative objects designated for removal.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.

3.2 REMOVAL

- .1 Remove in their entirety all materials and objects specified for removal.
- .2 Do not disturb adjacent Work designated to remain in place.

3.3 DISPOSAL OF MATERIAL

- .1 All demolished materials, except materials designated to be reused, will become property of contractor and will be removed from site and

disposed of to the satisfaction of the Departmental Representative and in accordance with environmental guidelines. It is the sole responsibility of the Contractor to dispose of all demolished materials at provincially approved landfill sites. Ensure that disposal site is willing to accommodate any materials disposed of from Work site.

- .2 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.
- .3 All treated wood is to be disposed of at the one of the Provincial Regional lined waste disposal sites at either Robin Hood Bay, St. John's, NL or Norris Arm, NL. The owner will be responsible for testing of the treated wood in accordance with the "Treated Wood Waste Disposal" Guidance Document published by the Provincial Department of Municipal Affairs and Environment" (GD-PPD-PPD-075.1). The results of this testing will be provided to the Contractor prior to the disposal of any treated wood. Refer to Appendix "A", Regulatory Approvals, for details.

#### 3.4 RESTORATION

- .1 Upon completion of Work, remove debris, trim surfaces, and leave Work site in clean condition.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of Work.

END OF SECTION