

- | | | |
|---------------------------------------|--|--|
| <u>1.1 SECTION INCLUDES</u> | .1 Barriers.
.2 Traffic Controls. | |
| <u>1.2 RELATED SECTIONS</u> | .1 Section 01 35 28 - Health and Safety Requirements.
.2 Section 01 50 00 - Temporary Facilities. | |
| <u>1.3 INSTALLATION AND REMOVAL</u> | .1 Provide temporary controls in order to execute Work expeditiously.
.2 Remove from site all such Work after use. | |
| <u>1.4 HOARDING</u> | .1 Erect temporary site enclosure using new 1.2 m high snow fence wired to rolled steel "T" bar fence posts spaced at 2.4 m on centre. Provide one lockable truck gate. Maintain fence in good repair. | |
| <u>1.5 GUARD RAILS AND BARRICADES</u> | .1 Provide secure, rigid guard rails and barricades around open excavations.
.2 Provide barricades along wharf structure when wheel guard is removed.
.3 Provide as required by governing authorities. | |
| <u>1.6 ACCESS TO SITE</u> | .1 Provide and maintain access to adjacent harbour facilities. | |
| <u>1.7 PUBLIC TRAFFIC FLOW</u> | .1 Provide and maintain competent signal flag operators, traffic | |

signals, barricades and flares,
lights, or lanterns as required to
perform Work and protect the public.

1.8 FIRE ROUTES

- .1 Maintain access to property
including overhead clearances for
use by emergency response vehicles.

1.9 PROTECTION FOR
OFF-SITE AND PUBLIC
PROPERTY

- .1 Protect surrounding private and
public property from damage during
performance of Work.
- .2 Be responsible for damage incurred.

END OF SECTION