

Containment Cell Construction**Cheggoggin Point SCH****Yarmouth County, NS****Project No. R.095833.001**

Containment Cell Construction

Page 1

PART 1 - GENERAL

- | | | | |
|-----|--|----|--|
| 1.1 | <u>Description</u> | .1 | This section specifies requirements for construction of the containment cell consisting of component layers, and to dimensions indicated. |
| 1.2 | <u>Reference Standards</u> | .1 | ASTM C127-88(1993)e1 (or latest edition) Specific Gravity and Absorption of Coarse Aggregate |
| | | .2 | AASHTO T85-88 (or latest edition) Specific Gravity and Absorption of Coarse Aggregate |
| 1.3 | <u>Related Work</u> | .1 | Refer to other Specification Sections for related information. |
| 1.4 | <u>Source Sampling</u> | .1 | Inform <i>Departmental Representative</i> of proposed source of materials and provide access for sampling at least 2 weeks prior to commencing work. Forward, prepaid, a sample rock to be used to a testing consultant to be determined by the Departmental Representative for approval. Sample to be between 5 and 10 kg, representative of quarry and submitted minimum 2 weeks prior to starting work. |
| 1.4 | <u>Existing Conditions and Haul Road</u> | .1 | It is important that Contractors intending to bid on work visit the site and ascertain what preparatory work will be required for the following:

.1 Condition of existing structures over which material must be hauled.

.2 Preparation, maintenance and removal of temporary roadways to and on the containment cell for the use of trucks, cranes, excavators, draglines, etc.

.3 Preparation, maintenance and removal of all temporary causeways and/or fills as |

Containment Cell Construction

Chegoggin Point SCH

Yarmouth County, NS

Project No. R.095833.001

Containment Cell Construction

Page 2

required for trucks, loaders, excavators, cranes, draglines, etc.

.4 The land surrounding the site is the property of Her Majesty the Queen in the Right of Canada and the Contractor will exercise extreme care to prevent damage to the land.

.5 Contractor shall be solely responsible for construction and maintenance of haul roads which shall be considered incidental to the work. All temporary roads shall be removed at the completion of the project and the land restored to its original condition.

1.5 Measurement for
Payment

.1 Corestone will be measured in accordance with **Section 01 29 00**.

.2 Filterstone (200-400 kg) will be measured in accordance with **Section 01 29 00**.

.3 Armourstone (2-4 tonne) will be measured in accordance with **Section 01 29 00**.

.4 Mobilization and demobilization will be considered incidental to work.

.5 Transportation of material to the site and any excavation and preparation of the foundation base will not be measured for payment but will be considered incidental to the work.

.6 No payment will be made for material used to construct and/or maintain haul roads, causeways, fills or working roadways on top of corestone layer.

.7 Clearing, grubbing and stripping of quarries to be incidental to the work.

.8 Making good to the satisfaction of the *Departmental Representative*, any damage to

Containment Cell Construction

Chegoggin Point SCH

Yarmouth County, NS

Project No. R.095833.001

Containment Cell Construction

Page 3

the existing structures will be considered incidental to the work.

- .9 Do not mix different categories of material in the same truckload. Only one class of material will be weighed for payment at any given time. If rocks of markedly different sizes are present, *Departmental Representative* reserves the right to weigh such rocks separately for payment. There will be no additional payment for weighing individual stone units which do not meet the category of material listed for the truckload.

PART 2 - PRODUCTS2.1 Materials

.1 Rock Material

- .1 All rock materials to be tested and approved by the *Departmental Representative* prior to installation in the work.

- .2 All rock materials to be free from cracks, seams and other defects which may impair durability.

.3 **Armourstone, Filterstone and Corestone to meet the following requirements:**

Specific Gravity minimum 2.65 and Absorption maximum 2.0%. Slate, sandstone, shale and stone containing mica not acceptable for corestone, filterstone or armourstone.

- .4 Actual Specific Gravity and Absorption will be determined by testing selected samples of material being incorporated into the works. Materials with a specific gravity less than 2.65 or an absorption rate in excess of 2% will be rejected.

.2 Corestone:

- .1 To be quarried material rough and angular in shape requiring approval by

Containment Cell Construction

Chegoggin Point SCH

Yarmouth County, NS

Project No. R.095833.001

Containment Cell Construction

Page 4

the *Departmental Representative* prior to being used in the work.

- .2 Material not to contain organic matter, frozen lumps, sod, roots, logs, stumps or any other objectionable matter.
- .3 Corestone gradation shall be within the following limits:

METRIC SIZE	% PASSING BY MASS
450 mm	100
200 mm	44 - 75
100 mm	25 - 50
50 mm	7 - 14

- .4 Silt and clay content must not exceed 3% by mass.
 - .5 The *Departmental Representative* will complete a visual inspection of corestone to determine acceptability for inclusion in the work.
 - .6 Material to be blended so that a homogeneous mix of smaller and larger sizes within the approved range is attained.
- .3 Filterstone:
- .1 Greatest dimension of each stone not to exceed two times least dimension.
 - .2 Filterstone shall be quarried or field stone, rough and angular in shape.
 - .3 Filterstone shall vary in size between 200 kg and 400 kg where shown on the drawings.

Containment Cell Construction**Cheggoggin Point SCH****Yarmouth County, NS****Project No. R.095833.001**

Containment Cell Construction

Page 5

.4 Fifty percent (50%) by weight of the Filter stone shall be individual stones greater than, or equal to, 300 kg.

.4 Armourstone:

.1 Greatest dimensions of each stone not to exceed two times least dimension.

.2 Armourstone to be quarried or field stone, rough and angular in shape.

.3 Armourstone shall vary in size between 2 and 4 tonnes as shown on the plans.

.4 Fifty percent (50%) by weight of the armourstone will be individual stones greater than, or equal to, 3 tonnes.

PART 3 - EXECUTION

3.1 Toe Protection

.1 Provide toe protection by placing armourstone for containment cell as indicated on drawings.

3.2 Corestone

.1 Place core material to lines, grades and dimensions indicated on the plan.

.2 Place material on clean harbour bottom to specified grades, and after the removal of kelp, debris, snow, ice, etc.

.3 Execute work in such a manner to protect core material from storm wave action or tidal erosion damage. Replacement of material lost due to storm or erosion damage will be the responsibility of the Contractor.

.4 Do not extend corestone material for containment cell more than 10 metres beyond filterstone protection.

Containment Cell Construction**Cheggoggin Point SCH****Yarmouth County, NS****Project No. R.095833.001**

Containment Cell Construction

Page 6

.5 Corestone material may be placed by end dumping. However, Contractor shall note that due to the side slopes of the containment cell that mechanical placing of the core will be necessary to produce the slopes and shapes required.

.6 Grades, lines, dimensions, slope and quantity of core, to be reviewed and approved by the *Departmental Representative* before proceeding with overlaying filter layer.

3.3 Filterstone

.1 Place filter layer material to lines, grades and dimensions indicated on the plans.

.2 Place filter layer material in two layers as shown on plans.

.3 Do not extend filter material for containment cell more than 10 metres beyond armourstone protection.

.4 Place each filterstone individually using mechanical means to the lines, grades and dimensions shown on the plans. Do not dump filter units into place. Commence placement at toe of slope and proceed up the slope towards the crest. Place each filterstone so that it is stable, secure on slope and supported by units below. Control placement of filterstone so as to produce a uniform and continuous cover over the underlying layer.

.5 Replace filterstone units broken or damaged during placement. Damaged units to be removed from the work and will not be paid for.

.6 Grades, lines, dimensions, slopes and quantity of filterstone to be reviewed and approved by *Departmental Representative* before proceeding with the overlying armour layer.

Containment Cell Construction**Cheggoggin Point SCH****Yarmouth County, NS****Project No. R.095833.001**

Containment Cell Construction

Page 7

-
- 3.4 Armourstone
- .1 Place armourstone in layers as shown on the plan to the lines, grades and dimensions shown on the plan.
 - .2 Place each armourstone individually using mechanical means to the lines, grades and dimensions shown on the plans. Do not dump armour units into place. Commence placement at toe of slope and proceed up the slope towards the crest elevation. Place each unit so that it is stable and secure on slope and supported by units below. Control placement of armour units so as to produce a uniform and continuous cover.
 - .3 Replace armourstone units broken or damaged during placement. Damaged units to be removed from the work and will not be paid for.
- 3.5 Tolerances
- .1 Completed component layers to be within the following tolerances of line and grades indicates:
 - .1 Core: $\pm 50\text{mm}$
 - .2 Filter: $\pm 100\text{mm}$
 - .3 Armourstone: $\pm 150\text{mm}$
 - .4 Armourcrest: minimum design elevation
- 3.6 Cross Sections
- .1 During construction the Contractor shall submit cross-section sheets to the *Departmental Representative* showing the following:
 - .1 Cross-sections at stations every 10 metres along the containment cell slope.
 - .2 The design cross-section showing proposed core, filter, and armourstone in solid lines.
 - .3 Superimposed in dashed lines elevations taken at 2 metre intervals perpendicular to the centreline and at top and toe of slopes showing core,
-

Containment Cell Construction

Chegoggin Point SCH

Yarmouth County, NS

Project No. R.095833.001

Containment Cell Construction

Page 8

filter, and armourstone as constructed surfaces.

- .4 Cross-sections to be referenced to the plan view of the containment cell with stations shown for reference.
- .5 Cross-sections to be submitted as work at each station is completed for each class of stone. Next layer not to be placed until *Departmental Representative* or his representative has reviewed and approved the as-built elevations for underlying layer.
- .6 After construction is complete and before the Final Certificate of Completion will be paid, Contractor to submit detailed as-built survey plan to *Departmental Representative* to show that contract grades and elevations have been achieved. Provide an electronic file and two sets of prints. Divers will be required to assist with survey for elevations required below chart datum. The following minimum requirements to be met:
 - .1 Elevations every 10 meters along the centerline of the containment cell and every 6 meters perpendicular to the centerline, on the end cone, and top and toe of slopes.

3.7 Settlement Monitoring

- .1 Contractor will monitor settlement during construction and provide *Departmental Representative* a daily report of settlement observations including cracking, slumping or slope failures. The daily reports will include the recording of crest elevations at the end of each day and again before work starts in the area the next day / time.

3.8 Protection

- .1 Take into account anticipated weather conditions and degree of exposure of site and tidal conditions in setting requirements

Containment Cell Construction**Cheggoggin Point SCH****Yarmouth County, NS****Project No. R.095833.001**

Containment Cell Construction

Page 9

for protection.

- .2 Schedule and carry out construction so that each phase of work is not left exposed longer than necessary.
- .3 Progress of placement of core and stone to be recorded daily by *Departmental Representative's* inspector with Contractor's concurrence. Replacement of material lost due to storm wave action or tidal erosion damage to be based on daily journal of work progress and to be considered incidental to the work.

3.9 Roadways

- .1 Construction, maintenance and removal of working roadway layers to be the responsibility of the Contractor and is to be considered incidental to the work.
- .2 Construction, maintenance and removal of causeways, fills, etc. as required, to be the responsibility of the Contractor and is to be considered incidental to the work.

3.10 Temporary
Navigational
Buoys

- .1 The Contractor is to maintain temporary buoys to mark the position of the outer end of the containment cell toe as construction proceeds. All buoys are to meet the requirements of Canadian Coast Guard Standard TP968 and be equipped with radar reflectors.

http://www.ccg-gcc.gc.ca/eng/CCG/ATN_Aids_To_Navigation_System

- .2 The Contractor shall coordinate the buoy installation with the local harbour authority.
 - .3 The Contractor is responsible for all costs associated with the supply, installation and removal of all temporary navigational buoys.
-