



AMENDMENT / MODIFICATION

003

**RETURN BIDS TO:
RETOURNER LES SUBMISSION À :**

Parks Canada Agency Bid Receiving Unit
National Contracting Services
220 - 4 Avenue S.E., suite 720
Calgary, AB T2G 4X3

Tender To: Parks Canada Agency
We hereby offer to sell to Her Majesty the Queen in right of Canada, in accordance with the terms and conditions set out herein, referred to herein or attached hereto, the goods, services, and construction listed herein and on any attached sheets at the price(s) set out therefor.

Issuing Office - Bureau de distribution

Parks Canada Agency
National Contracting Services
220 - 4 Avenue S.E., suite 720
Calgary, AB T2G 4X3

Title-Sujet Lake Louise Water Infrastructure Upgrades – Banff National Park		
Solicitation No. - No. de l'invitation 5P420-18-0432/A		Date: December 31, 2018
GETS Reference No. – No de reference de SEAG PW-18-00854687		Amendment No. - N° de la modif. 003
Solicitation Closes:		
at – á 02:00 PM	on – le January 15, 2019	Time Zone - Fuseau horaire MST - HNR
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>		
Address Inquiries to: - Adresser toute demande de renseignements à : Jen Maheu jennifer.maheu@canada.ca		
Telephone No. - No de téléphone (587) 432-8458		Fax No. – No de FAX: (866) 246-6893
Destination of Goods, Services, and Construction: Destinations des biens, services et construction: See Herein – Voir ici		

TO BE COMPLETED BY THE BIDDER (type or print)

Vendor/Firm Name	
Address - Adresse	
Name of person authorized to sign on behalf of the Vendor/Firm Nom de la personne autorisée a signer au nom du fournisseur/ de l'entrepreneur	
Titale - Titre	
Telephone No. - N° de telephone: _____	
Facsimile No. - N° de télécopieur: _____	
Signature	Date

AMENDMENT 03

This amendment is being raised to make changes to Appendix 1 – Combined Price Form and to distribute questions and answers.

A) APPENDIX 1 – COMBINED PRICE FORM**Section: UNIT PRICE TABLE****Previous:**

B	PROJECT LOCATION 1 – FEEDERMAIN AND RESERVOIR SITE					
4.2	Supply and Install Pull Box:	26 05 31				
4.2.1	In Landscaped Area		10	Ea		
4.2.2	In Road Structure		0	Ea		

Updated:

B	PROJECT LOCATION 1 – FEEDERMAIN AND RESERVOIR SITE					
4.2	Supply and Install Pull Box:	26 05 31				
4.2.1	In Landscaped Area		5	Ea		
4.2.2	In Road Structure		5	Ea		

Previous:

D	PROJECT LOCATION 3 – FAIRVIEW PUMP HOUSE SITE					
2.1	Supply and Install Watermain: 400 mm Diameter HDPE	33 14 16	90	lm		

Updated:

D	PROJECT LOCATION 3 – FAIRVIEW PUMP HOUSE SITE					
2.1	Supply and Install 400 mm or 250 mm diameter PVC DR18 Watermain	33 14 16	100	lm		

Bidders are instructed to make this change accordingly. If this is missed in the bidders bid, Canada will make this change on behalf of the bidder and use the unit price provided to obtain the correct total extended price.

B) QUESTIONS AND ANSWERS

Q17 Section 40 70 10 Reservoir Communication Cabling and Drawing E-002 indicate communication scope of work within the contract. Clarify which pay item within Appendix 1 does this apply to.

A17 Item B 4 in the Price Table.

Q18 Section 26 05 00 1.1.1.1.2 Indicates contractor is to supply Fortis Alberta switching cubical. Confirm

Division 26 is to supply Fortis Switching Cubical Precast Base 755-0557. Fortis Alberta is to supply and install the switching cubical.

A18 The contractor will be responsible to supply and install the precast concrete switch cubicle base and the precast concrete transformer base in accordance with Fortis Alberta requirements. Fortis Alberta will supply and install the switching cubicle and transformer.

Q19 Drawing E-121 does not indicate service guard posts protection for 75 KVA PMT or Switching Cubical. Clarify if this is required.

A19 Guard Posts will be required for both the switching cubicle and the transformer. Contractor to include in their bid price a total of eight 150 mm diameter concrete filled steel posts set in concrete.

Q20 I noticed this project was previously tendered and pulled. Can you please tell me why it was pulled?

A20 In accordance with SI06 "Insufficient Funding", Canada canceled the solicitation as the lowest compliant bid exceeded the amount of funding allocated to the work.

Q21 I can't find anywhere in the documents that breaks down the scope and quantities and allows for pricing the items required. Would it be possible to add the schedule to the documents?

A21 The Bid and Acceptance Form is contained in the Invitation to Tender document pages 10-14.

Q22 Drawing G-003 Detail 1: Reference to backfill with CLSM. Please provide pay item and required quantity.

A22 Item B 1 in the Price Table. Use plan view of the reservoir and valve chamber to scale the required dimensions. Assume 4.0 m depth. Grout minimum 1.0 m of all pipe ends.

Q23 Drawing G-003 Detail 1: Please provide details on structure depth, dimensions, and construction (ie cast in place or precast, wall/top slab thickness, etc)

Q23 Existing reservoir and valve chamber are of cast in place construction. See also response to Amendment 3, Q22.

Q24 Drawing G-003 Detail 1: Are abandon lines to be grouted?

A24 All lines identified to be abandoned shall be grouted using CLSM. Grout minimum 1.0 m of all pipe ends.

Q25 Drawing C-111, C-112, C-113 Please provide pay item and quantity for common excavation.

A25 Common excavation will be paid under item B 5.1 in the Price Table.

Q26 Drawing C-111, C-112, C-113 Please confirm Mannix Pit will be utilized for disposal of surplus excavated material.

A26 Excess non-organic excavated material can be disposed at Pit 69 near the Lake Louise Overflow Campground. All organic materials shall be removed and disposed outside the National Park.

Q27 Drawing C-111, C-112, C-113 We are requesting Pay Item 5.1 – Access Road, be measured in m2 as there are areas that are not a consistent width (turnouts, etc.).

Q27 Access Road construction will be paid under item B 5.1 in the Price Table.

Q28 Drawing C-111, C-112, C-113 We are requesting a pay item and quantities for clearing and grubbing.

A28 Clearing and grubbing will be paid in item B 2 in the Price Table.

Q29 Are there any development and building permits to be obtained by the contractor?

A29 No.

All other terms and conditions remain unchanged.