

## **Part 1 General**

### **1.1 ACCESS AND EGRESS**

- .1 Design, construct and maintain temporary "access to" and "egress from" work areas, independent of finished surfaces and in accordance with relevant municipal, provincial and other regulations.

### **1.2 USE OF SITE AND FACILITIES**

- .1 Execute work with least possible interference or disturbance to normal use of premises. Make arrangements with Departmental Representative to facilitate work as stated.
- .2 Maintain existing services to building and provide for personnel and vehicle access.
- .3 Where security is reduced by work provide temporary means to maintain security.
- .4 Departmental Representative will assign sanitary facilities for use by Contractor's personnel. Keep facilities clean.
- .5 Use only elevators existing in building for moving workers and material.
  - .1 Protect walls of passenger elevators, to approval of Departmental Representative prior to use.
  - .2 Accept liability for damage, safety of equipment and overloading of existing equipment.
- .6 Closures: protect work temporarily until permanent enclosures are completed.

### **1.3 ALTERATIONS, ADDITIONS OR REPAIRS TO EXISTING BUILDING**

- .1 Execute work with least possible interference or disturbance to building operations and normal use of premises. Arrange with Departmental Representative to facilitate execution of work.

### **1.4 EXISTING SERVICES**

- .1 Notify, Departmental Representative and utility companies of intended interruption of services and obtain required permission.
- .2 Where Work involves breaking into or connecting to existing services, give Departmental Representative 48 hours of notice for necessary interruption of mechanical or electrical service throughout course of work. Keep duration of interruptions minimum. Carry out interruptions after normal working hours of occupants, preferably on weekends.

### **1.5 SPECIAL REQUIREMENTS**

- .1 Carry out noise generating Work Monday to Friday from 18:00h to 6:00h.
- .2 Submit a schedule.
- .3 Ensure Contractor's personnel employed on site become familiar with and obey regulations including safety, fire, traffic and security regulations.
- .4 Keep within limits of work and avenues of ingress and egress.

- .5 Ingress and egress of Contractor vehicles at site is limited to 3 hours or less and must be moved immediately if directed.
- .6 Deliver materials outside between 6:00h to 18:00h unless otherwise approved by Departmental Representative.
- .7 All deliveries shall be scheduled 48 hours in advance so that the vehicle authorization form can be submitted to the Departmental Representative.

**Part 2 Products**

**2.1 NOT USED**

- .1 Not Used.

**Part 3 Execution**

**3.1 NOT USED**

- .1 Not Used.

**END OF SECTION**