



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

**Bid Receiving - PWGSC / Réception des soumissions -
TPSGC**

11 Laurier St. / 11, rue Laurier

Place du Portage, Phase III

Core 0B2 / Noyau 0B2

Gatineau

Québec

K1A 0S5

Bid Fax: (819) 997-9776

SOLICITATION AMENDMENT

MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address

**Raison sociale et adresse du
fournisseur/de l'entrepreneur**

Issuing Office - Bureau de distribution

Industrial Vehicles & Machinery Products Division

LEFTD - HS Division

140, O'Connor Street/

140, rue O'Connor,

East Tower, 4th Floor/

Tour Est, 4e étage

Ottawa

Ontario

K1A 0S5

Title - Sujet 3 Tonne Bridge Crane	
Solicitation No. - N° de l'invitation U6309-197271/A	Amendment No. - N° modif. 001
Client Reference No. - N° de référence du client U6309-197271	Date 2019-01-23
GETS Reference No. - N° de référence de SEAG PW-\$\$HS-652-76102	
File No. - N° de dossier hs652.U6309-197271	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2019-02-06	
Time Zone Fuseau horaire Eastern Standard Time EST	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Lafontaine, Raphael	Buyer Id - Id de l'acheteur hs652
Telephone No. - N° de téléphone (613) 296-5030 ()	FAX No. - N° de FAX () -
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

AMENDMENT 001

This amendment is raised to extend the bid closing date and modify the Statement of Work.

Closing Date

Delete:

2019-01-30

Insert:

2019-02-06

Statement of Work (SOW) – 12-12-2018

Delete: In its entirety

Insert: Bridge_Crane_SOW_Modified_EN.doc

All other terms and conditions remain unchanged.

Statement of Work (SOW)

1. Project Title:

3 tonne bridge crane installation

2. Project Objective:

The work is to supply, deliver, install, and commission a new 3 tonne electric overhead motorized bridge crane with electric chain hoist and motorized trolley. The bridge crane must be installed onto the rails and supports of our existing 10 tonne bridge crane. All three axes must be powered by variable frequency drives (VFD) with adjustable two speeds and operated via remote control. The 3 tonne and existing 10 tonne bridge cranes must be able to be used independently or simultaneously with the same acceleration and speeds via a selector switch on the remote controls

3. Existing 10 Tonne Crane

- Overall System: 10 tonne capacity bridge crane manufactured by Provincial Engineering Ltd. – Niagara Falls.
- Bridge: Double girder top running with approximately 12.2m span. Upgraded to adjustable 2 speed control by VFD in 2017
- Trolley: Top running. Upgraded to adjustable 2 speed control by VFD in 2017.
- Hoist: Wire rope hoist with 7m lift at a single lift speed of approximately 4.5m/minute
- Operators controls: Enrange Flex 8EX-T remote controls

4. Requirements:

The contractor must supply, deliver, install and commission the 3 tonne Bridge Crane and ancillary items in accordance with the following:

4.1. Complete Bridge Crane:

- The bridge crane and it's components must have a lift capacity of 3 tonnes
- The operator control must be via remote control with built in emergency stop button and selection switch to control either crane independently or simultaneously. Two remote controls must be supplied or the existing remotes for the 10 tonne bridge crane can be reused if compatible.

- The contractor must provide and install safety limit switches to prevent collisions into end stops or between the two crane bridges (3 tonne and existing 10 tonne). In simultaneous mode the cranes do not need to communicate in regards to end stop limit switches.
- The Bus bars and grounding must be upgraded to meet the total power requirements needed for both cranes being used simultaneously. The contractor is also responsible to upgrade the wiring from the bus bars to the disconnect.

4.2. Bridge:

- Top Running
- Single Girder
- Installed upon the rail runway of the existing 10 tonne bridge crane
- Travel speed via a VFD with adjustable 2 speed control
- The speeds and accelerations of the 3 tonne and 10 tonne bridges must be the same

4.3. Trolley:

- 3 tonne Kito MR trolley or equivalent
- Travel speed via a VFD with adjustable 2 speed control
- The speeds and accelerations of the 3 tonne and 10 tonne trolleys must be the same

4.4. Hoist:

- 3 tonne Kito ER2 electric chain hoist or equivalent
- A minimum of 6 meter lift
- Hoist speed via VFD with adjustable 2 speed control
- High speed of the 3 tonne hoist must match the speed of the 10 tonne hoist

4.5. Installation Requirements:

- All work including testing and commissioning must be completed according to the requirements of CSA B167-16

4.6. Commissioning:

- The contractor must arrange and pass an electrical safety authority (ESA) or Canadian Standards Association (CSA) equivalent examination of the 3 tonne bridge crane. The ESA/CSA report must be provided to the client within 1 week of being issued.
- The contractor must arrange and perform a load test of the 3 tonne bridge crane as per CSA B167-16. The results of the load test must be reviewed and accepted by an independent engineer before the 3 tonne crane can be put into service. Innovation, Science and Economic Development Canada will supply the necessary weights but the contractor must supply the rigging hardware to perform the load test.

4.7. Manuals, Drawings and Reports:

- The contractor must provide an electrical drawing of the complete system and manuals for the hoist, trolley and any other major components of the crane. The documents must be in English or French. Bilingual (English and French) documents are acceptable.
- The contractor must provide the Load Test and [ESA /CSA](#) Examination Report.

5. Constraints:

- 5.1. All efforts must be made to minimize the downtime of the 10 tonne crane during the delivery, installation and commissioning phases of the 3 tonne bridge crane.

6. Client Support:

- 6.1. Innovation, Science and Economic Development Canada will ensure the site and surrounding work area is clean and available during scheduled delivery, installation and commissioning phases of the 3 tonne bridge crane.