

**Part 1            ADDENDUM NO.3**

**1.1                General**

- .1            This Addendum is issued prior to tender closing and shall become an integral part of the Tender, Specifications, Drawings and Contract Documents for this project.
- .2            In the event of conflicts between the various Contract Documents, the order of precedence shall be as stipulated in the General Conditions of the Contract, except that this Addendum shall take overall precedence.

**Part 2            Question**

**2.1                For the pouring of concrete, because of several places where we must make concrete pouring in each community and that it may be impossible to do them all at the same time, we may not be able to bring a independent firm to test the concrete at all times that will proceed to a pouring. Is there an alternative that you accept to fit into your quality requirements?**

In order for all of the concrete to be poured to specification it is suggested that the contractor pre-cast all of the units and sea-lift them to each community along with the tanks and other materials. It must be noted that the sealift to each community is going to be late and winter weather may require heating and hording.

**2.2                Do you accept the option of taking a high-quality concrete and provide you with a concrete mixing procedure with a test at the beginning of the project only?**

We would accept the option of a high-quality concrete with a test at the beginning of the project. But we would ask that all site slabs have a cylinder poured and sent to a independent testing agency for testing. If any of the slabs fail the contractor would be required to remove and replace the slab.

**END OF SECTION**