

1.1 GENERAL

- .1 Canada will supply certain materials in the Contract for installation and incorporation into the Work by the Contractor.

1.2 MATERIAL SUPPLIED

- .1 Canada will supply the following:
- 2500 pieces of 200mm X 200mm pressure treated timbers at 6098mm lengths and 160 pieces of 200mm x 200mm timbers at 8537mm lengths, for use as crib timbers. Note that the crib timbers supplied by Canada is not a complete list of crib timber required to complete the work, as shown on the drawings.
 - 400 pieces of 150mm X 150mm pressure treated timbers at 6098mm lengths, for use as crib ballast floor timbers. Note that the ballast floor timbers supplied by Canada is not a complete list of timber required to complete the work, as shown on the drawings.
 - 28 pieces of 150mm X 200mm untreated hardwood timbers at 4878mm lengths for use as ladder uprights.
 - 350 pieces of 100mm X 150mm untreated hardwood fenders at 3,049mm lengths and 375 pieces of 100mm X 150mm fenders at 3,659mm lengths. Note that the fenders supplied by Canada is not a complete list of fenders required to complete the work, as shown on the drawings.
- .2 The location of all Canada supplied materials to be picked-up, is the DFO Storage Facility located on Glencoe Drive, Donovan's Industrial Park, Mount Pearl, NL. Contact Dion Upward, DFO, at 763-5689 to arrange for pick-up times.

1.3 DELIVERY REQUIREMENTS

- .1 Materials supplied by Canada will be available for pick-up following acceptance of Bid. Once turned over to the

Contractor, the Contractor is to make a complete check of the timber and report discrepancies to the Departmental Representative.

- .2 Failure of the Contractor to make a complete check of the Canada-supplied material and to acknowledge receipt of same shall not relieve him of this contractual responsibility to replace or repair any item subsequently found to be missing or damaged.
- .3 Departmental Representative will make final determination as to whether an item can be repaired or must be replaced.

1.4 CONTRACTOR'S DUTIES

- .1 Pick-up Canada-supplied material, at the DFO Storage Facility located on Glencoe Drive, Donovan's Industrial Park, Mount Pearl, NL.
- .2 Take possession of Canada-supplied material immediately upon pick-up and be responsible for transportation to site. Obtain and pay for services to load and transport to site. Handle at site, including lifting, uncrating etc.
- .3 Provide protection against inclement weather and site damage by use of appropriate covers.
- .4 Be responsible for the protection of such material against damage, loss, theft and fire from date of receipt until final installation of work is accepted by the Departmental Representative.
- .5 Any damage or loss of such material shall result in the Contractor being responsible for replacement or repair of timber at no cost to Canada.

P/N: R.100138.001	MATERIAL SUPPLIED BY	Section 01 16 10
Harbour Development	CANADA	Page 3
Prosser Rock, St. John's, NL		2019-01-01

- .6 The decision as to whether damaged items may be repaired or must be replaced with new materials shall be the Departmental Representative's decision.
- .7 Install such material and incorporate into the work. Perform assembly and make all connections as required to make item functional.
- .8 Dispose of containers, crating and protective covering off site as directed by the Departmental Representative as per Section 01 74 21.