



Parks Canada
Parcs Canada



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Parks Canada Agency
220 4 Ave SE, Suite 720
Calgary, AB T2G 4X3

AMENDMENT / MODIFICATION

002

Tender To: Parks Canada Agency

We hereby offer to sell to Her Majesty the Queen in right of Canada, in accordance with the terms and conditions set out herein, referred to herein or attached hereto, the goods, services, and construction listed herein and on any attached sheets at the price(s) set out therefor.

Soumission aux: l'Agence Parcs Canada

Nous offrons par la présente de vendre à Sa Majesté la Reine du Chef du Canada, aux conditions énoncées ou incluses par référence dans la présente at aux annexes ci-jointes, les biens, services et construction énumérés ici et sur toute feuille ci-annexée, au(x) prix indiqué(s).

Comments - Commentaries

Vendor/Firm Name and Address

Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution

Parks Canada Agency
220 4 Ave SE, Suite 720
Calgary, AB T2G 4X3

Title-Sujet Rock Creek Campground Water Treatment System – Grasslands National Park		
Solicitation No. - No. de l'invitation 5P420-18-0508/A		Date: February 8, 2019
GETS Reference No. – No de reference de SEAG PW-19-00861445		Amendment No. - N° de la modif. 2
Solicitation Closes:		
at – à 02:00 PM	on – le February 19, 2019	Time Zone - Fuseau horaire MST - HNR
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>		
Address Inquiries to: - Adresser toute demande de renseignements à : Rebecca Chen rebecca.chen2@canada.ca		
Telephone No. - No de téléphone (587) 439-3529		Fax No. – No de FAX: 1-866-246-6893
Destination of Goods, Services, and Construction: Destinations des biens, services et construction: See Herein – Voir ici		

TO BE COMPLETED BY THE BIDDER (type or print)

Vendor/Firm Name	
Address - Adresse	
Name of person authorized to sign on behalf of the Vendor/Firm Nom de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur	
Titale - Titre	
Telephone No. - N° de telephone: _____	
Facsimile No. - N° de télécopieur: _____	
Signature	Date

Amendment 02

This amendment is being raised to distribute information from the bidder's teleconference.

A) SITE VISIT ATTENDEES

Vendor	Representative's Name
Acadia Construction Management Ltd.	Garnett Radcliffe
Dunmac General Contractors Ltd.	Riley Magee
Southern Design and Build	Brandon Paulhus
Greg Penner management Ltd/DG Konkin Construction	Greg Penner
Leeville Construction Ltd.	Dustin Woloschuk
JNG Electric	Greg Wilson

Contact information for the attendees are available upon request and approval from the vendors.

B) TENDER PACKAGE REVISIONS

Specifications Section 01 11 00 Summary of Work
1.7 Work Sequence, part .8

DELETE:

2. Obtain Final Completion of the Work by July 31, 2019 (Contract Completion Date).

REPLACE WITH:

2. Obtain Final Completion of the Work by August 30, 2019 (Contract Completion Date).

C) QUESTIONS & ANSWERS

Q1 Are the drawings available electronically?

A1 Yes, the drawings are available in the package for download on the buy and sell website.

Q2 Has this project been tendered before?

A2 Yes, a version of this work has been tendered before. This current tender does not include the shower and washroom facility seen in previous tender.

Q3 Is there still a building?

A3 Yes, there is a simple utility building shown in the structural drawings to house the water treatment system.

Q4 Can a seed and mulch supplier be provided?

A4 PCA has provided the type of seed mix in the specification, but will not provide specific suppliers for the required seeding mix during the tender period. PCA and contractors have utilized numerous suppliers in Western Canada and the Northern US for seed supply for previous projects in Grasslands National Park, and should the successful bidder request contacts after the tender period, PCA will provide them.

Q5 The documents have a contradicting end date, is the project completion date July 31, 2019 or August 30, 2019?

A5 The correct completion date is August 30, 2019.

Q6 Is a certified cheque acceptable for the bond requirement?

A6 Yes, a certified cheque is an acceptable form of bid security.

Q7 Landscape Drawing L1.0 implies that we are to include a Gravel Roadway and some parking stalls at the new mechanical shed location, but L3.0 implies that we are to seed the entire area. There seems to be a contradiction between these two drawings – can you provide clarification on how we are to proceed with our pricing?

A7 The gravel roadway shown on Drawing L1.0 is not included in the scope of this project. The area excavated for construction is to be remediated with topsoil and seed and is shown on Drawing L2.0 and L3.0.

Q8 Are we to have any road building in our scope of work? If so, please clarify.

A8 No new road construction will be included in the scope of this project. Remediation and repair of existing facilities may be required due to construction methods and will not be measured for payment.

Q9 I also noticed that there are Sump Pit Manholes at both the Grey Water and the Black Water tanks, however the bid form only quantifies one to be installed. Please confirm if we are to carry pricing for one, or two man holes.

A9 The measurement and payment clauses for the Blackwater Tank and the Greywater Tank includes the cost of supply and installation of the manholes connected to those tanks.

The other manholes to be measured for payment as per the Unit Price Table are:

- 1, typical shallow manhole, downstream of the greywater tank, upstream of the first infiltration bed.
- 4, 900mm dia precast manholes (as part of the infiltration beds)
- 1, sump manhole, down stream of the last infiltration bed (downstream of bed 4)

Q10 In regards to the PEX SDR9 pipe and the curb stop. On drawing C1.0, it's showing a 65mm PEX pipe is needed and it should be connected to the curb stop of the same size. The problem is that the curb stop only goes up to 50mm (2") and the PEX pipe from Ipex only goes up to 2". I would like to know if its okay to work with 50mm and ignore the 65mm ipex pipe?

A10 It will be acceptable to supply and install the 50mm PEX pipe.

Q11 It seems somewhat confusing as what we are supposed to be doing with the main power feed to the mechanical bldg. It shows one small 100 amp panel with no main breaker in it. I believe the power feed to the bldg. are parallel 4c250 mcm cables which are impossible to terminate in a small panel such as this one. A service detail or at the least a single line drwg would clarify this. Please advise if this is a possibility

A11 Note 3 on Drawing C1.0 should read be "Water treatment building electrical cable to be 3c #3 TECK (CU) or 3c #1 ACWU (AL)." Main breaker is required for panel 4A as per panel schedule shown on drawing E5.0

All other terms and conditions remain unchanged.