

Part 1 General

1.1 DESCRIPTION OF WORK

- .1 In general, work under this contract consist of:
 - .1 Construction of a new Maintenance Facility that will consolidate all maintenance activities in one building.
 - .2 Demolition of the Coal Storage Building only after the new electrical infrastructure has been completed.
 - .3 New extensive electrical infrastructure work that will include a new diesel generator for the site and distribution to the new building and the existing buildings in the compound that will remain operational.
- .2 Site of Work is at: Fundy National Park, Alma, NB.

1.2 FAMILIARIZATION WITH SITE

- .1 Before submitting a bid, it is recommended that bidders visit the site to review and verify the form, nature and extent of the work, materials needed, the means of access and the temporary facilities required to perform the Work.
- .2 Obtain prior permission from the Departmental Representative before carrying out such site inspection.

1.3 CODES AND STANDARDS

- .1 Perform work in accordance with the 2015 National Building Code of Canada and any other code of provincial or local application, including all amendments up to bid closing date, provided that in any case of conflict or discrepancy, the more stringent requirement shall apply.
- .2 Materials and workmanship must meet or exceed requirements of specified standards, codes and referenced documents.

1.4 INTERPRETATION OF DOCUMENTS

- .1 Supplementary to the Order of Precedence article of the General Conditions of the Contract, the Division 01 sections take precedence over the technical specification sections in other Divisions of the Specification Manual.

1.5 TEAM ENGINEER

- .1 Unless specifically stated otherwise, the term Engineer where used in the Specifications and on the Drawings shall mean the Departmental Representative as defined in the General Conditions of the Contract

1.6 SETTING OUT WORK

- .1 Assume full responsibility for and execute complete layout of work to locations, lines and elevations indicated.

- .2 Provide devices needed to lay out and construct work.
- .3 Supply such devices as straight edges and templates required to facilitate Departmental Representative's inspection of work.
- .4 Supply stakes and other survey markers required for laying out work.

1.7 COST BREAKDOWN

- .1 Before submitting first progress claim submit breakdown of Contract price in detail as directed by Departmental Representative and aggregating contract price. Required forms will be provided for application of progress payment.
- .2 List items of work numerically following the same division/section number system of the specification manual and thereafter sub-divide into major work components and building systems as directed by Departmental Representative.
- .3 Upon approval, cost breakdown will be used as basis for progress payment.

1.8 DOCUMENTS REQUIRED

- .1 Maintain at job site, one copy each of the following:
 - .1 Contract Drawings
 - .2 Specifications
 - .3 Addenda
 - .4 Reviewed Shop Drawings
 - .5 List of outstanding shop drawings
 - .6 Change Orders
 - .7 Other modifications to Contract
 - .8 Field Test Reports
 - .9 Copy of Approved Work Schedule
 - .10 Health and Safety Plan and other safety related documents
 - .11 Other documents as stipulated elsewhere in the Contract Documents.

1.9 PERMITS

- .1 In accordance with the General Conditions, obtain and pay for building permit, certificates, licenses and other permits as required by municipal, provincial and federal authorities.
- .2 Provide appropriate notifications of project to municipal and provincial inspection authorities.
- .3 Obtain compliance certificates as prescribed by legislative and regulatory provisions of municipal, provincial and federal authorities as applicable to the performance of work.
- .4 Submit to Departmental Representative, copy of application forms and approval documents received from above referenced authorities.

1.10 ALTERATIONS, ADDITIONS OR REPAIRS TO EXISTING BUILDING

- .1 Execute work with least possible interference or disturbance to normal use of premises. Arrange with Departmental Representative to facilitate execution of work.

- .2 Where security has been reduced by work of Contract, provide temporary means to maintain security.
- .3 Provide temporary dust screens, barriers, warning signs in locations where renovation and alteration work is adjacent to areas which will be operative during such work.

1.11 ROUGHING-IN

- .1 Be responsible for obtaining manufacturer's literature and for correct roughing-in and hook-up of equipment, fixtures and appliances.

1.12 CUTTING, FITTING AND PATCHING

- .1 Ensure that cutting and patching required by all trades is included in total bid price submitted for the work.
- .2 Execute cutting including excavation, fitting and patching required to make work fit properly.
- .3 Where new work connects with existing and where existing work is altered, cut, patch and make good to match existing work. This includes patching of openings in existing work resulting from removal of existing services.
- .4 Do not cut, bore, or sleeve load-bearing members, except where specifically approved by Departmental Representative.
- .5 Make cuts with clean, true, smooth edges. Make patches inconspicuous in final assembly.
- .6 Fit work airtight to pipes, sleeves ducts and conduits.

1.13 CONCEALMENT

- .1 Conceal pipes, ducts and wiring in floor, wall and ceiling construction of finished areas except where indicated otherwise.

1.14 LOCATION OF FIXTURES

- .1 Location of equipment, fixtures and outlets, shown or specified shall be considered as approximate. Actual location shall be as required to suit conditions at time of installation and as is reasonable.
- .2 Locate equipment, fixtures and distribution systems to provide minimum interference and maximum usable space and in accordance with manufacturer's recommendations for safety, access and maintenance.
- .3 Inform Departmental Representative when impending installation conflicts with other new or existing components. Follow directives for actual location.
- .4 Submit field drawings to indicate relative position of various services and equipment when required by Departmental Representative.

1.15 EXISTING SERVICES

- .1 Where work involves breaking into or connecting to existing services, carry out work at times directed by governing authorities, with minimum of disturbance to operations.
- .2 Before commencing work, establish location and extent of service lines in area of work and notify Departmental Representative of findings.

- .3 Submit schedule to and obtain approval from Departmental Representative for any shut-down or closure of active service or facility. This includes disconnection of electrical power and communication services to tenant's operational areas. Adhere to approved schedule and provide notice to affected parties.
- .4 Provide temporary services when directed by Departmental Representative to maintain critical building and tenant systems.
- .5 Provide adequate bridging over trenches which cross sidewalks or roads to permit normal traffic.
- .6 Where unknown services are encountered, immediately advise Departmental Representative and confirm findings in writing.
- .7 Protect, relocate or maintain existing active services as required. When inactive services are encountered, cap off in manner approved by authorities having jurisdiction over service. Record locations of maintained, re-routed and abandoned service lines.

1.16 BILINGUAL NOTATIONS

- .1 Any items supplied and installed under this contract which have operating instructions on them such as door hardware, washroom accessories, push button activation controls powered hand dryers, mechanical equipment such as water coolers, etc., and which can be expected to be used by the building tenants, must have such operating instructions in bilingual format - English and French.
- .2 Factory embossed or recessed symbols illustrating equipment operation is an acceptable alternate to lettering.
- .3 Items supplied with factory - embossed or recessed lettering in one official language with an applied sticker or decal representing the second official language is not acceptable unless the Departmental Representative gives prior approval before any such items are ordered.
- .4 Internationally recognized colour coding such as red and blue center pieces for plumbing brass is acceptable.
- .5 No extra costs will be paid for re-stocking or re-ordering of materials and equipment due to Contractor's failure to fully meet bilingual signage requirements specified herein.
- .6 Ensure that all trades are made aware of above requirements.

1.17 BUILDING SMOKING ENVIRONMENT

- .1 Comply with smoking restrictions.

1.18 ASBESTOS DISCOVERY

- .1 Demolition of spray or trowel-applied asbestos can be hazardous to health. Should material resembling spray or trowel-applied asbestos be encountered in course of work, stop work and notify Departmental Representative immediately. Do not proceed with relevant work until written instructions have been received from Departmental Representative.

Part 2 Products

2.1 NOT USED

.1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION

Part 1 General

1.1 SUBMITTALS

- .1 Upon acceptance of bid and prior to commencement of work, submit to Departmental Representative the following work management documents:
 - .1 Work Schedule as specified herein.
 - .2 Shop Drawing Submittal Schedule specified in section 01 33 00
 - .3 Waste Management Plan specified in section 01 74 21
 - .4 Environmental Plan specified in section 01 35 43
 - .5 Health and Safety Plan specified in section 01 35 29
 - .6 Hot Work Procedures specified in section 01 35 24
 - .7 Lockout Procedures specified in section 01 35 25
 - .8 Dust Control Plan specified in section 01 50 00.
 - .9 List of workers requiring security clearance and those to be placed on Site Security Control list.

1.2 WORK SCHEDULE

- .1 Upon acceptance of bid submit:
 - .1 Preliminary work schedule within 7 calendar days of contract award.
 - .2 Detailed work schedule within 21 calendar days of contract award.
- .2 Schedule to indicate all calendar dates from commencement to completion of all work within the time stated in the accepted bid.
- .3 Provide sufficient details in preliminary schedule to clearly illustrate entire implementation plan, depicting efficient coordination of tasks and resources, to achieve completion of work on time and permit effective monitoring of work progress in relation to established milestones.
- .4 Preliminary work schedule content to include as a minimum the following:
 - .1 Bar (GANTT) Charts, indicating all work activities, tasks and other project elements, their anticipated durations, planned dates for achieving key activities and major project milestones supported with;
 - .2 Written narrative on key elements of work illustrated in bar chart, providing sufficient details to demonstrate a reasonable implementation plan for completion of project within designated time.
 - .3 Generally Bar Charts derived from commercially available computerized project management system are preferred but not mandatory.
- .5 Detailed Work Schedule:
 - .1 Prepare by use of Critical Path Method (CPM) indicating:
 - .1 Complete and detailed sequence of all construction activities. Show projected start and completion dates for each activity.

- .2 Number of calendar days required to carry out each activity.
- .3 Critical path items with resulting critical dates, non-critical activities and resulting float time.
- .4 Actual workdays from non-working days such as weekend and statutory days etc...
- .5 Projected and actual percentage of work completed for each major work activity.
- .2 Prepare CPM schedule by use of well recognized and widely used electronic software. Submit copy of schedule in paper format and one electronic version on diskette for each submission.
- .6 Work schedule must take into consideration and reflect the work phasing, required sequence of work, special conditions and operational restrictions as specified below and indicated on drawings.
- .7 Schedule work in cooperation with the Departmental Representative. Incorporate within Work Schedule, items identified by Departmental Representative during review of preliminary schedule.
- .8 Completed schedule shall be approved by Departmental Representative. When approved, take necessary measures to complete work within scheduled time. Do not change schedule without Departmental Representative's approval.
- .9 Ensure that all subtrades and subcontractors are made aware of the work restraints and operational restrictions specified.
- .10 Schedule Updates:
 - .1 Submit on a monthly basis.
 - .2 Provide information and pertinent details explaining reasons for necessary changes to implementation plan.
 - .3 Identify problem areas, anticipated delays, impact on schedule and proposed corrective measures to be taken.
- .11 Departmental Representative will make interim reviews and evaluate progress of work based on approved schedule. Frequency of such reviews will be as decided by Departmental Representative. Address and take corrective measures on items identified by reviews and as directed by Departmental Representative. Update schedule accordingly.
- .12 In every instance, change or deviation from the Work Schedule, no matter how minimal the risk or impact on safety or inconvenience to tenant or public might appear, will be subject to prior review and approval by the Departmental Representative.

1.3 PROJECT PHASING

- .1 Be aware that Facilities must be kept operational for the full duration of work of this contract. Building services to areas under use by tenants must also be maintained at all times during the Facility's operational hours and as specifically defined in this section.
- .2 Perform Work of this contract in three individual phases as indicated in the following sequence of activities:

- .1 Perform the electrical infrastructure upgrades necessary to ensure that the existing buildings may continue to operate during the following phases.
- .2 Demolish the existing Coal Storage Building.
- .3 Construct the new Maintenance Facility.
- .3 Unless indicated or approved otherwise, complete all work of a particular phase prior to commencement of another phase. Obtain Departmental Representative's permission prior to moving between phases.

1.4 OPERATIONAL RESTRICTIONS

- .1 The Contractor must recognize that the compound staff will be affected by implementation of this contract. The Contractor must perform the work with utmost regard to the safety and convenience of building occupants and users. All work activities must be planned and scheduled with this in mind. The Contractor will not be permitted to disturb any portion of the building without providing temporary facilities as necessary to ensure safe and direct passage through disturbed or otherwise affected areas.
- .2 Contractor to meet with the Departmental Representative on a weekly basis to identify intended work areas, activities and scheduling for the coming week.
- .3 To assure that construction work may proceed productively without risk to safety of building occupants and the public, be aware that certain work of this contract must be carried out during "Off-Hours".
- .4 Off Hours: means a period of time which is outside the daily operational hours of the tenants of the Facility. For the purposes of this contract, Off-Hours are defined as follows:
 - .1 Weeknight Off-Hours: between the hours of 18:00 and 07:00 for each weekday Monday to Thursday inclusive.
 - .2 Weekend Off-Hours: between the hours of 18:00 Friday evening to 07:00 Monday morning.
 - .3 Dependent on the nature and location of the construction activity and due to an unanticipated operational requirement of the Tenant, certain off-hour periods may be redefined by adjusting the start and end time periods or cancellation of a specific off-hour workshift during the course of the Work.
- .5 The following work may be performed during Off-Hours:
 - .1 Electrical infrastructure upgrades and tie-ins to existing building electrical distribution.
- .6 Departmental Representative reserves the right to stop certain daytime work activities, if the nature of that activity generates excessive noise or dust and have Contractor re-schedule that particular work to be performed during the Off-Hour period.
- .7 Ensure that all trades are aware of the "Off-Hour" requirements of this contract and ensure that any extra costs incurred as a result is included in the Contractor's bid price for the work. No extra cost will be paid due to failure by General Contractor or his sub-contractors to recognize the off-hour requirements and other restrictions specified herein and to include all necessary allowances within their bids.
- .8 Facility circulation maintained:

- .1 Ensure that the compound driveways and parking areas are maintained free and clear providing safe and uninterrupted passage for users at all times during the entire work.
 - .2 Maintain those areas clean and free of construction materials and equipment. Provide temporary dust barriers and other suitable enclosures to ensure users are not exposed to construction activities and are protected from exposure to dust, noise and hazardous conditions.
 - .3 Maintain fire escape routes accessible and firefighting access open all times for the duration of the project.
 - .4 Do not under any circumstances block fire exit doors. Do not leave construction materials or debris in corridors, stairwells building entrances and exits.
- .9 Safety Signage:
- .1 Provide onsite, and erect as required during progress of work, proper bilingual signage, mounted on self-supporting stands, warning the public and building occupants of construction activities in progress and alerting need to exercise caution in proceeding through disturbed areas of the facility, and directing building occupants through any detours which may be required.
 - .2 Signage to be professionally printed and mounted on wooden backing, coloured and to express messages as directed by the Departmental Representative.
 - .3 Generally maximum size of sign should be in the order of 1.0 square meters. Number of signs required will be dependent on number of areas in facility under renovation at any one time.
 - .4 Include costs for the supply and installation of these signs in the bid price.
- .10 Dust and Dirt Control:
- .1 Effectively plan and implement dust control measures and cleaning activities as an integral part of all construction activities. Review all measures with the Departmental Representative before undertaking work, especially for major dust generating activities.
 - .2 Do not allow demolition debris and construction waste to accumulate on site and contribute to the propagation of dust.
 - .3 As work progresses, maintain construction areas in a tidy condition at all times. Remove gross dust accumulations by cleaning following the completion of any major dust generating activity.
 - .4 Immediately remove all debris and dust from within occupied areas as generated by work therein during a given workshift.
 - .5 Disconnect and seal-off ductwork of HVAC servicing the construction area to stop spread of dust into other areas of Facility.
 - .6 Avoid situations and practises which results in dust and dirt being brought from the construction areas or from the exterior and tracked inside the building.
 - .7 Stop workers with soiled footwear from entering building. This includes roofing mechanics and heavy civil workers.
 - .8 Inform workers and make them sensitive to the need for dust and dirt control. Stringently enforce rules and regulations, immediately address non-compliance.

- .9 Keep access doors to work areas closed at all times. Use only designated doors for entry or egress.
- .11 Work in Occupied Areas:
 - .1 Where work must be carried out in an occupied area beyond the boundaries of the enclosed construction site, perform such work during the non-operational off-hour periods of the Facility.
 - .2 Ensure that all dust, dirt, debris, construction waste, materials, tools and equipment are completely removed at the end of each "off-hour" work shift. Clean and reinstate area ready for daytime use by tenant.
 - .3 Provide temporary dust barriers around immediate work areas and place fabric drop sheets over workstations, equipment and other furnishings located immediately adjacent to such work.
 - .4 Conduct work in such a way as to minimize the creation of dust and to avoid contaminating areas beyond the immediate location.
 - .5 Discuss and obtain Departmental Representative's approval beforehand on the type and extent of dust barriers, protective devices and measures needed.
 - .6 Be responsible for temporarily moving office furnishings, workstations, computer equipment and other objects as needed to gain access and conduct work. Reinstall all dislocated items at end of each workshift making the area operational again.
 - .7 Disconnect and reconnect any power and communications systems feeding workstations as required.
 - .8 Clean such areas as well as those corridors and routes used to gain entry and access.
- .12 Cleaning of tenant occupied areas used by Contractor:
 - .1 Clean lobbies, corridors, stairs and other circulation routes used by workers to gain access to work by conducting cleaning, vacuuming and washing of floors, walls and other soiled surfaces.
- .13 Ensure that all sub-trades are made aware of and abide by the contents of this section and in particular the work restrictions specified herein due to tenant operational requirements.

1.5 PROJECT MEETINGS

- .1 Schedule and administer project meetings, held on a minimum bi-weekly basis, for entire duration of work and more often when directed by Departmental Representative as deemed necessary due to progress of work or particular situation.
- .2 Prepare agenda for meetings.
- .3 Notify participants in writing 4 days in advance of meeting date.
 - .1 Ensure attendance of all subcontractors.
 - .2 Departmental Representative will provide list of other attendees to be notified.
- .4 Hold meetings at project site or where approved by Departmental Representative.
- .5 Preside at meetings and record minutes.

- .1 Indicate significant proceedings and decisions. Identify action items by parties.
- .2 Distribute to participants by mail or by facsimile within 3 calendar days after each meeting.
- .3 Make revisions as directed by Departmental Representative.
- .4 Departmental Representative will advise whether submission of minutes by Email is acceptable. Decision will be based on compatibility of software among participants.

1.6 WORK COORDINATION

- .1 The General Contractor is responsible for coordinating the work of the various trades and predetermining where the work of such trades interfaces with each other.
 - .1 Designate one person from own employ having overall responsibility to review contract documents and shop drawings, plan and manage such coordination.
- .2 The General Contractor shall convene meetings between trades whose work interfaces and ensure that they are fully aware of the areas and the extent of where interfacing is required.
 - .1 Provide each trade with the plans and specs of the interfacing trade, as required, to assist them in planning and carrying out their respective work.
 - .2 Develop coordination drawings when deemed required illustrating potential interference between works of various trades and distribute to all affected parties including structural trade.
 - .1 Pay particularly close attention to overhead work above ceilings and within or near to building structural elements.
 - .2 Coordination drawings to identify all building elements, services lines, rough-in points and indicate from where various services are coming.
 - .3 Review coordination drawings at purposely called meetings. Have subcontractors sign-off on drawings and publish minutes of each meeting.
 - .4 Plan and coordinate work in such a way to minimize quantity of service line offsets.
 - .5 Submit copy of coordination drawings and meeting minutes to Departmental Representative for information purposes.
- .3 Submission of shop drawings and ordering of prefabricated equipment or prebuilt components shall only occur once coordination meeting for such items has taken place between trades and all conditions affecting the work of the interfacing trades has been made known and accounted for.
- .4 Work Cooperation:
 - .1 Ensure cooperation between trades in order to facilitate the general progress of the work and avoid situations of spatial interference.
 - .2 Ensure that each trade provides all other trades reasonable opportunity for the completion of the work and in such a way as to prevent unnecessary delays, cutting, patching and the need to remove and replace completed work.
- .5 No extra costs to the Contract will be considered by the Departmental Representative as a result of Contractor's failure to effectively coordinate all portions of the Work. Disputes

between the various trades as a result of their not being informed of the areas and extent of interface work shall be the sole responsibility of the General Contractor to be resolved at own cost.

Part 2 Products

2.1 NOT USED

.1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION

| | | |
|---|---|--|
| PSPC Compound Maintenance Facility Project No: R.075814.001 | MATERIALS SUPPLIED BY DEPARTMENTAL REPRESENTATIVE | Section 01 16 10 Page 1 2016-07-22 |
|---|---|--|

Part 1 General

1.1 RELATED SECTIONS

- .1 The Departmental Representative will supply certain material and equipment in the Contract for installation and incorporation into the Work by the Contractor.

1.2 MATERIAL SUPPLIED

- .1 Departmental Representative will supply the following materials to the Contract:
 - .1 All existing wood working equipment being relocated from the existing carpentry shop.
- .2 The above noted items will be delivered and turned over to the Contractor at the site of work.

1.3 CONTRACTOR'S DUTIES

- .1 Take possession of the supplied material.
- .2 Promptly inspect delivered material. Report missing, damaged or defective items in writing to Departmental Representative in accordance with delivery requirements specified above.
- .3 Unload and handle at site, including lifting, uncrating etc...
- .4 Store material on site at a location approved by Departmental Representative. Protect against inclement weather and site damage by use of appropriate covers.
- .5 Be responsible for the protection of such material against damage, loss, theft and fire from date of receipt, loading, unloading, temporary storage and until final installation of work is accepted by the Departmental Representative.
- .6 Any damage or loss of such material shall result in the Contractor being responsible for replacement or repair of equipment at no additional cost to the Contract.
- .7 The decision as to whether damaged items may be repaired or must be replaced with new equipment shall be the Departmental Representative's decision.
- .8 Install such material and equipment and incorporate into the work. Perform assembly and make all connections as required to make item functional.
- .9 Dispose of containers, crating and protective covering as directed by the Departmental Representative.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION

Part 1 General

1.1 RELATED SECTIONS

- .1 Section 01 45 00 – Quality Control.
- .2 Section 01 78 00 – Closeout Submittals.

1.2 SUMITTAL GENERAL REQUIREMENTS

- .1 Submit to Departmental Representative for review requested submittals specified in various sections of the specifications including shop drawings, samples, permits, compliance certificates, test reports, work management plans and other data required as part of the work.
- .2 Submit with reasonable promptness and in orderly sequence to allow for Departmental Representative's review and not cause delay in Work. Failure to submit in ample time will not be considered sufficient reason for an extension of Contract time and no claim for extension by reason of such default will be allowed.
- .3 Do not proceed with work until relevant submissions have been reviewed.
- .4 Present shop drawings, product data, samples and mock-ups in SI Metric units.
- .5 Where items or information is not produced in SI Metric units, provide soft converted values.
- .6 Review submittals prior to submission. Ensure that necessary requirements have been determined and verified and that each submittal has been checked and co-ordinated with requirements of Work and Contract Documents.
 - .1 Submittals not stamped, signed, dated and identified as to specific project will be returned unexamined by Departmental Representative and considered rejected.
- .7 Verify field measurements and affected adjacent Work are coordinated.
- .8 Notify Departmental Representative, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .9 Contractor's responsibility for errors, omissions or deviations in submission from requirements of Contract Documents is not relieved by Departmental Representative's review.
- .10 Submittal format: paper originals, or alternatively clear and fully legible photocopies of originals. Facsimiles are not acceptable, except in special circumstances pre-approved by Departmental Representative. Poorly printed non-legible photocopies or facsimiles will not be accepted and be returned for resubmission.
- .11 Make changes or revision to submissions which Departmental Representative may require, consistent with Contract Documents and resubmit as directed by Departmental Representative. When resubmitting, identify in writing of any revisions other than those requested.
- .12 Keep one reviewed copy of each submittal document on site for duration of Work.

1.3 SHOP DRAWINGS AND PRODUCT DATA

- .1 The term "shop drawings" means fabrication drawings, erection drawings, diagrams, illustrations, schedules, performance charts, technical product data, brochures, specifications, test reports installation instructions and other data which are to be provided by Contractor to illustrate compliance with specified materials and details of a portion of work.
- .2 Shop Drawing Quantities: submit sufficient copies required by the General Contractor and sub-contractors plus 3 copies which will be retained by Departmental Representative.
 - .1 Ensure sufficient copies are submitted to enable one complete set to be included in each of the maintenance manuals specified in 01 78 00.
- .3 Shop Drawings Format:
 - .1 Opaque white prints or photocopies of original drawings or standard drawings modified to clearly illustrate work specific to project requirements. Maximum sheet size to be 1000 x 707 mm.
 - .2 Product Data from manufacturer's standard catalogue sheets, brochures, literature, performance charts and diagrams, used to illustrate standard manufactured products, to be original full colour brochures, clearly marked indicating applicable data and deleting information not applicable to project.
 - .3 Non or poorly legible drawings, photocopies or facsimiles will not be accepted and returned not reviewed.
- .4 Shop Drawings Content:
 - .1 Indicate materials, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of Work. Where items or equipment attach or connect to other items or equipment, confirm that all interrelated work has been coordinated, regardless of section or trade from which the adjacent work is being supplied and installed.
 - .2 Supplement manufacturer's standard drawings and literature with additional information to provide details applicable to project.
 - .3 Delete information not applicable to project on all submittals.
 - .4 Equipment installation/start-up data: include manufacturer's recommended installation instructions, pre-start and start-up checklists for those pieces of equipment and systems designated to be commissioned as specified in section 01 91 13.
 - .5 Allow 14 calendar days for Departmental Representative's review of each submission.
 - .6 Adjustments or corrections made on shop drawings by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, advise Departmental Representative in writing prior to proceeding with Work.
 - .7 If upon review by Departmental Representative, no errors or omissions are discovered or if only minor corrections and comments are made, fabrication and installation may proceed upon receipt of shop drawings. If shop drawings are rejected and noted to be resubmitted, do not proceed with that portion of work

until resubmission and review of corrected shop drawings, through same submission procedures indicated above.

- .8 Be advised that costs and expenses incurred by Departmental Representative to conduct more than one review of incorrectly prepared shop drawing submittal for a particular material, equipment or component of work may be assessed against the Contractor in the form of a financial holdback to the Contract.
- .9 Accompany each submission with transmittal letter, in duplicate, containing:
 - .1 Date.
 - .2 Project title and project number.
 - .3 Contractor's name and address.
 - .4 Identification and quantity of each shop drawing, product data and sample.
 - .5 Other pertinent data.
- .10 Submissions shall include:
 - .1 Date and revision dates.
 - .2 Project title and project number.
 - .3 Name and address of:
 - .1 Subcontractor.
 - .2 Supplier.
 - .3 Manufacturer.
 - .4 Contractor's stamp, signed by Contractor's authorized Representative certifying approval of submissions, verification of field measurements and compliance with Contract Documents.
 - .5 Cross references to details of contract drawings and specifications section number for which shop drawing submission addresses.
 - .6 Details of appropriate portions of Work as applicable:
 - .1 Fabrication.
 - .2 Layout, showing dimensions, including identified field dimensions, and clearances.
 - .3 Setting or erection details.
 - .4 Capacities.
 - .5 Performance characteristics.
 - .6 Standards.
 - .7 Operating weight.
 - .8 Wiring diagrams.
 - .9 Single line and schematic diagrams.
 - .10 Relationship to adjacent work.
- .12 After Departmental Representative's review, distribute copies.
- .13 The review of shop drawings by the Departmental Representative or by an authorized Consultant or designate is for sole purpose of ascertaining conformance with general concept. This review shall not mean that Canada

approves the detail design inherent in the shop drawings, responsibility for which shall remain with Contractor submitting same, and such review shall not relieve Contractor of responsibility for errors or omissions in shop drawings or of responsibility for meeting all requirements of the construction and Contract Documents. Without restricting generality of foregoing, Contractor is responsible for dimensions to be confirmed and correlated at job site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for co-ordination of Work of all sub-trades.

1.4 SAMPLES

- .1 Submit for review samples as specified in respective specification Sections. Label samples with origin and intended use.
- .2 Deliver samples to Departmental Representative's office or to other address as directed. Do not drop off samples at construction site except for pre-approved circumstances previously approved by Departmental Representative.
- .3 Notify Departmental Representative in writing, at time of submission of deviations in samples from requirements of Contract Documents.
- .4 Where colour, pattern or texture is criterion, submit full range of samples.
- .5 Adjustments made on samples by Departmental Representative are not intended to change Contract Price. If adjustments will result in a cost increase to the Contract notify Departmental Representative in writing prior to proceeding with Work.
- .6 Make changes in samples which Departmental Representative may require, consistent with Contract Documents.
- .7 Reviewed and accepted samples will become standard of workmanship and material against which installed Work will be verified.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 SECTION INCLUDES

- .1 Fire Safety Requirements
- .2 Hot Work Permit

1.2 RELATED WORK

- .1 Section 01 35 29 – Health and Safety Requirements.

1.3 REFERENCES

- .1 Fire Protection Standards issued by Fire Protection Services, Labour Program Division of Service Canada:
 - .1 FCC No. 301-June 1982 Standard for Construction Operations.
 - .2 FCC No. 302-June 1982 Standard for Welding and Cutting.
- .2 FCC standards may be viewed at:
 - .1 <http://www.hrsdc.gc.ca/en/lp/lo/fp/standards/commissioner.shtml>
 - .2 Fire Protection Services - Atlantic Region office, Halifax, N.S, Tel. (902) 426-6053.

1.4 DEFINITIONS

- .1 Hot Work defined as:
 - .1 Welding work
 - .2 Cutting of materials by use of torch or other open flame devices
 - .3 Grinding with equipment which produces sparks.
 - .4 Use of open flame torches such as for roofing work.

1.5 SUBMITTALS

- .1 Submit copy of Hot Work Procedures and sample of Hot Work permit to Departmental Representative for review, within 14 calendar days of acceptance of bid.
- .2 Submit in accordance with section 01 33 00.

1.6 FIRE SAFETY REQUIREMENTS

- .1 Implement and follow fire safety measures during Work. Comply with following:
 - .1 National Fire Code.
 - .2 Fire Protection Standards FCC 301 and FCC 302.
 - .3 Federal and Provincial Occupational Health and Safety Acts and Regulations.
- .2 In event of conflict between any provisions of above authorities the most stringent provision will apply. Should a dispute arise in determining the most stringent

requirement, Departmental Representative will advise on the course of action to be followed.

1.7 HOT WORK AUTHORIZATION

- .1 Obtain Departmental Representative's written "Authorization to Proceed" before conducting any form of Hot Work on site.
- .2 To obtain authorization submit to Departmental Representative:
 - .1 Contractor's typewritten Hot Work Procedures to be followed on site as specified below.
 - .2 Description of the type and frequency of Hot Work required.
 - .3 Sample Hot Work Permit to be used.
- .3 Upon review and confirmation that effective fire safety measures will be implemented and followed during performance of hot work, Departmental Representative will give authorization to proceed as follows:
 - .1 Issue one written "Authorization to Proceed" covering the entire project for duration of work or;
 - .2 Subdivide the work into pre-determined, individual activities, each activity requiring a separately written authorization to proceed.
- .4 Requirement for individual authorization will be based on:
 - .1 Nature or phasing of work;
 - .2 Risk to Facility operations;
 - .3 Quantity of various trades needing to perform hot work on project or;
 - .4 Other situation deemed necessary by Departmental Representative to ensure fire safety on premises.
- .5 Do not perform any Hot Work until receipt of Departmental Representative's written "Authorization to Proceed" for that portion of work.
- .6 In tenant occupied Facility, coordinate performance of Hot Work with Facility Manager through the Departmental Representative. When directed, perform Hot Work only during non-operative hours of the Facility. Follow Departmental Representative's directives in this regard.

1.8 HOT WORK PROCEDURES

- .1 Develop and implement safety procedures and work practices to be followed during the performance of Hot Work.
- .2 Hot Work Procedures to include:
 - .1 Requirement to perform hazard assessment of site and immediate work area beforehand for each hot work event in accordance with Safety Plan specified in section 01 35 29.
 - .2 Use of a Hot Work Permit system with individually issued permit by Contractor's Superintendent to worker or subcontractor granting permission to proceed with Hot Work.
 - .3 Permit required for each Hot Work event.

- .4 Designation of a person on site as a Fire Safety Watcher responsible to conduct a fire safety watch for a minimum duration of 30 minutes immediately following the completion of the Hot Work.
- .5 Compliance with fire safety codes, standards and occupational health and safety regulations specified.
- .6 Site specific rules and procedures in force at the site as provided by the Facility Manager.
- .3 Generic procedures, if used, must be edited and supplemented with pertinent information tailored to reflect specific project conditions. Label document as being the Hot Work Procedures for this contract.
- .4 Procedures shall clearly establish responsibilities of:
 - .1 Worker performing hot work,
 - .2 Person issuing the Hot Work Permit,
 - .3 Fire Safety Watcher,
 - .4 Subcontractor(s) and Contractor.
- .5 Brief all workers and subcontractors on Hot Work Procedures and of Permit system. Stringently enforce compliance.

1.9 HOT WORK PERMIT

- .1 Hot Work Permit to include the following:
 - .1 Project name and project number;
 - .2 Building name and specific room or area where hot work will be performed;
 - .3 Date of issue;
 - .4 Description of hot work type needed;
 - .5 Special precautions to be followed, including type of fire extinguisher needed;
 - .6 Name and signature of permit issuer.
 - .7 Name of worker to which the permit is issued.
 - .8 Permit validity period not to exceed 8 hours. Indicate start time/date and termination time/date.
 - .9 Worker's signature with time/date of hot work completion.
 - .10 Stipulated time period of safety watch.
 - .11 Fire Safety Watcher's signature with time/date.
- .2 Permit to be typewritten form. Industry Standard forms shall only be used if all data specified above is included on form.
- .3 Each Hot Work Permit to be completed in full, signed and returned to Contractor's Superintendent for safe keeping on site.

1.10 DOCUMENTS ON SITE

- .1 Keep Hot Work Permits and Hazard assessment documentation on site for duration of Work.

- .2 Upon request, make available to Departmental Representative or to authorized safety Representative for inspection.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 SECTION INCLUDES

- .1 Procedures to isolate and lockout electrical facility and other equipment from energy sources.

1.2 RELATED WORK

- .1 Section 01 35 29 – Health and Safety Requirements.

1.3 REFERENCES

- .1 CSA C22.1-15 - Canadian Electrical Code, Part 1, Safety Standard for Electrical Installations.
- .2 CAN/CSA C22.3 No.1-15 - Overhead Systems.
- .3 CSA C22.3 No.7-15 - Underground Systems.
- .4 COSH: Canada Occupational Health and Safety Regulations made under Part II of the Canada Labour Code.

1.4 DEFINITIONS

- .1 Electrical Facility: means any system, equipment, device, apparatus, wiring, conductor, assembly or part thereof that is used for the generation, transformation, transmission, distribution, storage, control, measurement or utilization of electrical energy, and that has an amperage and voltage that is dangerous to persons.
- .2 Guarantee of Isolation: means a guarantee by a competent person in control or in charge that a particular facility or equipment has been isolated.
- .3 De-energize: in the electrical sense, that a piece of equipment is isolated and grounded, e.g. if the equipment is not grounded, it cannot be considered de-energized (DEAD).
- .4 Guarded: means that an equipment or facility is covered, shielded, fenced, enclosed, inaccessible by location, or otherwise protected in a manner that, to the extent that is reasonably practicable, will prevent or reduce danger to any person who might touch or go near such item.
- .5 Isolate: means that an electrical facility, mechanical equipment or machinery is separated or disconnected from every source of electrical, mechanical, hydraulic, pneumatic or other kind of energy that is capable of making it dangerous.
- .6 Live/alive: means that an electrical facility produces, contains, stores or is electrically connected to a source of alternating or direct current of an amperage and voltage that is dangerous or contains any hydraulic, pneumatic or other kind of energy that is capable of making the facility dangerous to persons.

1.5 COMPLIANCE REQUIREMENTS

- .1 Comply with the following in regards to isolation and lockout of electrical facilities and equipment:

- .1 Canadian Electrical Code
- .2 Federal and Provincial Occupational Health and Safety Acts and Regulations.
- .3 Regulations and code of practice as applicable to mechanical equipment or other machinery being de-energized.
- .4 Procedures specified herein.
- .2 In event of conflict between any provisions of above authorities the most stringent provision will apply

1.6 SUBMITTALS

- .1 Submit copy of lockout procedures, sample of lockout permit and lockout tags proposed for use in accordance with Section 01 33 00. Submit within 14 calendar days of acceptance of bid.

1.7 ISOLATION OF EXISTING SERVICES

- .1 Obtain Departmental Representative's written authorization prior to working on existing live or active electrical facilities and equipment and before proceeding with isolation of such item.
- .2 To obtain authorization, submit to Departmental Representative the following documentation:
 - .1 Written request to isolate the particular service or facility and;
 - .2 Copy of Contractor's Lockout Procedures.
- .3 Make a Request for Isolation for each event, unless directed otherwise by Departmental Representative, as follows:
 - .1 Fill-out standard form in current use at the Facility as provided by Departmental Representative or;
 - .2 Where no form exists, make written request indicating:
 - .1 The equipment, system or service to be isolated and its location;
 - .2 Duration of isolation period (i.e.: start time & date and completion time & date).
 - .3 Voltage of service feed to system or equipment being isolated.
 - .4 Name of person making the request.
- .4 Do not proceed with isolation until receipt of written notification from Departmental Representative granting the Isolation Request and authorizing to proceed with the work.
 - .1 Note that Departmental Representative may designate another person at the Facility being authorized to grant the Isolation Request.
- .5 Conduct safe, orderly shutdown of equipment or facility. De-energize, isolate and lockout power and other sources of energy feeding the equipment or facility.
- .6 Determine in advance, as much as possible, in cooperation with the Departmental Representative, the type and frequency of situations which will require isolation of existing services.

- .7 Plan and schedule shut down of existing services in consultation with the Departmental Representative and the Facility Manager. Minimize impact and downtime of Facility operations. Follow Departmental Representative's directives in this regard.
- .8 Conduct hazard assessment as part of the process in accordance with health and safety requirements specified Section 01 35 29.

1.8 LOCKOUTS

- .1 De-energize, isolate and lockout electrical facility, mechanical equipment and machinery from all potential sources of energy prior to working on such items.
- .2 Develop and implement clear and specific lockout procedures to be followed as part of the Work.
- .3 Prepare typed written Lockout Procedures describing safe work practices, procedures, worker responsibilities and sequence of activities to be followed on site by workforce to safely isolate an active piece of equipment or electrical facility and effectively lockout and tagout it's sources of energy.
- .4 Include as part of the Lockout Procedures a system of lockout permits managed by Contractor's Superintendent or other qualified person designated by him/her as being "in-charge" at the site.
 - .1 A lockout permit shall be issued to specific worker providing a Guarantee of Isolation before each event when work must be performed on a live equipment or electrical facility.
 - .2 Duties of person managing the permit system to include:
 - .1 Issuance of permits and lockout tags to workers.
 - .2 Determining permit duration.
 - .3 Maintaining record of permits and tags issued.
 - .4 Making a Request for Isolation to Departmental Representative when required as specified above.
 - .5 Designating a Safety Watcher, when one is required based on type of work.
 - .6 Ensuring equipment or facility has been properly isolated.
 - .7 Collecting and safekeeping lockout tags returned by workers as a record of the event.
- .5 Clearly establish, describe and allocate responsibilities of:
 - .1 Workers.
 - .2 Person managing the lockout permit system.
 - .3 Safety Watcher.
 - .4 Subcontractor(s) and General Contractor.
- .6 Generic procedures, if used, must be edited and supplemented with pertinent information to reflect specific project requirements.
 - .1 Incorporate site specific rules and procedures in force at site as provided by Facility Manager through the Departmental Representative.

- .2 Clearly label the document as being the Lockout procedures applicable to work of this contract.
 - .7 Use energy isolation lockout devices specifically designed and appropriate for type of facility or equipment being locked out.
 - .8 Use industry standard lockout tags.
 - .9 Provide appropriate safety grounding and guards as required
- 1.9 CONFORMANCE**
 - .1 Brief all workers and subcontractors on requirements of this section. Stringently enforce use and compliance.
- 1.10 DOCUMENTS ON SITE**
 - .1 Post Lockout Procedures on site in common location for viewing by workers.
 - .2 Keep copies of Request for Isolation forms and lockout permits and tags issued to workers on site for full duration of Work.
 - .3 Upon request, make available to Departmental Representative or to authorized safety Representative for inspection.
- Part 2 Products**
- 2.1 NOT USED**
 - .1 Not Used.
- Part 3 Execution**
- 3.1 NOT USED**
 - .1 Not Used.

END OF SECTION

Part 1 General

1.1 RELATED WORK

- .1 Section 01 35 24 – Special procedures on Fire Safety Requirements.
- .2 Section 01 35 25 – Special Procedures on Lockout Requirements.

1.2 DEFINITIONS

- .1 COSH: Canada Occupational Health and Safety Regulations made under Part II of the Canada Labour Code.
- .2 Competent Person: means a person who is:
 - .1 Qualified by virtue of personal knowledge, training and experience to perform assigned work in a manner that will ensure the health and safety of persons in the workplace, and;
 - .2 Knowledgeable about the provisions of occupational health and safety statutes and regulations that apply to the Work and;
 - .3 Knowledgeable about potential or actual danger to health or safety associated with the Work.
 - .4 Medical Aid Injury: any minor injury for which medical treatment was provided and the cost of which is covered by Workers' Compensation Board of the province in which the injury was incurred.
 - .5 PPE: personal protective equipment
 - .6 Work Site: where used in this section shall mean areas, located at the premises where Work is undertaken, used by Contractor to perform all of the activities associated with the performance of the Work.

1.3 SUBMITTALS

- .1 Make submittals in accordance with Section 01 33 00.
- .2 Submit site-specific Health and Safety Plan prior to commencement of Work.
 - .1 Submit within 5 work days of notification of Bid Acceptance. Provide 3 copies.
 - .2 Departmental Representative will review Health and Safety Plan and provide comments.
 - .3 Revise the Plan as appropriate and resubmit within 5 work days after receipt of comments.
 - .4 Departmental Representative's review and comments made of the Plan shall not be construed as an endorsement, approval or implied warranty of any kind by Canada and does not reduce Contractor's overall responsibility for Occupational Health and Safety of the Work.
 - .5 Submit revisions and updates made to the Plan during the course of Work.
- .3 Submit name of designated Health & Safety Site Representative and support documentation specified in the Safety Plan.
- .4 Submit building permit, compliance certificates and other permits obtained.

- .5 Submit copy of Letter in Good Standing from Provincial Workers Compensation or other department of labour organization.
 - .1 Submit update of Letter of Good Standing whenever expiration date occurs during the period of Work.
- .6 Submit copies of reports or directions issued by Federal, Provincial and Territorial health and safety inspectors.
- .7 Submit copies of incident reports.
- .8 Submit WHMIS MSDS - Material Safety Data Sheets.

1.4 COMPLIANCE REQUIREMENTS

- .1 Comply with Occupational Health and Safety Act for Province of New Brunswick, and General Regulations made pursuant to the Act.
- .2 Comply with Canada Labour Code - Part II (entitled Occupational Health and Safety) and the Canada Occupational Health and Safety Regulations (COSH) as well as any other regulations made pursuant to the Act.
 - .1 The Canada Labour Code can be viewed at: [www.http://laws.justice.gc.ca/en/L-2/](http://laws.justice.gc.ca/en/L-2/)
 - .2 COSH can be viewed at: [www.http://laws.justice.gc.ca/eng/SOR-86-304/ ne.html](http://laws.justice.gc.ca/eng/SOR-86-304/ne.html)
 - .3 A copy may be obtained at: Canadian Government Publishing Public Works & Government Services Canada Ottawa, Ontario, K1A 0S9 Tel: (819) 956-4800 (1-800-635-7943) Publication No. L31-85/2000 E or F)
- .3 Observe construction safety measures of:
 - .1 Part 8 of National Building Code
 - .2 Municipal by-laws and ordinances.
- .4 In case of conflict or discrepancy between above specified requirements, the more stringent shall apply.
- .5 Maintain Workers Compensation Coverage in good standing for duration of Contract. Provide proof of clearance through submission of Letter in Good Standing.
- .6 Medical Surveillance: Where prescribed by legislation or regulation, obtain and maintain worker medical surveillance documentation.

1.5 RESPONSIBILITY

- .1 Be responsible for health and safety of persons on site, safety of property on site and for protection of persons and environment adjacent to the site to extent that they may be affected by conduct of Work.
- .2 Comply with and enforce compliance by all workers, sub-contractors and other persons granted access to Work Site with safety requirements of Contract Documents, applicable federal, provincial, and local by-laws, regulations, and ordinances, and with site-specific Health and Safety Plan.

1.6 SITE CONTROL AND ACCES

- .1 Control the Work and entry points to Work Site. Approve and grant access only to workers and authorized persons. Immediately stop and remove non-authorized persons.
 - .1 Departmental Representative will provide names of those persons authorized by Departmental Representative to enter onto Work Site and will ensure that such authorized persons have the required knowledge and training on Health and Safety pertinent to their reason for being at the site, however, Contractor remains responsible for the health and safety of authorized persons while at the Work Site.
- .2 Isolate Work Site from other areas of the premises by use of appropriate means.
 - .1 Erect fences, hoarding, barricades and temporary lighting as required to effectively delineate the Work Site, stop non-authorized entry, and to protect pedestrians and vehicular traffic around and adjacent to the Work and create a safe environment. See Section 01 50 00 for minimum acceptable requirements.
 - .2 Post signage at entry points and other strategic locations indicating restricted access and conditions for access.
 - .3 Use professionally made signs with bilingual message in the 2 official languages or international known graphic symbols.
- .3 Provide safety orientation session to persons granted access to Work Site. Advise of hazards and safety rules to be observed while on site.
- .4 Ensure persons granted site access wear appropriate PPE. Supply PPE to inspection authorities who require access to conduct tests or perform inspections.
- .5 Secure Work Site against entry when inactive or unoccupied and to protect persons against harm. Provide security guard where adequate protection cannot be achieved by other means.

1.7 PROTECTION

- .1 Give precedence to safety and health of persons and protection of environment over cost and schedule considerations for Work.
- .2 Should unforeseen or peculiar safety related hazard or condition become evident during performance of Work, immediately take measures to rectify situation and prevent damage or harm. Advise Departmental Representative verbally and in writing.

1.8 FILING OF NOTICE

- .1 File Notice of Project with pertinent provincial health and safety authorities prior to beginning of Work.
 - .1 Departmental Representative will assist in locating address if needed.

1.9 PERMITS

- .1 Post permits, licenses and compliance certificates, specified in section 01 10 10, at Work Site.

- .2 Where a particular permit or compliance certificate cannot be obtained, notify Departmental Representative in writing and obtain approval to proceed before carrying out applicable portion of work.

1.10 HAZZARD ASSESSMENTS

- .1 Perform site specific health and safety hazard assessment of the Work and its site.
- .2 Carryout initial assessment prior to commencement of Work with further assessments as needed during progress of work, including when new trades and subcontractors arrive on site.
- .3 Record results and address in Health and Safety Plan.
- .4 Keep documentation on site for entire duration of the Work.

1.11 PROJECT/SITE CONDITIONS

- .1 Following are potential health, environmental and safety hazards at the site for which Work may involve contact with:
 - .1 Existing hazardous and controlled products stored on site
 - .2 Existing hazardous substances or contaminated materials
- .2 Above items shall not be construed as being complete and inclusive of potential health and safety hazards encountered during Work.
- .3 Include above items in the hazard assessment of the Work.
- .4 MSDS Data sheets of pertinent hazardous and controlled products stored on site can be obtained from Departmental Representative.

1.12 MEETINGS

- .1 Attend pre-construction health and safety meeting, convened and chaired by Departmental Representative, prior to commencement of Work, at time, date and location determined by Departmental Representative. Ensure attendance of:
 - .1 Superintendent of Work
 - .2 Designated Health & Safety Site Representative
 - .3 Subcontractors
- .2 Conduct regularly scheduled tool box and safety meetings during the Work in conformance with Occupational Health and Safety regulations.
- .3 Keep documents on site.

1.13 HEALTH AND SAFETY PLAN

- .1 Prior to commencement of Work, develop written Health and Safety Plan specific to the Work. Implement, maintain, and enforce Plan for entire duration of Work and until final demobilization from site.
- .2 Health and Safety Plan shall include the following components:
 - .1 List of health risks and safety hazards identified by hazard assessment.
 - .2 Control measures used to mitigate risks and hazards identified.

- .3 On-site Contingency and Emergency Response Plan as specified below.
- .4 On-site Communication Plan as specified below.
- .5 Name of Contractor's designated Health & Safety Site Representative and information showing proof of his/her competence and reporting relationship in Contractor's company.
- .6 Names, competence and reporting relationship of other supervisory personnel used in the Work for occupational health and safety purposes.
- .3 On-site Contingency and Emergency Response Plan shall include:
 - .1 Operational procedures, evacuation measures and communication process to be implemented in the event of an emergency.
 - .2 Evacuation Plan: site and floor plan layouts showing escape routes, marshalling areas. Details on alarm notification methods, fire drills, location of firefighting equipment and other related data.
 - .3 Name, duties and responsibilities of persons designated as Emergency Warden(s) and deputies.
 - .4 Emergency Contacts: name and telephone number of officials from:
 - .1 General Contractor and subcontractors.
 - .2 Pertinent Federal and Provincial Departments and Authorities having jurisdiction.
 - .3 Local emergency resource organizations.
 - .5 Harmonize Plan with Facility's Emergency Response and Evacuation Plan. Departmental Representative will provide pertinent data including name of PWGSC and Facility Management contacts.
- .4 On-site Communication Plan:
 - .1 Procedures for sharing of work related safety information to workers and subcontractors, including emergency and evacuation measures.
 - .2 List of critical work activities to be communicated with Facility Manager which have a risk of endangering health and safety of Facility users.
- .5 Address all activities of the Work including those of subcontractors.
- .6 Review Health and Safety Plan regularly during the Work. Update as conditions warrant to address emerging risks and hazards, such as whenever new trade or subcontractor arrive at Work Site.
- .7 Departmental Representative will respond in writing, where deficiencies or concerns are noted and may request re-submission of the Plan with correction of deficiencies or concerns.
- .8 Post copy of the Plan, and updates, prominently on Work Site.

1.14 SAFETY SUPERVISION

- .1 Employ Health & Safety Site Representative responsible for daily supervision of health and safety of the Work.
- .2 Health & Safety Site Representative may be the Superintendent of the Work or other person designated by Contractor and shall be assigned the responsibility and authority to:

- .1 Implement, monitor and enforce daily compliance with health and safety requirements of the Work
- .2 Monitor and enforce Contractor's site-specific Health and Safety Plan.
- .3 Conduct site safety orientation session to persons granted access to Work Site.
- .4 Ensure that persons allowed site access are knowledgeable and trained in health and safety pertinent to their activities at the site or are escorted by a competent person while on the Work Site.
- .5 Stop the Work as deemed necessary for reasons of health and safety.
- .3 Health & Safety Site Representative must:
 - .1 Be qualified and competent person in occupational health and safety.
 - .2 Have site-related working experience specific to activities of the Work.
 - .3 Be on Work Site at all times during execution of the Work.
- .4 All supervisory personnel assigned to the Work shall also be competent persons.
- .5 Inspections:
 - .1 Conduct regularly scheduled safety inspections of the Work on a minimum bi-weekly basis. Record deficiencies and remedial action taken.
- .6 Cooperate with Facility's Occupational Health and Safety representative should one be designated by Departmental Representative.
- .7 Keep inspection reports and supervision related documentation on site.

1.15 TRAINING

- .1 Use only skilled workers on Work Site who are effectively trained in occupational health and safety procedures and practices pertinent to their assigned task.
- .2 Maintain employee records and evidence of training received. Make data available to Departmental Representative upon request.
- .3 When unforeseen or peculiar safety-related hazard, or condition occur during performance of Work, follow procedures in place for Employee's Right to Refuse Work in accordance with Acts and Regulations of Province having jurisdiction and advise Departmental Representative verbally and in writing.

1.16 MINIMUM SITE SAFETY RULES

- .1 Notwithstanding requirement to abide by federal and provincial health and safety regulations; ensure the following minimum safety rules are obeyed by persons granted access to Work Site:
 - .1 Wear appropriate PPE pertinent to the Work or assigned task; minimum being hard hat, safety footwear, safety glasses and hearing protection.
 - .2 Immediately report unsafe condition at site, near-miss accident, injury and damage.
 - .3 Maintain site and storage areas in a tidy condition free of hazards causing injury.
 - .4 Obey warning signs and safety tags.
- .2 Brief persons of disciplinary protocols to be taken for non-compliance. Post rules on site.

1.17 CORRECTION OF NON-COMPLIANCE

- .1 Immediately address health and safety non-compliance issues identified by authority having jurisdiction or by Departmental Representative.
- .2 Provide Departmental Representative with written report of action taken to correct non-compliance of health and safety issues identified.
- .3 Departmental Representative will stop Work if non-compliance of health and safety regulations is not corrected in a timely manner.

1.18 INCIDENT REPORTING

- .1 Investigate and report the following incidents to Departmental Representative:
 - .1 Incidents requiring notification to Provincial Department of Occupational Safety and Health, Workers Compensation Board or to other regulatory Agency.
 - .2 Medical aid injuries.
 - .3 Property damage in excess of \$10,000.00,
 - .4 Interruptions to Facility operations resulting in an operational lost to a Federal department in excess of \$5000.00.
- .2 Submit report in writing.

1.19 HAZARDOUS PRODUCTS

- .1 Comply with requirements of Workplace Hazardous Materials Information System (WHMIS).
- .2 Keep MSDS data sheets for all products delivered to site.
 - .1 Post on site.
 - .2 Submit copy to Departmental Representative.

1.20 BLASTING

- .1 Blasting or other use of explosives is not permitted on site without prior receipt of written permission and instructions from Departmental Representative.

1.21 POWDER ACTUATED DEVICES

- .1 Use powder actuated fastening devices only after receipt of written permission from Departmental Representative.

1.22 CONFINED SPACES

- .1 Abide by occupational health and safety regulations regarding work in confined spaces.

1.23 SITE RECORDS

- .1 Maintain on Work Site copy of safety related documentation and reports stipulated to be produced in compliance with Acts and Regulations of authorities having jurisdiction and of those documents specified herein.
- .2 Upon request, make available to Departmental Representative or authorized Safety Officer for inspection.

1.24 POSTING OF DOCUMENTS

- .1 Ensure applicable items, articles, notices and orders are posted in conspicuous location on Work Site in accordance with Acts and Regulations of Province having jurisdiction.
- .2 Post other documents as specified herein, including:
 - .1 Site specific Health and Safety Plan
 - .2 WHMIS data sheets

Part 2 Products

2.1 NOT USED

- .1 Not used.

Part 3 Execution

3.1 NOT USED

- .1 Not used.

END OF SECTION

Part 1 General

1.1 RELATED WORK

- .1 Section 01 74 22 – Waste Management and Disposal.

1.2 DEFINITIONS

- .1 Hazardous Material: Product, substance, or organism that is used for its original purpose; and that is either dangerous goods or a material that may cause adverse impact to the environment or adversely affect health of persons, animals, or plant life when released into the environment.

1.3 FIRES

- .1 Fires and burning of rubbish on site not permitted.

1.4 HAZARDOUS MATERIAL HANDLING

- .1 Store and handle hazardous materials in accordance with applicable federal and provincial laws, regulations, codes and guidelines. Store in location that will prevent spillage into the environment
- .2 Label containers to WHMIS requirements and keep MSDS data sheets on site for all hazardous materials.
- .3 Maintain inventory of hazardous materials and hazardous waste stored on site. List items by product name, quantity and date when storage began.
- .4 Store and handle flammable and combustible materials in accordance with National Fire Code.
- .5 Transport hazardous materials in accordance with federal Transportation of Dangerous Goods Regulations and applicable Provincial regulations.

1.5 DISPOSAL OF WASTES

- .1 Do not bury rubbish and waste materials on site. Dispose in accordance with project waste management requirements specified in section 01 74 22.
- .2 Do not dispose of hazardous waste or volatile materials, such as mineral spirits, paints, thinners, oil or fuel into waterways, storm or sanitary sewers or waste landfill sites.
- .3 Dispose of hazardous waste in accordance with applicable federal and provincial laws, regulations, codes and guidelines.

1.6 DRAINAGE

- .1 Provide temporary drainage and pumping as necessary to keep excavations and site free from water.
- .2 Do not pump water containing suspended materials into waterways, sewer or drainage systems.
- .3 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with governing regulations and requirements.

- .4 Provide control devices such as filter fabrics, sediment traps and settling ponds to control drainage and prevent erosion of adjacent lands. Maintain in good order for duration of work.

1.7 SITE AND PLANT PROTECTION

- .1 Protect trees and plants on site and adjacent properties where indicated.
- .2 Wrap in burlap, trees and shrubs adjacent to construction work, storage areas and trucking lanes, and encase with protective wood framework from grade level to height of 2 m.
- .3 Protect roots of designated trees to dripline during excavation and site grading to prevent disturbance or damage. Avoid unnecessary traffic, dumping and storage of materials over root zones.
- .4 Minimize stripping of topsoil and vegetation.
- .5 Restrict tree removal to areas indicated or designated by Departmental Representative.

1.8 POLLUTION CONTROL

- .1 Maintain temporary erosion and pollution control features installed under this contract.
- .2 Control emissions from equipment and plant to local authorities' emission requirements.
- .3 Prevent sandblasting and other extraneous materials from contaminating air beyond application area, by providing temporary enclosures.
- .4 Cover or wet down dry materials and rubbish to prevent blowing dust and debris. Provide dust control for temporary roads and around entire construction site.
- .5 Have appropriate emergency spill response equipment and rapid clean-up kit on site located adjacent to hazardous materials storage area. Provide personal protective equipment required for clean-up.
- .6 Report, spills of petroleum and other hazardous materials as well as accidents having potential of polluting the environment to Federal and Provincial Department of the Environment.
 - .1 Notify Departmental Representative and submit a written spill report to Departmental Representative within 24 hours of occurrence.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 INSPECTION

- .1 Give timely notice requesting inspection of Work designated for special tests, inspections or approvals by Departmental Representative or by inspection authorities having jurisdiction.
- .2 In accordance with the General Conditions, Departmental Representative may order any part of Work to be examined if Work is suspected to be not in accordance with Contract Documents.
- .3 If Contractor covers or permits to be covered Work designated for special tests, inspections or approvals before such is made, uncover Work until particular inspections or tests have been fully and satisfactorily completed and until such time as Departmental Representative gives permission to proceed.
- .4 Pay costs to uncover and make good work disturbed by inspections and tests.

1.2 TESTING

- .1 Tests on materials, equipment and building systems as specified in various sections of the Specifications is the responsibility of the Contractor except where stipulated otherwise.
 - .1 Provide all necessary instruments, equipment and qualified personnel to perform tests.
- .2 At completion of tests, turn over 2 sets of fully documented tests reports to the Departmental Representative. Submit in accordance with Section 01 33 00.
 - .1 Obtain additional copies for inclusion of a complete set in each of the maintenance manuals specified in Section 01 78 00.
- .3 Unspecified tests may also be made by Departmental Representative, at the discretion of the Departmental Representative. The costs of these tests will be paid for by the Departmental Representative.
- .4 Where tests or inspections reveal work not in accordance with contract requirements, Contractor shall pay costs for additional tests and inspections incurred by Departmental Representative as required to verify acceptability of corrected work.

1.3 INDEPENDENT INSPECTION AGENCIES

- .1 Departmental Representative will engage and pay for service of Independent Inspection and Testing Agencies for purpose of inspecting and testing portions of Work except for the following which remain part of Contractor's responsibilities:
 - .1 Inspection and testing required by laws, ordinances, rules, regulations or orders of public authorities.
 - .2 Inspection and testing performed exclusively for Contractor's convenience.
 - .3 Testing, adjustment and balancing of mechanical and electrical equipment and other building systems.

- .4 Performance verification tests before building commissioning procedures commences.
- .5 Mill tests and certificates of compliance.
- .6 Tests as specified within various sections designated to be carried out by Contractor under the supervision of Departmental Representative.
- .7 Additional tests as specified in Clause 1.2.4 above.
- .2 Provide sufficient advance notice to Departmental Representative of time when the Work will be ready for testing by designated Testing Agency in order for Departmental Representative to make attendance arrangements with such Agency. When directed by Departmental Representative notify the Agency directly.
- .3 When specified or directed, submit Representative samples of materials, in required quantities, to Testing Agency for testing purposes. Submit with reasonable promptness and in an orderly sequence so as not to cause delay in Work.
- .4 Provide labour and facilities to obtain, handle and deliver samples.
- .5 Provide sufficient space on site for Testing Agency's exclusive use to store equipment and cure test samples.
- .6 Employment of Independent Inspection and Testing Agencies by Departmental Representative does not relax responsibility to perform Work in accordance with Contract Documents.

1.4 ACCESS TO WORK

- .1 Facilitate Departmental Representative's access to Work. If part of Work is being fabricated at locations other than construction site, make preparations to allow access to such Work whenever it is in progress.
- .2 Furnish labour and facility to provide access to the work being inspected and tested.
- .3 Co-operate to facilitate such inspections and tests.

1.5 REJECTED WORK

- .1 Remove and replace defective Work, whether result of poor workmanship, use of defective or damaged products and whether incorporated in Work or not, which has been identified by Departmental Representative as failing to conform to Contract Documents.
- .2 Make good damages to new and existing construction and finishes resulting from removal or replacement of defective work.

1.6 MOCK-UPS

- .1 Prepare mock-ups of certain work as specified in various sections of the Specifications. Include in each mock-up all related work components representative of final assembly.
- .2 Construct in locations acceptable to Departmental Representative.
- .3 Prepare mock-ups for Departmental Representative's review with reasonable promptness and in an orderly sequence, so as not to cause any delay in Work.

- .4 Failure to prepare mock-ups in ample time is not considered sufficient reason for an extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .5 If requested, Departmental Representative will assist in preparing a schedule fixing dates for preparation.
- .6 Dismantle and remove mock-up when directed by Departmental Representative, unless approval is given for mock-up to remain as part of the Work.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 SITE ACCESS AND PARKING

- .1 The Departmental Representative will designate Contractor's access to project site as well as parking facilities for equipment and workers.
- .2 Maintain existing roads and parking areas at site, where used by Contractor, for duration of contract.
 - .1 Keep clean and free of mud and dirt by washing on a regular basis.
 - .2 Provide snow removal in areas located within construction site or enclosed by work.
 - .3 Make good and repair damage resulting from Contractor's use of existing roads, asphalted areas and lawns on site.

1.2 BUILDING ACCESS

- .1 Use only access doors, and circulation routes within building as designated by Departmental Representative to access interior work

1.3 CONTRACTOR'S SITE OFFICE

- .1 Be responsible for and provide own site office, including electricity, heat, lights and telephone. Locate site office as directed by Departmental Representative.

1.4 MATERIAL STORAGE

- .1 Locate site storage trailers where indicated on drawings or where directed by Departmental Representative. Place in location of least interference with existing Facility operations.

1.5 SITE ENCLOSURES

- .1 Provide temporary fence to enclose various construction areas of work site.
- .2 Erect portable steel fence using new 1200 mm high galvanized steel wire fence fabric supported by steel posts spaced at maximum 2.4 m oc.
 - .1 Provide one truck gate and one pedestrian gate.
 - .2 Maintain fence in good repair.
- .3 Make all gates lockable and provide keyed padlocks.
- .4 Obtain Departmental Representative's approval beforehand of location and layout of all temporary fence enclosures.
- .5 Provide battery powered lanterns around the perimeter of the site enclosure to clearly mark its location at night.
- .6 Provide warning signs affixed to all fenced areas, identifying those enclosed areas as "Construction Zones" with access restricted to only those persons so authorized by General Contractor.

- .7 Do not construe fencing as an acceptable replacement for pedestrian walkway and hoarding requirements specified below.

1.6 INTERIOR DUST CONTROL AND DUST BARRIERS

- .1 Control creation and spread of dust and dirt to building interior and in particular to areas within premises still under use by occupants.
- .2 Develop and implement a dust control plan, addressing effective measures to carry out work with least amount of dust being created and propagated.
 - .1 Carefully evaluate the type of work to be undertaken and the physical layout of each work area on site.
 - .2 Provide specifically tailored strategy for each work area.
 - .3 Pre-determine location and placement of dust barriers to confine resulting dust to immediate work area.
 - .4 Inform Departmental Representative of the proposed dust control measures to be followed at each work area and for each major dust generating activities. Obtain Departmental Representative's approval before proceeding with work.
- .3 Dust control plan to incorporate as a minimum the following dust protection and cleaning requirements:
 - .1 Erect dustproof partitions completely around work area to fully isolate construction from other parts of the building.
 - .2 Make all dust barriers airtight, effectively blocking and stopping all dust migration.
 - .3 Inspect dust barriers at various intervals during each work shift. Immediately fix tears, unsealed edges and maintain barriers effectively sealed for the entire work duration.
 - .4 Shut down existing ventilation system feeding construction space, or disconnect and seal-off supply and return air ducts to stop dust from contaminating other areas.
 - .5 Immediately clean areas in use by occupants and public contaminated by work.
 - .1 Vacuum carpets, wash floors and walls. Remove accumulated dust from all surfaces. Clean and remove smears, scuffs and marks.
- .4 Meager attempts at controlling dust will not be tolerated. Failure to provide effective dust control during work and to perform satisfactory cleaning thereafter will result in Departmental Representative to proceed and obtain a separate cleaning service agency to perform cleaning to tenant's satisfaction with cost for such services being charged against this Contract in the form of financial holdbacks.
- .5 Obtain Departmental Representative's approval before erecting any dust partitions simply to underside of finish ceiling.
- .6 Construction of dust barriers, enclosures and placement of temporary protective devices to be performed during Facility non-operational off-hour periods.

1.7 SANITARY FACILITIES

- .1 Provide sanitary facilities for work force in accordance with governing regulations and ordinances.

- .2 Post notices and take such precautions as required by local health authorities. Keep area and premises in sanitary condition.
- .3 Sanitary facilities are available at the site and may be used by Contractor's work force. Make arrangements for the use of such facilities through the Departmental Representative.
- .4 When permanent water and drain connections are completed, provide temporary water closets and urinals complete with temporary enclosures, inside building. Permanent facilities may be used on approval of Departmental Representative.

1.8 ENCLOSURE OF STRUCTURE

- .1 Provide temporary weathertight enclosures and protection for exterior openings until permanently enclosed.
- .2 Provide weathertight and heated enclosures to conduct exterior work during winter and other inclement weather conditions. Erect to allow accessibility for installation of materials and working inside of enclosure.
- .3 Design enclosures to withstand wind pressure and snow loading.

1.9 POWER

- .1 Power supply is available and will be provided for construction usage at current cost rates.
 - .1 Make arrangements for the use of such services through the Departmental Representative.
 - .2 Departmental Representative will designate and approve each location of existing power source to which connections can be made to obtain temporary power service.
 - .3 Connect to existing power supply in accordance with Canadian Electrical Code.
- .2 Provide and pay all costs to supply and install temporary cabling, panelboards, switching devices and other equipment as required to connect into power source, provide adequate ground fault protection and extend power supply from existing source to work areas. Perform work and make all connections in accordance with the Canadian Electrical Code, in compliance with the federal and provincial Occupational Health and Safety Regulations as specified in section 01 35 28 and to lockout requirements specified in section 01 35 25.
- .3 Provide and maintain temporary lighting to conduct work. Ensure illumination level is not less than 162 lx in all locations.
- .4 Electrical power and lighting systems installed under this Contract can be used for construction requirements provided that guarantees are not affected thereby. Make good damage. Replace lamps which have been used over period of 3 months.

1.10 WATER SUPPLY

- .1 Water supply is available on site and will be provided for construction usage at no cost. Make arrangements for the use and transportation of such services to work area through the Departmental Representative.
- .2 Permanent water supply system installed under this Contract can be used for construction requirements provided that guarantees are not affected thereby. Make good damage.

1.11 SCAFFOLDING

- .1 Design, construct and maintain scaffolding in rigid, secure and safe manner in accordance with CAN/CSA-S269.2-M87(R2003).
- .2 Erect scaffolding independent of walls. Remove when no longer required.

1.12 HEATING AND VENTILATING

- .1 Supply, install and pay for costs of temporary heat and ventilation used during construction, including costs of installation, fuel, operation, maintenance and removal of equipment. Use of direct-fired heaters discharging waste products into work areas will not be permitted.
- .2 Provide temporary heat and ventilation in enclosed areas as required to:
 - .1 Facilitate progress of work.
 - .2 Protect work and products against dampness and cold.
 - .3 Prevent moisture condensation on surfaces.
 - .4 Provide ambient temperatures and humidity levels for storage, installation and curing of materials.
 - .5 Provide adequate ventilation to meet health regulations for safe working environment.
- .3 Maintain minimum temperature of 10 degrees C, or higher where specified, as soon as finishing work is commenced and maintain until acceptance of structure by Departmental Representative.
 - .1 Maintain ambient temperature and humidity levels as required for comfort of office personnel.
- .4 Ventilating:
 - .1 Prevent accumulations of dust, fumes, mists, vapours or gases in areas occupied during construction.
 - .2 Provide local exhaust ventilation to prevent harmful accumulation of hazardous substances into atmosphere of occupied areas.
 - .3 Dispose of exhaust materials in manner that will not result in harmful exposure to persons.
 - .4 Ventilate storage spaces containing hazardous or volatile materials.
 - .5 Ventilate temporary sanitary facilities.
 - .6 Continue operation of ventilation and exhaust system for time after cessation of work process to assure removal of harmful contaminants.
- .5 Maintain strict supervision of operation of temporary heating and ventilating equipment to:
 - .1 Conform to applicable codes and standards.
 - .2 Enforce safe practices.
 - .3 Prevent abuse of services.
 - .4 Prevent damage to finishes.
 - .5 Vent direct-fired combustion units to outside.
- .6 Submit bid assuming new equipment and systems will not be used for temporary heating and ventilating.

- .7 Upon acceptance of bid, Departmental Representative may permit use of permanent system providing agreement can be reached on:
 - .1 Conditions of use, special equipment, protection and maintenance.
 - .2 Saving on Contract price.
 - .3 Provisions relating to warranties on equipment.

1.13 CONSTRUCTION SIGN AND NOTICES

- .1 Upon request by Departmental Representative, erect a self-supporting project sign in location indicated.
- .2 Departmental Representative will provide a vinyl sign facing for installation by Contractor on sign framework. Sign frame to be plywood face of approximately 1200 x 2400 mm in size complete with required wood framing at 400 mm o.c. and support posts.
- .3 Install sign plumb and level in neat wood framework and securely anchor in ground by posts to withstand wind pressure of 160 km/h.
- .4 Contractor or subcontractor advertisement signboards are not permitted on site.
- .5 Safety and Instruction Signs and Notices:
 - .1 Signs and notices for safety and instruction shall be in both official languages or commonly understood graphic symbols conforming to CAN3-Z321-96(R2006).
- .6 Maintenance and Disposal of Site Signs:
 - .1 Maintain approved signs and notices in good condition for duration of project and dispose of offsite on completion of project or earlier if directed by Departmental Representative

1.14 REMOVAL OF TEMPORARY FACILITIES

- .1 Remove temporary facilities from site when directed by Departmental Representative.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 GENERAL

- .1 Use new material and equipment unless otherwise specified.
- .2 Within 7 days of written request by Departmental Representative, submit following information for any materials and products proposed for supply:
 - .1 Name and address of manufacturer.
 - .2 Trade name, model and catalogue number.
 - .3 Performance, descriptive and test data.
 - .4 Compliance to specified standards.
 - .5 Manufacturer's installation or application instructions.
 - .6 Evidence of arrangements to procure.
 - .7 Evidence of manufacturer delivery problems or unforeseen delays.
- .3 Provide material and equipment of specified design and quality, performing to published ratings and for which replacement parts are readily available.
- .4 Use products of one manufacturer for equipment or material of same type or classification unless otherwise specified.
- .5 Permanent labels, trademarks and nameplates on products are not acceptable in prominent locations, except where required for operating instructions, or when located in mechanical or electrical rooms.

1.2 PRODUCT QUALITY

- .1 Contractor shall be solely responsible for submitting relevant technical data and independent test reports to confirm whether a product or system proposed for use meets contract requirements and specified standards.
- .2 Final decision as to whether a product or system meets contract requirements rest solely with the Departmental Representative in accordance with the General Conditions of the Contract.

1.3 ACCEPTABLE MATERIALS AND ALTERNATIVES

- .1 Acceptable Materials: When materials specified include trade names or trademarks or manufacturer's or supplier's name as part of the material description, select and only use one of the names listed for incorporation into the Work.
- .2 Alternative Materials: Submission of alternative materials to trade names or manufacturer's names specified must be done during the bidding period following procedures indicated in the Instructions to Bidders.
- .3 Substitutions: After contract award, substitution of a specified material will be dealt with as a change to the Work in accordance with the General Conditions of the Contract.

1.4 MANUFACTURER'S INSTRUCTIONS

- .1 Unless otherwise specified, comply with manufacturer's latest printed instructions for materials and installation methods to be used. Do not rely on labels or enclosure provided with products. Obtain written instructions directly from manufacturers.
- .2 Notify Departmental Representative in writing of any conflict between these specifications and manufacturer's instructions, so that Departmental Representative will designate which document is to be followed.

1.5 AVAILABILITY

- .1 Immediately notify Departmental Representative in writing of unforeseen or unanticipated material delivery problems by manufacturer. Provide support documentation.

1.6 WORKMANSHIP

- .1 Ensure quality of work is of highest standard, executed by workers experienced and skilled in respective duties for which they are employed.
- .2 Remove unsuitable or incompetent workers from site as stipulated in the General Conditions of the Contract.
- .3 Ensure cooperation of workers in laying out work. Maintain efficient and continuous supervision on site at all times.
- .4 Coordinate work between trades and subcontractors. See section 01 14 10 in this regard.
- .5 Coordinate placement of openings, sleeves and accessories.

1.7 FASTENINGS - GENERAL

- .1 Provide metal fastenings and accessories in same texture, colour and finish as base metal in which they occur. Prevent electrolytic action between dissimilar metals. Use non-corrosive fasteners, anchors and spacers for securing exterior work and in humid areas.
- .2 Space anchors within limits of load bearing or shear capacity and ensure that they provide positive permanent anchorage. Wood or organic material plugs not acceptable.
- .3 Keep exposed fastenings to minimum, space evenly and lay out neatly.
- .4 Fastenings which cause spalling or cracking of material to which anchorage is made, are not acceptable.
- .5 Do not use explosive actuated fastening devices unless approved by Departmental Representative. See section on Health and Safety Requirements in this regard.

1.8 FASTENINGS – EQUIPMENT

- .1 Use fastenings of standard commercial sizes and patterns with material and finish suitable for service.
- .2 Use heavy hexagon heads, semi-finished unless otherwise specified.
- .3 Bolts may not project more than one diameter beyond nuts.
- .4 Use plain type washers on equipment, sheet metal and soft gasket lock type washers where vibrations occur and, use resilient washers with stainless steel.

1.9 STORAGE, HANDLING AND PROTECTION

- .1 Deliver, handle and store materials in manner to prevent deterioration and soiling and in accordance with manufacturer's instructions when applicable. Provide same degree of protection to materials supplied by Departmental Representative.
- .2 Store packaged or bundled materials in original and undamaged condition with manufacturer's seal and labels intact. Do not remove from packaging or bundling until required in Work. Provide additional cover where manufacturer's packaging is insufficient to provide adequate protection.
- .3 Store products subject to damage from weather in weatherproof enclosures.
- .4 Store cementitious products clear of earth or concrete floors, and away from walls.
- .5 Keep sand, when used for grout or mortar materials, clean and dry. Store sand on wooden platforms and cover with waterproof tarpaulins during inclement weather.
- .6 Store sheet materials and lumber on flat, solid supports and keep clear of ground. Slope to shed moisture.
- .7 Store and mix paints in heated and ventilated room. Remove oily rags and other combustible debris from site daily. Take every precaution necessary to prevent spontaneous combustion.
- .8 Immediately remove damaged or rejected materials from site.
- .9 Touch-up damaged factory finished surfaces to Departmental Representative's satisfaction. Use touch-up materials to match original. Do not paint over name plates.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 GENERAL

- .1 Conduct cleaning and disposal operations to comply with local ordinances and anti-pollution laws.
- .2 Store volatile waste in covered metal containers, and remove from premises at end of each working day.
- .3 Provide adequate ventilation during use of volatile or noxious substances. Use of building ventilation systems is not permitted for this purpose.

1.2 MATERIALS

- .1 Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer.

1.3 CLEANING DURING CONSTRUCTION

- .1 Maintain work site/work areas in a tidy condition, free from accumulations of waste material and debris. Clean areas on a daily basis.
- .2 Keep building entrances, corridors, stairwells and tenant occupied areas of building in a clean dust free condition at all times. Conduct thorough cleaning of these areas at end of each workshift when used by workers or affected by the Work.
- .3 Provide on-site dumpster containers for collection of waste materials and debris.
- .4 Use separate collection bins, clearly marked as to purpose, for source separation and recycling of waste and debris in accordance with waste management requirements specified.
- .5 Remove waste materials, and debris from site on a minimum weekly basis.
- .6 Schedule cleaning operations so that resulting dust, debris and other contaminants will not fall on wet, newly painted surfaces nor contaminate building systems.
- .7 Provide dust barriers, dividers, seals on doors and employ other dust control measures as required to ensure that dust and dirt, generated by work, are not transmitted to other areas of building, this applies to buildings where electrical distribution upgrades will occur. Should dust migrate into areas of building, employ such means as may be necessary to immediately clean all contaminated surfaces to the satisfaction of the Departmental Representative.
- .8 Immediately clean all dust, dirt, smears, scuffs and soiled surfaces areas resulting from the Work.
 - .1 Perform cleaning, dusting and washing operations, carpet vacuuming (including shampooing if deemed required by Departmental Representative) and floor washing as necessary to thoroughly clean all soiled surfaces.
- .9 Remove snow and ice from access doors used by workforce.

1.4 FINAL CLEANING

- .1 In preparation for acceptance of the completed work perform final cleaning.
- .2 Remove grease, dust, dirt, stains, labels, fingerprints, marks and other foreign materials, from interior and exterior finished surfaces. Clean and polish surfaces including glass, mirrors, hardware, wall tile, stainless steel, chrome, baked enamel, plastic laminate, mechanical and electrical fixtures.
- .3 Replace items with broken pieces, scratches or disfigured.
- .4 Clean lighting reflectors, lenses, and other lighting surfaces.
- .5 Vacuum clean and dust building interiors, behind grilles, louvres and screens.
- .6 Wax, seal, shampoo or prepare floor finishes as recommended by manufacturer.
- .7 Inspect finishes, fitments and equipment. Ensure specified workmanship and operation.
- .8 Broom clean and wash exterior paved surfaces and walks; rake clean other surfaces of grounds.
- .9 Remove debris and surplus materials from crawl areas, roof areas and other accessible concealed spaces.
- .10 Clean equipment, washroom and kitchen fixtures to a sanitary condition. Replace filters of mechanical equipment.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 DEFINITIONS

- .1 Hazardous Material: Product, substance, or organism that is used for its original purpose, and that is either dangerous goods or a material that may cause adverse impact to the environment or adversely affect health of persons, animals, or plant life when released into the environment.

1.2 WASTE MANAGEMENT

- .1 Incorporate environmental and sustainable practises in managing waste resulting from work.
- .2 Divert as much waste as possible from landfill.
- .3 Coordinate work of subtrades and subcontractors to ensure all possible waste reduction and recycling opportunities are taken. Follow waste management requirements specified in trade sections of the Specifications.
- .4 Reduce waste during installation of new materials. Undertake practices which will optimize full use of materials and minimize waste.
- .5 Develop innovative procedures to reduce quantity of waste generated by construction such as by delivering materials to site with minimal packaging etc...
- .6 Provide on-site facilities to collect, handle and store anticipated quantities of reusable, salvageable and recyclable materials.
- .7 During demolition and removal work separate materials and equipment at source, carefully dismantling, labelling and stockpiling alike items for the following purposes:
 - .1 Reinstallation into the work where indicated.
 - .2 Salvaging reusable items not needed in project which Contractor may sell to other parties.
 - .3 Sending as many items as possible to locally available recycling facility.
 - .4 Segregating remaining waste and debris into various individual waste categories for disposal in a "non-mixed state" as recommended by waste processing/landfill sites.
- .8 Isolate product packaging and delivery containers from general waste stream. Send to recycling facility or return to supplier/manufacturer.
- .9 Send leftover material resulting from installation work for recycling whenever possible.
- .10 Establish methods whereby hazardous and toxic materials, and their containers used on site are properly handled, stored and disposed in accordance with applicable federal, provincial and municipal laws and regulations.

1.3 DISPOSAL REQUIREMENTS

- .1 Burying or burning of rubbish and waste materials is prohibited.

- .2 Disposal of volatile materials, mineral spirits, oil, paint, and other hazardous materials into waterways, storm, or sanitary sewers is prohibited.
- .3 Dispose of waste only at approved waste processing facility or landfill sites approved by authority having jurisdiction.
- .4 Contact the authority having jurisdiction prior to commencement of work, to determine what, if any, demolition and construction waste materials have been banned from disposal in landfills and at transfer stations. Take appropriate action to isolate such banned materials at site of work and dispose in strict accordance with provincial and municipal regulations.
- .5 Transport and dispose of waste intended for waste processing plant or landfill facility in separated condition and to Operator's rules and recommendations in support of their effort to recycle, reduce and divert certain waste stream from general landfill.
- .6 Collect, bundle and transport salvaged materials to be recycled in separated categories and condition as directed by recycling facility. Ship materials only to approved recycling facilities.
- .7 Sale of salvaged items by Contractor to other parties not permitted on site.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 SECTION INCLUDES

- .1 Administrative procedures preceding inspection and acceptance of Work by Departmental Representative.

1.2 RELATED SECTIONS

- .1 Section 01 78 00 – Closeout Submittals.

1.3 INSPECTION AND DECLARATION

- .1 Contractor's Inspection: Coordinate and perform, in concert with subcontractors, an inspection and check of all Work. Identify and correct deficiencies, defects, repairs and perform outstanding items as required to complete work in conformance with Contract Documents.
 - .1 Notify Departmental Representative in writing when deficiencies from Contractor's inspection have been rectified and that Work is deemed to be complete and ready for Departmental Representative's inspection of the completed work.
- .2 Departmental Representative's Inspection: Accompany Departmental Representative during all substantial and final inspections of the Work.
 - .1 Address defects, faults and outstanding items of work identified by such inspections.
 - .2 Advise Departmental Representative when all deficiencies identified have been rectified.
- .3 Note that Departmental Representative will not issue a Certificate of Substantial Performance of the work until such time that Contractor performs following work and turns over the specified documents:
 - .1 Project record as-built documents;
 - .2 Final Operations and Maintenance manuals;
 - .3 Maintenance materials, parts and tools;
 - .4 Compliance certificates from applicable authorities;
 - .5 Reports resulting from designated tests;
 - .6 Demonstration and training complete with user manuals;
 - .7 Manufacturer's Guarantee certificates.
 - .8 Testing, adjusting and balancing of equipment and systems complete with submission of test reports.
 - .9 Commissioning of equipment and systems specified.
- .4 Correct all discrepancies before Departmental Representative will issue the Certificate of Completion.

Part 2 Products

2.1 NOT USED

.1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION

Part 1 General

1.1 SECTION INCLUDES

- .1 Project Record Documents.
- .2 Operations and Maintenance data.

1.2 RELATED SECTIONS

- .1 Section 01 79 00 – Demonstration and Training.

1.3 PROJECT RECORD DOCUMENTS

- .1 Departmental Representative will provide 2 white print sets of contract drawings and 2 copies of Specifications Manual specifically for "as-built" purposes.
- .2 Maintain at site one set of the contract drawings and specifications to record actual as-built site conditions.
- .3 Maintain up-to-date, real time as-built drawings and specifications in good condition and make available for inspection by the Departmental Representative upon request.
- .4 As-Built Drawings:
 - .1 Record changes in red ink on the prints. Mark only on one set of prints and at completion of work, neatly transfer notations to second set (also by use of red ink).
 - .2 Submit both sets to Departmental Representative prior to application for Certificate of Substantial Performance.
 - .3 Stamp all drawings with "As-Built Drawings". Label and place Contractor's signature and date.
 - .4 Show all modifications, substitutions and deviations from what is shown on the contract drawings or in specifications.
- .5 Record following information:
 - .1 Depths of various elements of foundation in relation to first floor level and survey datum.
 - .2 Horizontal and vertical location of exterior underground utilities and appurtenances referenced to permanent surface improvements.
 - .3 Horizontal and vertical location of various elements in relation to Geodetic Datum;
 - .4 Location of internal utilities and appurtenances concealed in construction, referenced to visible and accessible features of structure;
 - .5 Field changes of dimension and detail;
 - .6 Location of all capped or terminated services and utilities.
 - .7 Chases for mechanical, electrical and other services;
 - .8 Ceiling and floor elevations;
 - .9 Reflected ceiling plan condition showing finished layout of all ceiling-mounted services and devices;

- .10 Plumbing, heating, air conditioning and ventilation, sprinkler and electrical service installation locations; all to be dimensioned and referenced to building columns or load bearing walls;
- .11 All structural steel installations to be fully dimensioned;
- .12 All design elevations, sections, floor plans and details dimensioned and marked-up to consistently report finished installation conditions;
- .13 Any details produced during the contract by the Departmental Representative to supplement or to change existing design drawings;
- .14 All change orders issued over the course of the contract must be documented on the finished as-built documents, accurately and consistently depicting the changed condition as it applies to all affected drawing details.
- .6 As-built Specifications: legibly mark in red each item to record actual construction, including:
 - .1 Changes made by Addenda and Change Orders.
 - .2 Mark up both copies of specifications; stamp "as-built", sign and date similarly to drawings as per above clause.
- .7 Maintain As-built documents current as the contract progresses. Departmental Representative will conduct reviews and inspections of the documents on a regular basis. Failure to maintain as-builts current and complete to satisfaction of the Departmental Representative shall be subject to financial penalties in the form of progress payment reductions and holdback assessments.

1.4 REVIEWED SHOP DRAWINGS

- .1 Provide a complete set of all shop drawings reviewed for project to incorporate into each copy of the Operations & Maintenance manuals.
- .2 Submit full sets at same time and as part of the contents of the Operation and Maintenance manuals specified.

1.5 OPERATIONS AND MAINTENANCE MANUAL

- .1 O&M Manual - Definition: an organized compilation of operating and maintenance data including detailed technical information, documents and records describing operation and maintenance of individual products or systems as specified in individual sections of the specifications.
- .2 Manual Language: final manuals to be in English.
- .3 Number of copies required:
 - .1 Submit 2 interim copies of the manual for review and inspection by Departmental Representative. Make revisions and additions as directed and resubmit.
 - .2 Upon review and acceptance by Departmental Representative, submit 3 final copies. Interim copies are not to be considered as part of the final copies unless they have been fully revised and are identical to the final approved version.
- .4 Submission Date: submit complete operation and maintenance manual to Departmental Representative 3 weeks prior to application for Certificate of Substantial Performance of the work.

- .5 Binding:
 - .1 Assemble, coordinate, bind and index required data into Operation and Maintenance Manual.
 - .2 Use vinyl, hard covered, 3 "D" ring binders, loose leaf, sized for 215 x 280 mm paper, with spine pocket.
 - .3 Where multiple binders are needed, correlate data into related consistent groupings.
 - .4 Identify contents of each binder on spine.
 - .5 Organize and divide data following same numerical system as the section numbers of the Specification Manual.
 - .6 Dividers: separate each section by use of cardboard dividers and labels. Provide tabbed fly leaf for each individual product and system and give description of product or component.
 - .7 Type lists and notes. Do not hand write.
 - .8 Drawings, diagrams and manufacturers' literature must be legible. Provide with reinforced, punched binder tab. Bind in with text; fold larger drawings to size of text pages.
- .6 Manual Contents:
 - .1 Cover sheet containing:
 - .1 Date submitted.
 - .2 Project title, location and project number.
 - .3 Names and addresses of Contractor, and all Sub-contractors.
 - .2 Table of Contents: provide full table of contents in each binder(s), clearly indicate which contents are in each binder.
 - .3 List of maintenance materials.
 - .4 List of spare parts.
 - .5 List of special tools.
 - .6 Original or certified copy of warranties and product guarantees.
 - .7 Copy of approval documents and certificates issued by Inspection Authorities.
 - .8 Copy of reports and test results performed by Contractor as specified.
 - .9 Product Information (PI Data) on materials, equipment and systems as specified in various sections of the specifications. Data to include:
 - .1 List of equipment including manufacturer's name, supplier, local source of supplies and service depot(s). Provide full addresses and telephone numbers.
 - .2 Nameplate information including equipment number, make, size, capacity, model number and serial number.
 - .3 Parts list.
 - .4 Installation details.
 - .5 Operating instructions.
 - .6 Maintenance instructions for equipment.
 - .7 Maintenance instructions for finishes.

- .7 Shop drawings:
 - .1 Include complete set of reviewed shop drawings into each copy of the operations and maintenance manual.
 - .2 Fold and bind material professionally in a manner that corresponds with the specification section numbering system.
 - .3 When large quantity of data is submitted, place into separate binders of same size as O&M binders.
- .8 Equipment and Systems Data: the following list indicates the type of data and extent of information required to be included for each item of equipment and for each system:
 - .1 Description of unit or system, and component parts. Give function, normal operation characteristics, and limiting conditions. Include performance curves, with engineering data and tests, and complete nomenclature and commercial number of replaceable parts.
 - .2 Panel board circuit directories: provide electrical service characteristics, controls, and communications.
 - .3 Include installed colour coded wiring diagrams.
 - .4 Operating Procedures: include start-up, break-in, and routine normal operating instructions and sequences. Include regulation, control, stopping, shut-down, and emergency instructions. Include summer, winter, and any special operating instructions.
 - .5 Maintenance Requirements: include routine procedures and guide for trouble-shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.
 - .6 Servicing and lubrication schedule, and list of lubricants required.
 - .7 Manufacturer's printed operation and maintenance instructions.
 - .8 Sequence of operation by controls manufacturer.
 - .9 Provide original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.
 - .10 Provide installed control diagrams by controls manufacturer.
 - .11 Provide Contractor's coordination drawings, with installed colour coded piping diagrams.
 - .12 Provide list of original manufacturer's spare parts, current prices, and recommended quantities to be maintained in storage.
 - .13 Include test and balancing reports.
 - .14 Additional requirements as specified in individual specification sections.
- .9 Materials and Finishes Maintenance Data:
 - .1 Building Products, Applied Materials, and Finishes: include product data, with catalogue number, size, composition, and colour and texture designations.
 - .2 Instructions for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.
 - .3 Moisture-protection and Weather-exposed Products: include manufacturer's recommendations for cleaning agents and methods, precautions against

detrimental agents and methods, and recommended schedule for cleaning and maintenance.

- .4 Additional Requirements: as specified in individual specifications sections.

1.6 SPARE PARTS, TOOLS AND MAINTENANCE MATERIALS

- .1 Provide spare parts, special tools and extra materials for maintenance purposes in quantities specified in individual specification sections.
- .2 Tag all items with associated function or equipment.
- .3 Provide items of same manufacture and quality as items in Work.
- .4 Deliver to site in well packaged condition. Store in location as directed by Departmental Representative.
- .5 Clearly mark as to contents indicating:
 - .1 Part number.
 - .2 Identification of equipment or system for which parts are applicable.
 - .3 Installation instructions or intended use as applicable.
 - .4 Name, address and telephone number of nearest supplier.
- .6 Prepare and submit complete inventory list of items supplied. Include list within Maintenance Manual.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 RELATED SECTIONS

- .1 Section 01 78 00 – Operations and Maintenance Manual.

1.2 DESCRIPTION

- .1 Demonstrate scheduled operation and maintenance of equipment and systems to Owner's personnel prior to date of final inspection.
- .2 Departmental Representative will provide a list of Owner's personnel to receive instructions,
- .3 Cooperate with Departmental Representative in coordinating time and attendance of Owner's personnel with manufacturer's training Representative(s).

1.3 QUALITY CONTROL

- .1 Ensure that only personnel from own forces, Subcontractors or Suppliers competent and fully knowledgeable in the particular material component, equipment or system installation are used to provide training and demonstrations.
- .2 When specified in individual Sections, obtain the manufacturers authorized Representative to demonstrate operation of equipment and systems, instruct Owner's personnel, and provide written report that demonstration and instructions have been completed.
- .3 Upon request, provide evidence to Departmental Representative of individual Trainer's knowledge and qualifications.

1.4 SUBMITTALS

- .1 Submit schedule of time, date and complete list of equipment and systems for which demonstration and training sessions will be provided. Submit schedule a minimum of 2 weeks prior to designated dates, for Departmental Representative's approval.
- .2 Submit report within 1 week after completion of demonstration, that demonstration and instructions have been satisfactorily completed. Provide time and date of when each demonstration was actually given, with list of persons present.

1.5 CONDITIONS FOR DEMONSTRATIONS

- .1 Prior to carrying out demonstration and training, ensure that equipment has been inspected and tested, is fully operational, has been performance verified and TAB has been carried out.
- .2 Provide copies of completed operation and maintenance manuals for use in demonstrations and instructions.

1.6 PREPARATION

- .1 Verify that conditions for demonstration and instructions comply with requirements.

- .2 Verify that designated personnel are present.

1.7 DEMONSTRATION AND INSTRUCTIONS

- .1 Include the following items within the demonstration and training:
 - .1 Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, and maintenance of each of equipment.
 - .2 Instruct personnel in all phases of operation and maintenance using operation and maintenance manuals as the basis of instruction.
 - .3 Review contents of manual in detail to explain all aspects of operation and maintenance.
 - .4 Prepare and insert additional data in operations and maintenance manuals when the need for additional data becomes apparent during instructions.
 - .5 Provide other specific training and instructions as specified in trade sections.

1.8 TIME ALLOCATED FOR INSTRUCTIONS

- .1 Observe the allocated time period specified in trade sections. Provide additional time when required to ensure all personnel fully understand all aspects of the information and instructions being provided. Allow for questions by participants.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 SECTION INCLUDES

- .1 This section deals with commissioning activities to occur during the construction stage and the early period of facility occupancy stage.
- .2 Section includes:
 - .1 Commissioning activities to be performed by the Contractor who is assigned membership on a Commissioning Team as part of the contract requirements.
 - .2 Commissioning activities to be performed by other members of the Commissioning Team.
- .3 In general, Contractor's commissioning activities consists of performing specified tasks and functions to assist the Commissioning Agent, along with other members of the commissioning team who will commission various components and systems of the Facility.

1.2 RELATED SECTIONS

- .1 Section 01 78 00 – Operations and Maintenance Manuals
- .2 Section 01 79 00 – Demonstration and Training

1.3 BACKGROUND INFORMATION

- .1 Historically in the past, the term commissioning has been used in reference to the process used to conduct testing, adjusting and balancing of the heating, ventilation and air conditioning (HVAC) systems of a building.
- .2 Commissioning (or the commissioning process), as understood by PWGSC, is a planned program of activities conducted in concert with other activities performed during each stage of project delivery.
 - .1 The commissioning process identifies issues during the Planning and Design stages which are addressed during the Construction and Occupancy Stages of a Facility to ensure that the built facility is constructed and proven to operate satisfactorily under all weather, environmental and occupancy conditions to meet operational and user requirements.
 - .2 Commissioning activities during the Construction stage incorporates a third-party verification process and a transfer of critical operational knowledge to Facility personnel.

1.4 COMMISSIONING OBJECTIVES

- .1 A Commissioning Plan has been prepared by the Design Consultant, on behalf of PWGSC, which identifies, among other issues, specific commissioning activities to be carried out by the commissioning team during the Construction and Occupancy Stages of the project.
- .2 The commissioning activities have the following objectives:
 - .1 Collect data on equipment and systems being supplied and document their installation;

- .2 Conduct checks and tests on fully installed building components, equipment, systems and integrated systems to:
 - .1 Verify whether they operate in accordance with requirements of Contract Documents;
 - .2 Verify performance against design criteria and user requirements and measure peak capacities;
- .3 Prepare a Building Management Manual (BMM) which contains operations and maintenance data, as-built record documents, commissioning reports, training data and other critical information for future use by Facility operational staff;
- .4 Ensure transfer of knowledge on the operations, maintenance and management of the Facility to Tenant and Operational personnel by means of appropriate training.
- .3 Work to achieve the above objectives requires a collaborative effort from all members of the commissioning team.
 - .1 Contractor's commissioning activities and responsibilities are described in Clause 1.8 below.
- .4 Commissioning activities performed by the Commissioning Agent and the Design Consultant does not replace checks, tests, adjustments, balancing and other performance verification procedures to be carried out by the Contractor as an integral part of performing the Work of this contract as specified in other sections of the Specifications.

1.5 PRE-CX REVIEW

- .1 The following systems and controls, complete with associated equipment and components, will be commissioned by the Commissioning Agent and requires related commissioning activities to be performed by Contractor as specified herein and in section(s):
 - .1 **Architectural and Structural**
 - .1 Accessibility and operational safety
 - .2 Lunch room equipment
 - .3 Elevating dock system
 - .4 Overhead doors
 - .5 Door and window hardware
 - .2 **Mechanical**
 - .1 Environmental control systems, indoor space conditions, IAQ monitoring, noise & vibration
 - .2 Exhaust systems and related make-up systems
 - .3 Heat recovery systems
 - .4 Dust collection systems
 - .5 Plumbing and other building services
 - .6 Compressed air system
 - .7 Fire suppression and fire protection systems
 - .3 **Electrical**
 - .1 High voltage switch gear and transformation equipment and distribution systems

- .2 Low voltage (below 750 V) distribution systems
- .3 Emergency power generation, uninterruptible power, battery systems, lighting
- .4 Lighting equipment and distribution systems
- .5 Fire exit emergency signage
- .6 Transfer switches, controllers, fire alarm systems, control panels, enunciators
- .7 Voice communications and audio/video systems
- .8 Electronic data and communications information systems
- .9 Intrusion and access security and safety systems
- .10 Lightning protection systems

1.6 DEFINITIONS

- .1 For the purpose of this contract, the various terms listed below, as they relate directly or indirectly to the commissioning process, shall be deemed to have the following meaning.
- .2 Commissioning Process: a planned program of tasks, activities and procedures carried out systematically during the Construction and Occupancy Stages in accordance with the commissioning objectives, specified in clause 1.4.2 above, to:
 - .1 Verify whether the fully installed equipment, systems and integrated systems operate in accordance with contract documents and design criteria and;
 - .2 Ensure that appropriate documentation is compiled to effectively train O& M staff and prepare a comprehensive Building Management Manual (BMM).
- .3 Commission (i.e.: to commission a building component or system): tests and checks conducted by Commissioning Agent on all systems and integrated systems of Facility; carried out only after they are fully installed, functional and Contractor's Performance Verification responsibilities have been completed and approved.
 - .1 Contractor provides assistance during this process by operating equipment and systems, by troubleshooting and making adjustments as may be required.
 - .2 Systems are run under their full operation and under various modes to determine if they function correctly, consistently, at peak efficiency and interactively with each other as intended in accordance with Contract Documents and design criteria.
 - .3 During these checks, adjustments may be made enhancing performance to meet environmental or user requirements.
- .4 Commissioning Agent: a specifically appointed person, representing the Departmental Representative, responsible for the development of a Commissioning Plan and managing its implementation by overseeing and coordinating various activities and responsibilities to be performed by members of the Commissioning Team.
 - .1 In this project, the Commissioning Agent is part of the engineering consultant firm engaged by PWGSC to prepare the final design and contract documents for this Work.
 - .2 Commissioning Agent plays a lead role in support to the Departmental Representative to ensure that the commissioning objectives are achieved.

- .5 Commissioning Manager: a PWGSC departmental employee providing advice and guidance on commissioning requirements to the Commissioning Agent in support to the Departmental Representative.
- .6 Commissioning Plan: The document which describes the organization, scheduling, allocation of resources, required documentation, target dates, and team roles and responsibilities for verification that the built works meet Contract Document and design criteria requirements.
- .7 Contractor: means the General Contractor, however it also refers to any personnel from subcontractors, including the controls and TAB specialists, suppliers and manufacturer's technical persons which Contractor employs to carry out his/her designated commissioning duties and activities.
- .8 Design Consultant: persons from the civil, architectural, mechanical and electrical design disciplines of the engineering firm(s) which have been engaged by the Departmental Representative to prepare the final design and produce the contract documents. Design Consultant also has specifically identified commissioning activities for this project.
- .9 Design Criteria: All those factors included in the design of a Facility prescribed by the tenant needs or as determined by Designer as necessary in order to meet all Facility functional and user operational requirements
- .10 Installation/Start-up Checks: (sometimes referred to as pre-functional checks) A written compilation of checks and inspections to be performed by Contractor during the pre-start-up and start-up of a particular equipment or system component.
 - .1 Checklist sheets are produced which include the following data:
 - .1 Product manufacturer's installation instructions and recommended checks and;
 - .2 Special procedures as specified in relevant sections of Specifications;
 - .3 Other items considered good installation and engineering industry practices deemed appropriate for proper and efficient operation.
 - .2 Standard Installation/Start-up Checklist sheets prepared by equipment manufacturer are acceptable for use. However, supplement with additional data representative of specific project conditions as deemed required by Commissioning Agent.
 - .3 Use Checklist sheets for all equipment installation. Document in writing on checklist the various checks made, deficiencies noted and corrective action taken.
 - .4 Installer to sign Checklist sheets upon completion, certifying that stated checks and inspections have been performed.
 - .5 Use of Installation/Start-up Checklists shall not be considered part of the commissioning process but shall be stringently used for all equipment pre-start and start-up procedures.
 - .6 Return completed Installation/Start-up Checklist sheets after use to Commissioning Agent for retention. Checklists are required by Commissioning Agent when Facility is commissioned and will be included in the BMM manual at completion of project.
- .11 Performance Verification: (sometimes referred to Functional Testing) checks, running dynamic tests and adjustments carried out by Contractor on equipment and systems, upon their installation, to ensure they operate correctly, efficiently and function independently

and interactively with other systems as intended in accordance with contract documents and manufacturer's recommendations.

- .1 Performance Verification shall not be considered part of the commissioning process. It is however considered an essential and integral part of Contractor's responsibilities in the equipment installation process which must be stringently conducted, successfully completed and approved by Departmental Representative before a piece of equipment or system is considered fully installed and functional.
- .2 Facility components and systems will not be commissioned by Commissioning Agent until performance verification has been completed and approved.
- .12 Performance Verification Report Sheets (PV sheets): forms developed by Commissioning Agent for Contractor's use to record measured data and readings taken during functional testing and Performance Verification procedures.
- .13 Product Information (PI Data): a compilation of data gathered on a particular piece of equipment, typically produced by manufacturer, which includes nameplate information, installation/startup instructions, parts list, operating instructions, maintenance guidelines and other pertinent technical data and recommended checks that is necessary to prepare for start-up and functional testing and used during operation and maintenance of such equipment. This documentation is included in the Building Management Manual (BMM) at completion of work.

1.7 COMMISSIONING TEAM

- .1 A commissioning team will be assembled to carryout various functions needed to effectively commission the Facility. Contractor shall be part of this team with duties and responsibilities as specified in this section and in other sections of the Specifications.
- .2 Members of the Commissioning Team are as follows:
 - .1 Commissioning Agent
 - .2 Design Consultant
 - .3 Contractor
 - .4 Construction Commissioning Supervisor
 - .5 Departmental Representative
 - .6 PWGSC Commissioning Manager
 - .7 PWGSC departmental personnel providing advice and project quality control to Departmental representative when required.
 - .8 Facility's operation and maintenance personnel staff as identified by Departmental Representative.
- .3 Effective commissioning requires coordination between members of the commissioning team. Cooperate with other team members in fulfilling assigned duties and as follows:
 - .1 Communicate commissioning objectives, to subcontractors, suppliers and manufacturers.
 - .2 Coordinate activities between subcontractors and trades as needed to carryout Contractor's assigned commissioning activities.
 - .3 Ensure attendance of subcontractors and required specialist at commissioning meetings and during the commissioning process.
- .4 Construction Commissioning Supervisor:

- .1 Assign a person, under Contractor's employ, to be the Construction Commissioning Supervisor.
- .2 Person to be knowledgeable and have past experience in commissioning of mechanical and electrical systems. Submit affidavit confirmation person's qualifications for Departmental Representative's review and approval.
- .3 Construction Commissioning Supervisor to coordinate and oversee all work activities and input required from subcontractors and applicable trades as required to make equipment, subsystems and system ready for commissioning and to conduct commissioning duties assigned to the Contractor.
- .4 Construction Commissioning Supervisor shall:
 - .1 Be the main point of contact, representing the Contractor, with whom the Commissioning Agent and Departmental Representative will to deal with in matters relating to commissioning.
 - .2 Attend all commissioning meetings and ensure that appropriate persons from subcontractors, trades, suppliers and manufacturers attend meetings when deemed required by Commissioning Agent or Departmental Representative.

1.8 CONTRACTOR'S COMMISSIONING ACTIVITIES

- .1 General:
 - .1 Organize and arrange for the services of subcontractors, their specialists and manufacturer's technical representatives to perform Contractor's commissioning activities.
 - .2 Ensure that personnel forming part of the Commissioning Team are qualified and knowledgeable of installed equipment and systems and with design intent.
 - .3 Develop in conjunction with the Commissioning Agent a commissioning schedule as specified in clause 1.11.
 - .4 Notify Departmental Representative in writing when Facility is ready for be commissioned. Give 14 calendar day notice.
 - .5 Commissioning will only commence once that full documentation has been received and installed equipment and systems have undergone successful performance verification.
 - .6 Note that Certificate of Substantial Completion will only be issued when:
 - .1 All commissioning documentation has been received and found suitable by Departmental Representative;
 - .2 Designated equipment and systems have been commissioned and;
 - .3 Training has been completed.
 - .7 Performance faults:
 - .1 Equipment and systems found not operating correctly or not performing as intended during commissioning shall be re-verified by checking 100% of all equipment and components of the unfunctional system, including related controls as required to rectify the deficiencies and ensure correct performance.
 - .2 Costs to conduct additional tests and inspections, as deemed required by Departmental Representative, to determine acceptability and proper performance of such item to be paid for by Contractor.

- .2 Prior to Facility being commissioned:
 - .1 Submit commissioning documentation as specified in clause 1.13 below.
 - .2 Submit the Installation/Start-up Checklist sheets to Commissioning Agent for review prior to conducting the pre-start and start-up of any piece of equipment. Incorporate additional start-up instructions onto checklist as determined by the Commissioning Agent's review.
 - .3 Conduct the pre-start and start-up of all equipment by following and filling out the approved Installation/Start-up Checklists.
 - .4 Conduct Performance Verification on all installed equipment and systems. Use and fill out the PV Report Sheets provided.
 - .5 Upon completion of start-up and performance verification process, submit signed copy of Checklist and PV sheets to Commissioning Agent as affidavit that required checks and tests were successfully conducted.
 - .6 Record performance measurements and data reading on PV sheets and return to Commissioning Agent for compilation.
 - .7 Give Departmental Representative and Commissioning Agent a minimum of 5 days' notice for start-up and performance verification of equipment and systems which must be witnessed by Commissioning Agent as determined by Commissioning Agent beforehand on PV sheets.
 - .8 Provide missing information and data as identified by Commissioning Agent and Departmental Representative during documentation review.
 - .9 Submit above noted documentation before Commissioning will proceed.
 - .10 Address deficiencies in Work identified during performance verification of equipment and systems. Conduct additional performance verification thereafter.
 - .11 Arrange for special tools and devices, identified at commissioning meeting(s), as deemed required to assist with commissioning.
 - .12 Provide access ladders, two way radios and other equipment required by Team when facility will be commissioned.
- .3 When Facility is being Commissioned:
 - .1 Provide qualified tradespersons to be present at site to assist Commissioning Agent for the time period and commissioning activity specified.
 - .2 Assist in commissioning architectural building component, mechanical and electrical systems specified and as follows:
 - .1 Operate designated building component, mechanical/electrical equipment and system under all modes of operation and conduct checks and tests as directed by Commissioning Agent.
 - .2 Check and verify that building component, equipment, systems and integrated systems, including their controls, are functioning and responding correctly and interactively with each other.
 - .3 Test systems independently and then in unison with other related systems.
 - .4 Conduct all Commissioning checks and tests in presence of and witnessed by Commissioning Agent and Departmental Representative.
 - .5 Assist Design Consultant and other members of the commissioning team who will also be present to commission Facility.

- .3 Specific procedures used to commission Facility will be provided by Commissioning Agent which includes:
 - .1 Sequential order of building component and system to be tested.
 - .2 Running systems under various anticipated modes and demands (example: high and low cooling or heating loads, duplicating outside temperature conditions, fire alarm and power failure conditions etc...).
 - .3 Running building controls through all sequences of operation to verify and confirm that equipment and systems are responding as designed and intended.
 - .4 Operating designated equipment at peak capacities, recording output data against design criteria.
- .4 Run component or systems as long as necessary to effectively commission all items as deemed required by Commissioning Agent and Departmental Representative.
- .5 Monitor equipment and system responses.
- .6 Record test results, measurements and other data on commissioning forms provided by Commissioning Agent.
- .7 Assist in analysing results. Identify system deficiencies and components not responding as intended.
- .8 Correct deficiencies and system non-conformance issues. Adjust, calibrate or fine tune system components as required. Debug system software as may be required.
- .9 Retest systems when directed to confirm compliance.
- .4 Upon completion of Facility Commissioning:
 - .1 Provide training to maintenance & operational personnel as specified in clause 1.12 below.
 - .2 Turn over any filled-in checks sheets or reports resulting from commissioning.

1.9 COMMISSIONING ACTIVITIES OF OTHER TEAM MEMBERS

- .1 Commissioning Agent:
 - .1 Represents the Departmental Representative during the commissioning process.
 - .2 Coordinates activities of the commissioning team members to ensure that commissioning activities are carried out properly and in a timely manner.
 - .3 Prepares commissioning schedule in concert with Contractor.
 - .4 Chairs commissioning meetings.
 - .5 Works with Contractor, subcontractors, equipment suppliers, Design Consultant resources, PWGSC and Tenant Representatives to resolve technical problems which may arise during the process.
 - .6 Witnesses Contractor's pre-start, start-up and performance verification procedures for certain equipment and systems specified when deemed required due to their critical nature and function in the Facility.
 - .7 Verifies that Installation/Start-up Checklists and Performance Verification checks and tests are used and stringently followed by Contractor.
 - .8 Assists Contractor in coordination of training activities for facility staff.
 - .9 Submits final commissioning report to Departmental Representative.

- .2 Design Consultant:
 - .1 Prepares in concert with Commissioning Agent the Commissioning Plan.
 - .2 Reviews Contractor's Installation/Start-up Checklists for completeness, incorporating supplement data not addressed on checklist. Provides to Contractor checklist for products which manufacturer does not provide installation and start-up instructions.
 - .3 Develops performance verifications report sheets for use by Contractor to record actual data and measurements against design data criteria.
 - .4 Includes, on performance verification report sheets, design data and anticipated performance values for equipment and systems to undergo verification.
 - .5 Compiles commissioning documentation submitted by Contractor. Prepares final Building Management Manuals.
 - .6 Assists Commissioning Agent in witnessing pre-start, start-up and performance verification activities.
 - .7 Approves type and method of calibration for instruments used by Contractor to conduct performance verification and commissioning tests.
 - .8 Assists Commissioning Agent in reviewing and analysing tests results.
 - .9 Participate in the training sessions provided by Contractor to tenant O&M staff by giving introductory information on design philosophy, design intent and systems designs,
 - .10 Assist in the resolution of issues relating to commissioning.
- .3 Tenant Representative:
 - .1 Participates with other team members to ensure that systems as installed meet the operational and functional requirements.
 - .2 Periodically attends commissioning meetings as required.
 - .3 Attends final commissioning activities.
 - .4 Assists in resolving technical problems by providing additional details on operational requirements.
- .4 Facility Operations and Maintenance Staff:
 - .1 Participates in the commissioning process to obtain early introduction to the facility systems and to provide early operator feedback.
 - .2 Prime interest is in the familiarization and training of appropriate maintenance staff.
 - .3 Staff may attend certain critical equipment start-up and performance verification activities and provide comments and practical suggestions on issues which may arise during actual operation, maintenance and repair of the equipment and systems.
 - .4 Attends commissioning meetings periodically, depending on issues being discussed.
 - .5 Identifies the appropriate staff which must receive the O & M training.

1.10 COMMISSIONING MEETINGS

- .1 General briefing on commissioning will be conducted at first project construction meeting at commencement of work.

- .1 Issues discussed will include scope and extent of commissioning and clarify responsibilities of commissioning team members.
- .2 All team members must attend, including subcontractors of equipment and systems to be commissioned.
- .2 Include commissioning as one agenda item at each construction meeting held and chaired by Contractor during construction. Give subject due consideration for each material and equipment supplied and for all matters of Work.
- .3 At the 60% construction completion stage, as determined by Departmental Representative, a separate commissioning scope meeting will be called by Departmental Representative to review progress of work, discuss schedule of equipment start-up activities and prepare for upcoming commissioning. Issues at meeting will include:
 - .1 Review duties and responsibilities of Contractor and subcontractors, addressing delays and potential problems.
 - .2 Determine the degree of involvement of each trade and manufacturer's representatives in the commissioning process.
- .4 Separate commissioning meetings will be held from the 60% construction stage to project completion. Meetings are tentatively scheduled to be held on a bi-monthly basis but may be more frequent during the equipment start-up and functional testing period.
- .5 Whenever possible meetings will be held immediately following the construction meetings.
- .6 Meeting will be chaired by Commissioning Agent, who will record and distribute minutes.
- .7 Ensure that all subcontractors and relevant manufacturer representatives are present at the 60% commissioning scope meeting and at other meetings as deemed required.

1.11 COMMISSIONING SCHEDULE

- .1 Contractor assumes liabilities and costs for inspections. Including disassembly and re-assembly after approval, starting, testing and adjusting, including supply of testing equipment.
 - .1 Address commissioning activities within the construction work schedule. Clearly identify allocated time period for commissioning and training activities.
 - .2 Provide a separate independent commissioning schedule at the 60% construction stage in order that specific issues and individual details of commissioning can be reviewed, discussed and dealt with from that period onward to project completion. Submit monthly updates thereafter,
 - .3 Develop commissioning schedule in conjunction with Commissioning Agent. Indicate allocated time period and anticipated dates for:
 - .1 Submission of commissioning documentation, including O&M Manuals.
 - .2 Equipment and system start-up and performance verification, making them ready to be commissioned.
 - .3 Allocated period to commission designated building components and systems.
 - .4 Training period.
 - .5 Work during Warranty period.

- .4 Submit schedule to Departmental Representative for review.

1.12 TRAINING

- .1 Commence process of familiarizing Tenant and O&M personnel in the early stages of work on purpose and operation of various equipment and systems. Continue process throughout the entire construction duration.
 - .1 Provide informal briefings during occasional site visits, at planned commissioning meetings and during the final commissioning site activities.
- .2 Conduct formal demonstration and training sessions only after all identified systems have been commissioned by Commissioning Agent and Departmental Representative has given approval to proceed with the training process.
- .3 Provide training and demonstration on equipment, sub-systems, systems and integrated systems as specified.
- .4 Carryout training in accordance with requirements of section 01 79 00.
- .5 Submit written agenda of training session(s) 4 weeks beforehand for review by Commissioning Agent and Departmental Representative.
- .6 Coordinate content with Commissioning Agent. Design Consultant will provide introductory presentation giving general outline of each system design and intended function.
- .7 Submit training manuals for review 2 weeks prior to actual training.
- .8 Ensure required tools and O&M Manuals are on site for training and system demonstration.
- .9 As a minimum, the training sessions to cover the following information:
 - .1 Introduction.
 - .2 Description of the system with factory personnel being involved at appropriate times.
 - .3 Instructions on start-up procedures including seasonal procedures, system checklists and emergency procedures.
 - .4 Operational procedures, including occupancy considerations, seasonal change-over, manual and automatic operations and emergency modes.
 - .5 Instruction on system shutdowns, including checklists.
 - .6 Instructions on all aspects of system maintenance, including routine servicing, lubrication, overhaul and factory servicing.
 - .7 Information concerning the scope of warranties and their use.
 - .8 A description of spare parts in stock and their service.
 - .9 A description of normal tools required for servicing the systems/equipment.
 - .10 Submit typewritten record of training sessions given and list of attendees. Use forms of format approved by Departmental Representative.

1.13 COMMISSIONING DOCUMENTATION

- .1 Submit the following documentation for use during commissioning and for incorporation thereafter into a Building Management Manual (BMM):

- .1 Operations and Maintenance Manuals, Project Record Documents and other data as specified in Section 01 78 00. Data to include:
 - .1 Equipment Product Information (PI Data) complete with:
 - .1 Nameplate info,
 - .2 Installation instructions,
 - .3 Operating procedures and
 - .4 Maintenance guidelines.
 - .2 Reviewed shop drawings,
 - .3 As-built record drawings and Specifications.
- .2 Completed Installation/Start-up Checklist sheets used.
- .3 Performance Verifications checks and tests procedures and completed report sheets used.
- .4 Copy of any static and dynamic test and reports conducted.
- .5 TAB report and other reports as specified in various trade sections.
- .2 Above documentation is required by Commissioning Agent to commission Facility. Submit data minimum 3 weeks before commencement of commissioning.
- .3 Documentation to include detailed information and number of copies as specified for maintenance manuals of section 01 78 00.
- .4 Commissioning Agent and Design Consultant will compile above documentation and produce a BMM manuals for operation/maintenance staff and tenant use.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION