



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Parks Canada Agency
220 4 Ave SE, Suite 720
Calgary, AB T2G 4X3

AMENDMENT / MODIFICATION

005

Tender To: Parks Canada Agency

We hereby offer to sell to Her Majesty the Queen in right of Canada, in accordance with the terms and conditions set out herein, referred to herein or attached hereto, the goods, services, and construction listed herein and on any attached sheets at the price(s) set out therefor.

Soumission aux: l'Agence Parcs Canada

Nous offrons par la présente de vendre à Sa Majesté la Reine du Chef du Canada, aux conditions énoncées ou incluses par référence dans la présente at aux annexes ci-jointes, les biens, services et construction énumérés ici et sur toute feuille ci-annexée, au(x) prix indiqué(s).

Comments - Commentaries

Vendor/Firm Name and Address

Raison sociale et adresse du fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution

Parks Canada Agency
220 4 Ave SE, Suite 720
Calgary, AB T2G 4X3

Title-Sujet Lake Louise Campground Operations Centre – Banff National Park	
Solicitation No. - No. de l'invitation 5P420-18-0568/A	Date: March 8, 2019
GETS Reference No. – No de reference de SEAG PW-19-00864219	Amendment No. - N° de la modif. 5
Solicitation Closes:	
at – á 02:00 PM	on – le March 14, 2019
Time Zone - Fuseau horaire MDT - HAR	
F.O.B. - F.A.B.	
Plant-Usine: <input type="checkbox"/>	Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>
Address Inquiries to: - Adresser toute demande de renseignements à :	
Rebecca Chen rebecca.chen2@canada.ca	
Telephone No. - No de téléphone (587) 439-3529	Fax No. – No de FAX: 1-866-246-6893
Destination of Goods, Services, and Construction: Destinations des biens, services et construction:	
See Herein – Voir ici	

TO BE COMPLETED BY THE BIDDER (type or print)

Vendor/Firm Name	
Address - Adresse	
Name of person authorized to sign on behalf of the Vendor/Firm Nom de la personne autorisée a signer au nom du fournisseur/ de l'entrepreneur	
Titale - Titre	
Telephone No. - N° de telephone: _____	
Facsimile No. - N° de télécopieur: _____	
Signature	Date

Amendment 05

This amendment is being raised to extend the solicitation closing date, to make changes to the tender package and to distribute questions and answers.

A) BID CLOSING DATE

The closing date for tender 5P420-18-0568/A is extended from March 12, 2019 to **March 14, 2019 at 2:00PM Mountain Daylight Time (MDT)**.

B) TENDER PACKAGE REVISIONS

DSP3_18-0568:

ADD: 14020-SENTINEL-DUAL-SWING

ADD: 14020-SWING-GATE-RECEIVER-CONCEPT1

C) QUESTIONS & ANSWERS

Q40 The exterior concrete on the west side is indicated as both sidewalks and aprons. Please confirm.

A40 Concrete apron only in front of garage doors. Concrete sidewalk in front of main entry door and along west wall to connect to apron.

Q41 The architectural drawings show ICF wall panels from top of footing to ceiling where the structural drawings do not show any ICF panels. Which is correct?

A41 The structural drawings show the concrete portion of the ICF walls. The insulation is omitted in a few of these drawings for clarity but they are ICF walls as indicated on the architectural drawings.

Q42 Is there an option to have strip footings with grade beam up to top of slab with ICF panels from top of slab to ceiling?

A42 No, the ICF foundation walls thermally protect the slab and provides a continuous drainage plane.

Q43 Can we get a detail for the front gate that is shown on plan A100?

A43 LiftMaster 14020.220 20'. See the two attachments in DSP3_18-0568

Q44 There is a specification for blinds but they are not shown anywhere on the plans and the specifications does not appear to define where they are intended.

A44 Window coverings will be supplied and installed by Parks Canada.

Q45 There appears to be mention of a radon collection system on drawing 1/A101 but there does not appear to be any other information, including the specifications. Can you provide details?

A45 Refer to 1/A101 for location. Refer to keynote 10 & 14 on M100 for further information.

Q46 There is resilient flooring 09 65 00 specified but there is none shown on the finish schedule, where is this located?

A46 There is no resilient flooring in the project. Disregard reference to resilient flooring in specification.

Q47 There is a typical footing detail 6/A402 that is shown but this does not appear anywhere else on the plans, if it is required what storm service line does it tie into?

A47 It refers to 2/A301. The weeping tile does not need to tie into a storm service line. It will be drained max. 15m away from the building, location to be determined at a later date.

Q48 The overhand detail 7/A402 does not appear to be consistent with the building elevations shown on drawing A201. Does this detail govern at all overhang locations?

A48 7/A402 is the typical overhang condition only for the porch roofs with exterior spaces below only.

Q49 Sidewalks do not show any slab thickenings on the edges. Please confirm this is only required at the aprons.

A49 No slab thickening required on the edges for concrete sidewalks.

Q50 The downspouts for the gutter system are indicated on drawing A102 & 3/A401, There is no method of support for them, do you want these to drop straight to the ground or routed to follow the sloped trusses?

A50 As mentioned in keynote 10 on A201, the downspouts are rain chains and therefore no side support is required. The rain chain will need to be secured to the splashpad below.

Q51 Wall types W1a, W1b & W1d suggest a residential application. Is it acceptable to use NMD90 or AC90 with INEXO boxes for ICF construction? Otherwise channelling of the insulation for EMT and masonry boxes would be required to meet the specifications, please confirm method of installation.

A51 The existing specifications for cabling systems still stands. At this time, it is not acceptable to replace the EMT with NMD90 and AC90 cabling systems.

Q52 Concrete sidewalks and aprons are not specified as to what type of finish is required, specifications indicate broom and exposed aggregate finishes. Please clarify.

Q52 Concrete sidewalks and aprons to have broom finish.

Q53 The civil drawings show the open storage area as asphalt, Architectural show this area to be a F3, concrete.

A53 To be F3 Concrete as shown on architectural drawings.

Q54 There are reinforcing details for the concrete aprons, but none for the sidewalks. Please confirm the reinforcing requirements.

A54 Refer to concrete specifications on S001 and S002. Specifically, Concrete Reinforcement note 11.

All other terms and conditions remain unchanged.