

1 / C3.1 PLAN
Scale: 1:250

PLANT SCHEDULE					
QTY.	BOTANICAL NAME	COMMON NAME	MIN. SIZE	ROOT	NOTES
TREES					
6	POPULUS TREMULOIDES	TREMBLING ASPEN	250cm	WIRE BASKET	
3	PICEA GLAUCA	WHITE SPRUCE	250cm	WIRE BASKET	
11	CORYLUS CORNUTA	BEAKED HAZEL	90cm	POTTED	
NOTE: ALL TREE AND SHRUB LOCATIONS TO BE FIELD MARKED BY DEPARTMENTAL REPRESENTATIVE					

NOTES:

1. SURVEY BENCHMARKS AVAILABLE – CONTACT DEPARTMENTAL REPRESENTATIVE
2. THE CONTRACTOR IS RESPONSIBLE TO LOCATE UNDERGROUND UTILITIES PRIOR TO EXCAVATION.
3. THE CONTRACTOR IS RESPONSIBLE TO DISPOSE OF SURPLUS MATERIAL FROM SITE.
4. ALL TURF AREAS DISTURBED DURING CONSTRUCTION SHALL HAVE PARKS CANADA APPROVED TOPSOIL AND SEED MIX APPLIED.
5. ALL ITEMS (MATERIAL AND LABOUR) NOT SPECIFICALLY IDENTIFIED AS "TO BE SUPPLIED BY PARKS CANADA" ARE THE RESPONSIBILITY OF THE CONTRACTOR.



2 / C3.1 ACCESSIBLE PARKING/DROP OFF AREA
Scale: 1:100

PAVED ACCESSIBLE PARKING/DROP OFF AREA MATERIAL TABLE		
MATERIAL	THICKNESS	COMPACTION REQUIRED
ASPHALT	2 LIFTS – 50mm	98% MARSHALL DENSITY
BASE COURSE	300mm	98% SPMDD

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

LEGEND

- EXISTING BUSHLINE
- EXISTING ASPHALT PATH
- EXISTING ELEVATION
- PROPOSED ELEVATION
- PROPOSED ASPHALT PATH TYPE 1
- PROPOSED ASPHALT PATH TYPE 2
- PROPOSED GRANULAR PATH
- EXISTING WOODEN GUARDRAIL
- PROPOSED WOODEN GUARDRAIL
- PROPOSED SIGN
- PROPOSED ASPHALT (PARKING/DROP OFF AREA)
- GARBAGE/RECYCLING
- TREMBLING ASPEN
- WHITE SPRUCE

No.	Date	Description	Drawn by Dessiné par	Approved Approuvé
3	2019/02/11	ISSUED FOR TENDER	MP	CH
2	2019/01/09	95% Submission	MP	CH
1	2018/12/10	65% Submission	MP	CH

Revision / Revision

A/B Detail number / Sheet number — A Numéro de detail / B Numéro de la feuille

Linear dimensions in millimetres — Dimensions linéaires en millimétres

Parks Canada / Parcs Canada

Project title/Titre du projet

RIDING MOUNTAIN NATIONAL PARK TOWNSITE PAVING & PARKING WASAGAMING, MANITOBA

Drawing title / Titre du dessin

OMINNIK MARSH TRAILHEAD

PLANS
&
PLANTING SCHEDULE

Surveyed by/Arpenté par	Drawn by/Dessiné par	Date
	MP	2019-01-29
Designed by/Concept par: MP	Reviewed by/Revisé par: CH	Scale/Échelle: AS SHOWN

Client Acceptance/Acceptation du client — Date
Approved by/Approuvé par — Date

Project No./Nº du projet: PRO 828.2
Asset No./Nº du bien:
Drawing Set No./Nº de serie du dessin
Sheet No. / N. de la feuille: C3.1