

Project No.: F2470-190001

April 2, 2019

The following changes to the tender documents are effective immediately and will form part of the contract documents:

1. Specification Section 31 23 33 – Excavating, Trenching, and Backfilling Part 1.1.3:

Clarification: The designated spoil pile location is to be the Hamlet landfill facility. The contractor is responsible for contacting the Hamlet to arrange for disposal. The contact information regarding the landfill facility is:

Jimmy Keenainak
Works Foreman
Hamlet of Pangnirtung
PO Box 253
Pangnirtung, NU
X0A 0R0
Phone: (867) 473-8660
Fax: (867) 473-8367

2. Specification Section 35 31 22 Rip-Rap Part 3.1:

Add: 3.1.5 Place rip-rap at low tide from the existing shoreline.

3. Specification Section 35 31 23.13 Rubble Mound Breakwaters Part 3.1:

Add: 3.1.5 Place armour stone at low tide from the existing breakwater roadway or from the tidal flats.

4. Specification Sections 31 23 33 – Excavating, Trenching, and Backfilling Part 1.1.6, 33 42 13 – Pipe Culverts Part 1.2.5 and 35 31 22 – Rip-Rap Part 1.1.3.

Delete: Contractor is responsible for ensuring a rock crusher is available for the production of crushed rock required for this project. The operational status of the rock crusher in the borrow pit east of the Hamlet of Pangnirtung is unknown at time of Tender. Contractor is responsible for confirming the status of the rock crusher and if required, costs associated with supplying a crusher to the borrow pit for the duration of the project to be included in the lump sum costs of the project.

Add: The rock crusher owned and operated by the Hamlet will be fully operational for the production of all the crushed rock required for this project.

5. Specification Sections 31 23 33 – Excavating, Trenching, and Backfilling Part 2.1.1, 33 42 13 – Pipe Culverts Part 2.2.1.2, 35 31 22 – Rip-Rap Part 2.1.1.1.3 and 35 31 23.13 – Rubble Mound Breakwaters Part 2.1.1.2.3

Delete: All rock materials may be supplied from the borrow pit east of the Hamlet of Pangnirtung and shall be of a dense, hard, durable character, free of organic material, in-filled joints, seams, or other defects, resistant to breakdown by handling, frost action or weathering, and not subject to deterioration in sea water.

Add: All rock materials must be supplied from the borrow pit east of the Hamlet of Pangnirtung and shall be of a dense, hard, durable character, free of organic material, in-filled joints, seams, or other defects, resistant to breakdown by handling, frost action or weathering, and not subject to deterioration in sea water. The contact information regarding the Hamlet rock is:

Jimmy Keenainak
Works Foreman
Hamlet of Pangnirtung
PO Box 253
Pangnirtung, NU
X0A 0R0
Phone: (867) 473-8660
Fax: (867) 473-8367