

SUPREME COURT OF CANADA - WINDOW REPAIRS

Heritage Conservation Services
Architecture and Engineering Services
Real Property Branch
Public Services and Procurement Canada

Services de la Conservation du Patrimoine
Services d'Architecture et de Génie
Direction Générale des Biens Immobiliers
Services Publics et Approvisionnement Canada

NOTE:

ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.



INDEX



- A1 - INDEX, LOCATION PLAN, SITE PLAN AND PHOTO
- A2 - GROUND FLOOR PLAN WINDOW NUMBERS FOR REPAIR
- A3 - FIRST FLOOR PLAN WINDOW NUMBERS FOR REPAIR
- A4 - SECOND FLOOR PLAN WINDOW NUMBERS FOR REPAIR
- A5 - THIRD FLOOR PLAN WINDOW NUMBERS FOR REPAIR
- A6 - SOUTH ELEVATION WINDOW NUMBERS FOR REPAIR
- A7 - EAST ELEVATION WINDOW NUMBERS FOR REPAIR
- A8 - NORTH ELEVATION WINDOW NUMBERS FOR REPAIR
- A9 - WEST ELEVATION WINDOW NUMBERS FOR REPAIR
- A10 - EAST & WEST ELEVATIONS - INTERIOR WEST COURTYARD
- A11 - EAST & WEST ELEVATIONS - INTERIOR EAST COURTYARD
- A12 - NORTH & SOUTH ELEVATIONS - INTERIOR COURTYARDS
- A13 - WINDOW TYPES AND APPROXIMATE SIZES
- A14 - WINDOW REPAIR SCHEDULE
- A15 - REPAIR DETAILS

05		
04		
03		
02		
01	ISSUED FOR TENDER	
revision		date

LOCATION PLAN



SITE PLAN
NOT TO SCALE



project **SUPREME COURT OF CANADA WINDOW REPAIRS** project

drawing **INDEX, LOCATION PLAN, SITE PLAN AND PHOTO** dessin

designed	HCS	conçu
date	July 2018	
drawn	HCS	dessiné
date	July 2018	
reviewed		examiné
date		
approved		approuvé
date		
tender		soumission
Project Manager		Administrateur de projets
project no.		no. du projet
	R.080533.402	
drawing no.		no. du dessin

NOTE:
 ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.

REPAIR NOTES:


(R1) (r1) REPLACE EXISTING GLAZING. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.01.

(R2) (r2) GAP SEAL. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.02.

(R3) (r3) RESTRAINT AT HATCH. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.03.


(R4) (r4) SCREW REPLACEMENT. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.04 (ASSUME 90% AT HINGE AND 10% AT STAY).

R - REPAIR WORK AT EXTERIOR SASH.
 r - REPAIR WORK AT INTERIOR SASH.
 R^x / r^x - 'x' EQUALS REPAIR QUANTITY ABOVE.



GROUND FLOOR PLAN
 1 : 400

05		
04		
03		
02		
01	ISSUED FOR TENDER	
revision		date



project **SUPREME COURT OF CANADA WINDOW REPAIRS** project

drawing **GROUND FLOOR PLAN WINDOW NUMBERS FOR REPAIR** dessin

designed	HCS	conçu
date	July 2018	
drawn	HCS	dessiné
date	July 2018	
reviewed		examiné
date		
approved		approuvé
date		
tender		soumission
Project Manager		Administrateur de projets
project no.	R.080533.402	no. du projet
drawing no.		no. du dessin

NOTE:
 ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.

REPAIR NOTES:


(R1) (r1) REPLACE EXISTING GLAZING. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.01.

(R2) (r2) GAP SEAL. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.02.

(R3) (r3) RESTRAINT AT HATCH. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.03.


(R4) (r4) SCREW REPLACEMENT. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.04 (ASSUME 90% AT HINGE AND 10% AT STAY).

R - REPAIR WORK AT EXTERIOR SASH.
 r - REPAIR WORK AT INTERIOR SASH.
 R^x / r^x - 'x' EQUALS REPAIR QUANTITY ABOVE.



FIRST FLOOR PLAN
 1 : 400


05		
04		
03		
02		
01	ISSUED FOR TENDER	
revision		date



project **SUPREME COURT OF CANADA WINDOW REPAIRS** project

drawing **FIRST FLOOR PLAN WINDOW NUMBERS FOR REPAIR** dessin

designed	HCS	conçu
date	July 2018	
drawn	HCS	dessiné
date	July 2018	
reviewed		examiné
date		
approved		approuvé
date		
tender		soumission
Project Manager		Administrateur de projets
project no.		no. du projet
	R.080533.402	
drawing no.		no. du dessin



NOTE:

ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.

REPAIR NOTES:


(R1) (r1) REPLACE EXISTING GLAZING. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.01.

(R2) (r2) GAP SEAL. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.02.

(R3) (r3) RESTRAINT AT HATCH. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.03.


(R4) (r4) SCREW REPLACEMENT. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.04 (ASSUME 90% AT HINGE AND 10% AT STAY).

R - REPAIR WORK AT EXTERIOR SASH.
r - REPAIR WORK AT INTERIOR SASH.
R^x / r^x - 'x' EQUALS REPAIR QUANTITY ABOVE.



SECOND FLOOR PLAN
1 : 400

05		
04		
03		
02		
01	ISSUED FOR TENDER	
revision		date



project **SUPREME COURT OF CANADA WINDOW REPAIRS** project

drawing **SECOND FLOOR PLAN WINDOW NUMBERS FOR REPAIR** dessin

designed	HCS	conçu
date	July 2018	
drawn	HCS	dessiné
date	July 2018	
reviewed		examiné
date		
approved		approuvé
date		
tender		soumission
Project Manager		Administrateur de projets
project no.	R.080533.402	no. du projet
drawing no.		no. du dessin




NOTE:

ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.

REPAIR NOTES:


- (R1) (r1) REPLACE EXISTING GLAZING. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.01.
- (R2) (r2) GAP SEAL. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.02.
- (R3) (r3) RESTRAINT AT HATCH. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.03.
- (R4) (r4) SCREW REPLACEMENT. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.04 (ASSUME 90% AT HINGE AND 10% AT STAY).

R - REPAIR WORK AT EXTERIOR SASH.
r - REPAIR WORK AT INTERIOR SASH.
R^x / r^x - 'x' EQUALS REPAIR QUANTITY ABOVE.



THIRD FLOOR PLAN
1 : 400

05		
04		
03		
02		
01	ISSUED FOR TENDER	
revision		date



project / projet
SUPREME COURT OF CANADA WINDOW REPAIRS

drawing / dessin
THIRD FLOOR PLAN WINDOW NUMBERS FOR REPAIR

designed / conçu	HCS	date / date	July 2018
drawn / dessiné	HCS	date / date	July 2018
reviewed / examiné		date / date	
approved / approuvé		date / date	
tender / soumission		date / date	
Project Manager / Administrateur de projets		project no. / no. du projet	R.080533.402
drawing no. / no. du dessin			

NOTE:

ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.

REPAIR NOTES:


(R1) r1 REPLACE EXISTING GLAZING. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.01.

(R2) r2 GAP SEAL. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.02.

(R3) r3 RESTRAINT AT HATCH. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.03.

(R4) r4 SCREW REPLACEMENT. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.04 (ASSUME 90% AT HINGE AND 10% AT STAY).

R - REPAIR WORK AT EXTERIOR SASH.
 r - REPAIR WORK AT INTERIOR SASH.
 R^x / r^x - 'x' EQUALS REPAIR QUANTITY ABOVE.



SOUTH ELEVATION

1 : 400

05		
04		
03		
02		
01	ISSUED FOR TENDER	
revision		date

A C	A detail no. no. du détail B key location empl. clé C detail location empl. du détail	A B C
--------	--	-------------

project **SUPREME COURT OF CANADA WINDOW REPAIRS** project

drawing **SOUTH ELEVATION WINDOW NUMBERS FOR REPAIR** dessin

designed HCS conçu
 date July 2018

drawn HCS dessiné
 date July 2018

reviewed examiné
 date

approved approuvé
 date

tender soumission
 Project Manager Administrateur de projets

project no. no. du projet
 R.080533.402

drawing no. no. du dessin
A-6 of/de 15

NOTE:

ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.

REPAIR NOTES:


(R1) (r1) REPLACE EXISTING GLAZING. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.01.

(R2) (r2) GAP SEAL. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.02.

(R3) (r3) RESTRAINT AT HATCH. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.03.

(R4) (r4) SCREW REPLACEMENT. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.04 (ASSUME 90% AT HINGE AND 10% AT STAY).

R - REPAIR WORK AT EXTERIOR SASH.
 r - REPAIR WORK AT INTERIOR SASH.
 R^x / r^x - 'x' EQUALS REPAIR QUANTITY ABOVE.



EAST ELEVATION

1 : 400

05		
04		
03		
02		
01	ISSUED FOR TENDER	
revision		date

A C	A detail no. no. du détail B key location empl. clé C detail location empl. du détail	A B C
--------	--	----------

project **SUPREME COURT OF CANADA WINDOW REPAIRS** project

drawing **EAST ELEVATION WINDOW NUMBERS FOR REPAIR** dessin

designed	HCS	conçu
date	July 2018	
drawn	HCS	dessiné
date	July 2018	
reviewed		examiné
date		
approved		approuvé
date		
tender		soumission
Project Manager		Administrateur de projets
project no.	R.080533.402	no. du projet
drawing no.		no. du dessin

REPAIR NOTES:

(R1) (r1) REPLACE EXISTING GLAZING. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.01.


(R2) (r2) GAP SEAL. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.02.

(R3) (r3) RESTRAINT AT HATCH. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.03.

(R4) (r4) SCREW REPLACEMENT. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.04 (ASSUME 90% AT HINGE AND 10% AT STAY).

R - REPAIR WORK AT EXTERIOR SASH.
r - REPAIR WORK AT INTERIOR SASH.
R^x / r^x - 'x' EQUALS REPAIR QUANTITY ABOVE.

NOTE:
ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.



NORTH ELEVATION

1 : 400

05		
04		
03		
02		
01	ISSUED FOR TENDER	
revision		date

A C	A detail no. no. du détail B key location empl. clé C detail location empl. du détail	A B C
--------	--	-------------

project **SUPREME COURT OF CANADA WINDOW REPAIRS** project

drawing **NORTH ELEVATION WINDOW NUMBERS FOR REPAIR** dessin

designed	HCS	conçu
date	July 2018	
drawn	HCS	dessiné
date	July 2018	
reviewed		examiné
date		
approved		approuvé
date		
tender		soumission
Project Manager		Administrateur de projets
project no.		no. du projet
	R.080533.402	
drawing no.		no. du dessin




NOTE:

ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.

REPAIR NOTES:

- (R1) (r1) REPLACE EXISTING GLAZING. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.01.
- (R2) (r2) GAP SEAL. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.02.
- (R3) (r3) RESTRAINT AT HATCH. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.03.
- (R4) (r4) SCREW REPLACEMENT. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.04 (ASSUME 90% AT HINGE AND 10% AT STAY).

R - REPAIR WORK AT EXTERIOR SASH.
 r - REPAIR WORK AT INTERIOR SASH.
 R^x / r^x - 'x' EQUALS REPAIR QUANTITY ABOVE.



05		
04		
03		
02		
01	ISSUED FOR TENDER	
revision		date

A C	A detail no. no. du détail B key location empl. clé C detail location empl. du détail	A B C
--------	--	----------

project **SUPREME COURT OF CANADA WINDOW REPAIRS** project

drawing **WEST ELEVATION WINDOW NUMBERS FOR REPAIR** dessin

designed	HCS	conçu
date	July 2018	
drawn	HCS	dessiné
date	July 2018	
reviewed		examiné
date		
approved		approuvé
date		
tender		soumission
Project Manager		Administrateur de projets
project no.	R.080533.402	no. du projet
drawing no.	A-9 of/de 15	no. du dessin

WEST ELEVATION

1 : 400

REPAIR NOTES:

(R1) (r1) REPLACE EXISTING GLAZING. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.01.


(R2) (r2) GAP SEAL. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.02.

(R3) (r3) RESTRAINT AT HATCH. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.03.

(R4) (r4) SCREW REPLACEMENT. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.04 (ASSUME 90% AT HINGE AND 10% AT STAY).


R - REPAIR WORK AT EXTERIOR SASH.
 r - REPAIR WORK AT INTERIOR SASH.
 R^x / r^x - 'x' EQUALS REPAIR QUANTITY ABOVE.

NOTE:
 ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.



EAST ELEVATION - INTERIOR WEST COURTYARD

1 : 250



WEST ELEVATION - INTERIOR WEST COURTYARD

1 : 250

05		
04		
03		
02		
01	ISSUED FOR TENDER	
revision		date

A C	A detail no. no. du détail B key location empl. clé C detail location empl. du détail	A B C
--------	--	----------

project **SUPREME COURT OF CANADA WINDOW REPAIRS** project

drawing **EAST & WEST ELEVATIONS INTERIOR WEST COURTYARD** dessin

designed	HCS	conçu
date	July 2018	
drawn	HCS	dessiné
date	July 2018	
reviewed		examiné
date		
approved		approuvé
date		
tender		soumission
Project Manager		Administrateur de projets
project no.		no. du projet
	R.080533.402	
drawing no.		no. du dessin



REPAIR NOTES:

- (R1) (r1) REPLACE EXISTING GLAZING. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.01.
- (R2) (r2) GAP SEAL. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.02.
- (R3) (r3) RESTRAINT AT HATCH. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.03.
- (R4) (r4) SCREW REPLACEMENT. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.04 (ASSUME 90% AT HINGE AND 10% AT STAY).

R - REPAIR WORK AT EXTERIOR SASH.
r - REPAIR WORK AT INTERIOR SASH.
R^x / r^x - 'x' EQUALS REPAIR QUANTITY ABOVE.

NOTE:

ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.

05		
04		
03		
02		
01	ISSUED FOR TENDER	
revision		date

A C	A detail no. no. du détail B key location empl. clé C detail location empl. du détail	A B C
--------	--	----------

project **SUPREME COURT OF CANADA WINDOW REPAIRS** project

drawing **EAST & WEST ELEVATIONS INTERIOR EAST COURTYARD** dessin

designed HCS conçu
date July 2018

drawn HCS dessiné
date July 2018


reviewed examiné
date

approved approuvé
date

tender soumission
Project Manager Administrateur de projets


project no. no. du projet
R.080533.402

drawing no. no. du dessin
A-11 of/de 15



EAST ELEVATION - INTERIOR EAST COURTYARD

1 : 250



WEST ELEVATION - INTERIOR EAST COURTYARD

1 : 250


REPAIR NOTES:

- (R1) (r1) REPLACE EXISTING GLAZING. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.01.
- (R2) (r2) GAP SEAL. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.02.
- (R3) (r3) RESTRAINT AT HATCH. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.03.
- (R4) (r4) SCREW REPLACEMENT. REFER TO SPECIFICATION SECTION 080351.23 ARTICLE 3.04 (ASSUME 90% AT HINGE AND 10% AT STAY).

R - REPAIR WORK AT EXTERIOR SASH.
 r - REPAIR WORK AT INTERIOR SASH.
 R^x / r^x - 'x' EQUALS REPAIR QUANTITY ABOVE.


NOTE:

ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.



NORTH ELEVATION - INTERIOR COURTYARDS

1 : 250



SOUTH ELEVATION - INTERIOR COURTYARDS

1 : 250

05		
04		
03		
02		
01	ISSUED FOR TENDER	
revision		date




A C	A detail no. no. du détail B key location empl. clé C detail location empl. du détail	A B/C
--------	--	----------

project **SUPREME COURT OF CANADA WINDOW REPAIRS** project

drawing **NORTH & SOUTH ELEVATIONS INTERIOR COURTYARDS** dessin


designed	HCS	conçu
date	July 2018	
drawn		dessiné
date	HCS July 2018	
reviewed		examiné
date		
approved		approuvé
date		
tender		soumission
Project Manager		Administrateur de projets
project no.		no. du projet
	R.080533.402	
drawing no.		no. du dessin

NOTE:
 ALL DIMENSIONS ARE IN MILLIMETERS
 UNLESS OTHERWISE NOTED.



NOTES:
 WINDOW ELEVATIONS ARE NOT TO SCALE.
 ALL WINDOW DIMENSIONS ARE APPROXIMATE AND MUST BE VERIFIED ON SITE.


05		
04		
03		
02		
01	ISSUED FOR TENDER	
revision		date



project **SUPREME COURT OF CANADA WINDOW REPAIRS** project

drawing **WINDOW TYPES & APPROXIMATE SIZES** dessin


designed	HCS	conçu
date	July 2018	
drawn	HCS	dessiné
date	July 2018	
reviewed		examiné
date		
approved		approuvé
date		
tender		soumission
Project Manager		Administrateur de projets
project no.	R.080533.402	no. du projet
drawing no.		no. du dessin



NOTE:
 ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.

WINDOW REPAIR SCHEDULE										
Window No.	Window Type	Overall Size (approx.)	Exterior Window Repairs				Interior Window Repairs			
			R1	R2	R3	R4	r1	r2	r3	r4
Ground Floor										
W054	E	1524x3048	3		1					
W056	E	1524x3048	1		1					
W059	E	1524x3048	1		1					
W061	E	1524x3048	3		1					
W064	E	1524x3048	1		1					
First Floor										
W102	A3	2434x5944		1						
W103	A	2434x6858					1			
W105	A	2434x6858		1				1		
W107	A	2434x6858						1		
W111	A1	1828x5715	1							
W115	E1	1524x3048		2	1					
W121	F	762x3048		2	1					
W122	E1	1524x3048			1	1				
W136	E1	1524x3048	2							
W142	E	1524x3048	1		1	2				2
W160	K	762x1525	1							
Second Floor										
W212	E1	1524x3048			1	1				2
W219	F	762x3048	2							
Third Floor										
W312	T	762x1525				2				
W343	K	762x1525				4				
Fourth Floor										
W438	T	762x1525	2							
Total # of Windows: 21			18	6	10	10	1	2	0	4


05		
04		
03		
02		
01	ISSUED FOR TENDER	
revision		date




project / projet
SUPREME COURT OF CANADA WINDOW REPAIRS

drawing / dessin
WINDOW REPAIR SCHEDULE


designed / conçu	HCS
date	July 2018
drawn / dessiné	HCS
date	July 2018
reviewed / examiné	
date	
approved / approuvé	
date	
tender / soumission	
Project Manager / Administrateur de projets	
project no. / no. du projet	R.080533.402
drawing no. / no. du dessin	




NOTE:
ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.



1
R1/r1 - REPLACE GLAZING (USING EXISTING STOPS)
A15 1:1



2
R1/r1 - REPLACE GLAZING (USING NEW ALUM. STOP)
A15 1:1



3
R2/r2 - GAP SEAL
A15 1:1

05		
04		
03		
02		
01	ISSUED FOR TENDER	date
revision		date

A	A detail no. no. du détail	A
C	B key location empl. clé	B/C
	C detail location empl. du détail	


project **SUPREME COURT OF CANADA WINDOW REPAIRS** project

drawing **REPAIR DETAILS** dessin

designed	HCS	conçu
date	July 2018	
drawn	HCS	dessiné
date	July 2018	
reviewed		examiné
date		
approved		approuvé
date		
tender		soumission
Project Manager		Administrateur de projets
project no.		no. du projet
	R.080533.402	
drawing no.		no. du dessin
	A-15 of/de 15	




4
R3/r3 - RESTRAINT AT LATCH
A15 NTS



5
TYPICAL HINGES SHOWING FASTENERS
A15 NTS



6
TYPICAL STAY WITH THUMB SCREW LOCATION
A15 NTS



7
EXISTING STOP WITH FASTENERS
A15 NTS

