

MECHANICAL

1. Clarification of Drawing M-1:

- Only one new water heater is required. Contractor to supply and install 'A.O. Smith' Model: BTX-100 high efficiency direct vented water heater. Input: 100MBH, recovery: 15GPH. Supply and install with condensate neutralizer and mounted on stand as high as possible in basement D-003 where shown on drawings.
- Delete reference to new water heater 'AO Smith' Model: GCRL-40.

END OF ADDENDUM #1