



Date : **April 23, 2019**

Project : **Compensation for the Loss of Wetlands and Habitats in a Migratory Bird Sanctuary –
Îles de la Paix**

Project # : **R.071652.978**

CALL FOR TENDERS – CONSTRUCTION – ADDENDUM 1

1. General

- 1.1. This addendum includes modifications made to drawings and specifications. These modifications must be implemented in accordance with contract documents.
- 1.2. Contractor to include all modifications described below in his tender and adjust its price and schedule, if required.
- 1.3. This addendum follows documents issued on March 14 and 18, 2019.

2. Revisions

2.1. Specifications, Section 01 11 01 – Summary of Work:

2.1.1. Article 1.3.1 “Work must be carried out from Monday to Friday, between ~~7AM and 5PM~~, unless approved otherwise by Departmental Representative. Upon request to the Departmental Representative at least one (1) week ahead of time, Work could be authorized during certain weekends, or according to different schedule, depending on the grounds and justification for the request. »

is replaced by:

“Work must be carried out from Monday to Friday, between 6:30AM and 4:30PM, unless approved otherwise by Departmental Representative. Upon request to the Departmental Representative at least one (1) week ahead of time, Work could be authorized during certain weekends, or according to different schedule, depending on the grounds and justification for the request. »

2.1.2. Article 1.3.2 “A security service is responsible of site access control from Monday to Friday between ~~7:30AM and 5PM~~, except on holidays, but including the construction holiday. If that service is required outside the above hours, the Contractor will assume the ~~extra cost of a maximum of one hundred and fifty dollars (\$150) per day for week days and six hundred dollars (\$600) per day on the weekend.~~ »

is replaced by:

“A security service is responsible of site access control from Monday to Friday between 6:30AM and 4:30PM, except on holidays, but including the construction holiday. If that service is required outside the above hours, Canada will pay for a maximum of two hours per working day (Monday to Friday). For any overtime, the Contractor will assume the extra cost of a maximum of fifty dollars (\$50) per hour for week days and seventy-five dollars (\$75) per hour on the weekend.”

2.1.3. Under the **article 1.4.3** “Relations between Contractor and Groupe St-Pierre, subcontractor assigned by Canada, are as defined in Conditions of Contract. Responsibilities of Groupe St-Pierre are as follows:”, article 1.4.3.1 is to be replaced by the following:

“1.4.3.1. Reserve area on project site for stockpiling of stones, the rock fill transshipment ramp and two (2) bollards, as shown on drawings;”

2.2. Specifications, Section 01 32 16.07 – Construction Progress Schedule – Bar (Gantt) Chart:

2.2.1. Add the following sentence “These expenses can amount to as high as \$20,000.00 monthly.” At the end of **article 1.3.4.1**.

2.2.2 Article 1.5.3.1 “The time frame provided to the Contractor to perform all in-water and Île aux Plaines works as per plans and obtain Substantial Completion Certificate is a maximum ~~409 calendar days~~;”

is replaced by:

“The time frame provided to the Contractor to perform all in-water and Île aux Plaines works as per plans and obtain Substantial Completion Certificate is a maximum of 106 working days (excluding the weekends and 3 holidays);”

2.3. Specifications, Section 01 35 43 – Environmental Procedures:

2.3.1 Article 1.9.1.3 “Planting of **shrub swamps** (on the shore nourishment crest): between the end of the spring flood and the completion of shore nourishment work, ideally ~~no later than mid-September~~;”

is replaced by:

“Planting of **shrub swamps** (on the shore nourishment crest): between the end of the spring flood and the completion of shore nourishment work, no later than early September;”

2.4. Specifications, Section 01 52 00 – Construction Facilities:

2.4.1 The following sentence “Power supply to be provided via the transshipment site’s local network via three electrical panels available for a total of 400 A.” must replace the first sentence at the beginning of the **article 1.9.1**.

2.5. Specifications, Section 31 23 33.01 – Excavation, Trenching and Backfilling:

2.5.1 The following article must be added:

“1.9.3 The projected transshipment site is known to be contaminated. All required measures must be implemented so as not to increase contamination of premises during work. To this end, Canada may undertake an Environmental Characterization Assessment before, during and after the use of the work site. »

2.6. Specifications, Section 32 93 10 – Trees, Shrubs and Ground Cover Planting:

2.5.1 Article 3.5.2 must be replaced by the following:

“3.5 Install trunk protection material to ensure extra clearing width of 300 mm.”

2.7. Drawing C202 (sheet C08)

2.7.1 Sketch providing new location of electrical connections.

2.8. Drawing C303 (sheet C12)

2.8.1 Modification to profile A, thickness of 50-200 mm filter stone between breakwater sections is now 300 mm.

2.9. Drawing C404 (sheet C16)

2.9.1 Wire mesh, shown on AP-6 – Wood Duck Nest Box detail drawing, to be galvanized.

2.9.2 Wood pole, shown on AP-8 – Osprey Platform Wood Pole Mount detail drawing, to be water-based micronized copper azole pressure-treated wood.

2.10. Appendix 2 – Mitigation Measures

Article 1.6.1

2.10.1 Article 1.6.1 “Comply with the annual restriction period for work in water, which is from ~~March 15th to June 15th~~. This period is meant to protect the spawning of fresh water species and early spawners, egg-laying of turtles and bird nesting. »

is replaced by:

“Comply with the annual restriction period for work in water, which is from March 15th to June 1st. This period is meant to protect the spawning of fresh water species and early spawners, egg-laying of turtles and bird nesting.”

Prepared by

Guy Latreille p. eng.