SPECIFICATION

SLIPWAY RECONSTRUCTION

RIVER OF PONDS, NL

Project No.: 722303

PREPARED FOR:

Fisheries and Oceans Canada Small Craft Harbours

DATE:

April 2019





Slipway Reconstruction	List of Contents	Section 00 01 11
River of Ponds, NL		Page 1
PN: 722303		April 2019

Section	Title	Pages
-1 1 04		
	General Requirements	
01 10 10	GENERAL INSTRUCTIONS	10
01 29 83	PAYMENT PROCEDURES: TESTING LABORATORY SERVICES	2
01 33 00	SUBMITTAL PROCEDURES	5
01 35 24	* =	5
01 35 25	SPECIAL PROCEDURES ON LOCKOUT REQUIREMENTS	6
01 35 29	HEALTH AND SAFETY REQUIREMENTS	12
01 35 43	ENVIRONMENTAL PROCEDURES	4
01 45 00	QUALITY CONTROL	4
01 50 00	TEMPORARY FACILITIES	3
01 56 00	TEMPORARY BARRIERS AND ENCLOSURES	2
01 59 20	INSPECTOR'S CAMP AND BOARD	1
01 61 00	COMMON PRODUCT REQUIREMENTS	4
01 74 11	CLEANING	1
01 74 21	CONSTRUCTION/DEMOLITION WASTE MANAGEMENT AND DISPOSAL	5
01 78 00	CLOSEOUT SUBMITTALS	4
	Existing Conditions	
02 41 16	SITEWORK, DEMOLITION AND REMOVAL	3
Division 03 -		
	CONCRETE FORMING AND ACCESSORIES	4
	CONCRETE REINFORCING	5
	CAST-IN-PLACE CONCRETE	12
03 37 26	UNDERWATER PLACED CONCRETE	. 6
Division 06 -	Wood, Plastics, and Composites	
06 05 73	WOOD TREATMENT	3
	Thermal and Moisture Protection	
07 92 10	JOINT SEALING	6
Division 31 -		
	CORRECTED MAXIMUM DRY DENSITY FOR FILL	2
	AGGREGATE MATERIALS	4
	ROUGH GRADING	6
31 23 16.26	ROCK REMOVAL	4
31 23 33.01	EXCAVATING, TRENCHING AND BACKFILLING GEOTEXTILES	4
31 32 19.01	GEOTEXTILES	4
31 53 13	TIMBER CRIBWORK	8
31 53 16	STRUCTURAL TIMBER	7
	Exterior Improvements	
32 11 23	AGGREGATE BASE COURSES	4
	Transportation	
34 17 39	VEHICLE W-BEAM GUIDE RAIL	3
Division 35 -	Waterway and Marine Construction RUBBLE MOUND BREAKWATER	
35 31 23.13	KORRTE WOOND RKEVKMALEK	5

Slipway Reconstruction	List of Contents	Section 00 01 11
River of Ponds, NL		Page 2
PN: 722303		April 2019

Appendix A - Project Effects Determination Report

List of Drawings

COVER	
DWG 1 OF 9	EXISTING SITE PLAN, DEMOLITION PLAN AND LEGEND
DWG 2 OF 9	NEW SITE PLAN
DWG 3 OF 9	NEW SLIPWAY AND BOAT LAUNCH WAY PLAN
DWG 4 OF 9	EXISTING SLIPWAY SECTION AND NEW SLIPWAY SECTION
DWG 5 OF 9	BOAT LAUNCH WAY SECTION
DWG 6 OF 9	CONCRETE LAUNCH WAY SECTIONS
DWG 7 OF 9	MISC. DETAILS
DWG 8 OF 9	MISC. DETAILS
DWG 9 OF 9	GUIDE RAIL DETAIL, CRIB SECTION AND PRECAST PANEL SECTION &
	DETAILS

Slipway Reconstruction GENERAL INSTRUCTIONS Section 01 10 10
River of Ponds, NL Page 1
PN: 722303 April 2019

PART 1 - GENERAL

1.1 SCOPE

1 The scope for this project includes, but is not limited to, the provision of construction activities, removal of existing (1375 m²) wooden slipway. Construction of a new (1316 m²) timber slipway complete with a 200 mm thick concrete apron and a 41.2 LM boat launch way concrete ramp. The work covered consists of the furnishing of all plant, labour, equipment and materials for these improvements at River of Ponds, NL, Great Northern Peninsula, Newfoundland and Labrador, in strict accordance with specifications and accompanying drawings and subject to all terms and conditions of the contract.

1.2 DESCRIPTION OF WORK

- .1 In general, work under this contract consists of, but will not necessarily be limited to, the following:
 - .1 Demolition, removal and disposal of all existing hardwood timber decking members and PT support beams.
 - .2 Demolition of all concrete supports and reuse these supports in the backfill of the new work to be completed.
 - .3 Demolition, removal and disposal of the existing steel support beams, brackets and associated steel items as indicated on drawings.
 - .4 Demolition, removal and disposal of the existing asphalt pavement as indicated on the accompanying drawings.
 - .5 Construct a new timber slipway complete with rock fill, concrete footings, timber cribs, concrete piers, timber beams, hardwood runners and timber wood decking as indicated on accompanying drawings.
 - .6 Construct a new concrete boat launchway ramp 41.2 m long x 4.9 m wide complete with wheel guard.
 - .7 Construction of new reinforced concrete upland apron along the top edge of the new slipway as shown on drawings.
 - .8 Supply and installation of new armor stone along the new launchway as shown on drawings.
- .2 All as indicated on accompanying drawings and specifications hereto.

		<u> </u>	
Slipway Reconstructi River of Ponds, NL PN: 722303	on	GENERAL INSTRUCTIONS	Section 01 10 10 Page 2 April 2019
1.3 SITE OF WORK	.1	Work will be carried out at River Northern Peninsula, Newfoundland location as shown on the accompan	and Labrador in the
1.4 DATUM	.1	Datum used for this project is Lo (LNT) and is assumed to be +5.773 nail ramset in concrete as shown drawings.	3 metres. PWC 9801,
	.2	Bidders are advised to consult the issued by Fisheries and Oceans in of the tidal conditions affecting	n order to make sure
1.5 FAMILIARIZATION WITH SITE	.1	Before submitting a bid, bidders and its surroundings at their own schedule to review and verify the extent of the work, materials need completion of the work, the means site, severity, exposure and unce soil conditions, any accommodation require, and in general shall obtainformation as to risks, continguished information as to risks, continguished. No allowance shall be made connection on account of error of properly observe and determine the will apply.	n expense and e form, nature and eded for the s of access to the ertainty of weather, ons they may tain all necessary encies and other e or affect their subsequently in this r negligence to
	.2	Contractors, bidders or those the are to review specification Sect: Health and Safety Requirements be Take all appropriate safety measure to site, either before or after a	ion 01 35 29 - efore visiting site. ures for any visit
1.6 CODES AND STANDARDS	.1	Perform work in accordance with of the National Building Code of Standard 373 - Standard for Piers any other code of provincial or including all amendments up to padate provided that in any case of discrepancy, the more stringent apply.	Canada, FCC s and Wharves and local application roject bid closing f conflict or
	.2	Materials and workmanship must me requirements of specified standareferenced documents.	

Slipway Reconstructi River of Ponds, NL PN: 722303	.on	GENERAL INSTRUCTIONS	Section 01 10 10 Page 3 April 2019
1.7 TERM ENGINEER	.1	Unless specifically stated ot Engineer where used in the Sp Drawings shall mean the Depar as defined in the General Con Contract.	ecifications and on the tmental Representative
1.8 SETTING OUT WORK	.1	Set grades and layout work in points and grades established Representative.	
	.2	Assume full responsibility fo layout of work to locations, indicated or as directed by D Representative.	lines and elevations
	.3	Provide devices needed to lay	out and construct work.
	. 4	Supply such devices as straig required to facilitate Departinspection of work.	
	.5	Supply stakes and other surve laying out work.	y markers required for
1.9 COST BREAKDOWN	.1	Before submitting first progr breakdown of Contract price i Departmental Representative a price. Departmental Represent required forms for applicatio	n detail as directed by nd aggregating contract ative will provide the
	.2	Provide cost breakdown in sam numerical and subject title s specification project manual sub-divided into major work c by Departmental Representativ	ystem used in this and thereafter omponents as directed
	.3	Upon approval by Departmental breakdown will be used as bas payment.	=
	. 4 .	All work items not designated table as a measurement for paincluded in the lump sum arrathe Bid and Acceptance Form.	yment, are to be

Slipway Reconstruction	GENERAL INSTRUCTIONS	Section 01 10 10
River of Ponds, NL		Page 4
PN: 722303		April 2019

1.10 WORK SCHEDULE

- .1 Submit within 7 work days of notification of acceptance of bid, a construction schedule showing commencement and completion of all work within the time stated on the Bid and Acceptance Form and the date stated in the bid acceptance letter.
- .2 Provide sufficient details in schedule to clearly illustrate entire implementation plan, depicting efficient coordination of tasks and resources, to achieve completion of work on time and permit effective monitoring of work progress in relation to established milestones.
- As a minimum, work schedule to be prepared and submitted in the form of Bar (GANTT) Charts, indicating work activities, tasks and other project elements, their anticipated durations and planned dates for achieving key activities and major project milestones provided in sufficient details and supported by narratives to demonstrate a reasonable plan for completion of project within designated time, e.g., show target dates for the placement of each crib, if applicable. Generally Bar Charts derived from commercially available computerized project management system are preferred but not mandatory.
- .4 Submit schedule updates on a minimum monthly basis and more often, when requested by Departmental Representative, due to frequent changing project conditions. Provide a narrative explanation of necessary changes and schedule revisions at each update.
- .5 The schedule, including all updates, shall be to Departmental Representative's approval. Take necessary measures to complete work within approved time. Do not change schedule without Departmental Representative's approval.
- .6 All work on the project will be completed within the time indicated on the Bid and Acceptance Form.

1.11 ABBREVIATIONS

.1 Following abbreviations of standard specifications have been used in this specification and on the drawings:

CGSB - Canadian Government Specifications Board

CSA - Canadian Standards Association NLGA - National Lumber Grades Authority ASTM - American Society for Testing and

Slipway Reconstruct River of Ponds, NL PN: 722303	ion	GENERAL INSTRUCTIONS	Section 01 10 10 Page 5 April 2019
1.11 ABBREVIATIONS (Cont'd)			
		Materials	
	.2	Where these abbreviations and s this project, latest edition in bid call will be considered app	effect on date of
1.12 QUARRY AND EXPLOSIVES	.1	Make own arrangements with Provand owners of private propertie and transportation of rock and machinery necessary for work ovroads or streets as case may be	es, for the quarrying all materials and ver their property,
1.13 SITE OPERATIONS	.1	Arrange for sufficient space ad site for conduct of operations, and so on. Exercise care so as damage public or private proper interfere with normal day-to-da progress at site. All arrangeme access will be made by Contract	storage of materials not to obstruct or sty in area. Do not by operations in ents for space and
	.2	Remove snow and ice as required access in a manner that does no structures or interfere with thothers.	ot damage existing
1.14 PROJECT MEETINGS	.1	Departmental Representative wil meetings and assume responsibil and recording minutes.	
	.2	Project meetings will take place unless so directed by the Depar Representative.	
	.3	Departmental Representative will responsibility for recording min forwarding copies to all parties meetings.	nutes of meetings and
	. 4	Have a responsible member of fi project meetings.	rm present at all
1.15 PROTECTION	.1	Store all materials and equipme into work to prevent damage by	-

Slipway Reconstruction River of Ponds, NL PN: 722303	GENERAL INSTRUCTIONS	Section 01 10 10 Page 6 April 2019
1.15 PROTECTION . (Cont'd)	Repair or replace all materi in transit or storage to the Departmental Representative Canada.	e satisfaction of
1.16 DOCUMENTS . REQUIRED	1 Maintain at job site, one co .1 Contract Drawings .2 Specifications .3 Addenda .4 Reviewed Shop Drawing .5 List of outstanding sho .6 Change Orders .7 Other modifications to .8 Field Test Reports .9 Copy of Approved Work S .10 Site specific Health and safety related documents .11 Other documents as stipt Contract Documents.	op drawings Contract Schedule nd Safety Plan and other
1.17 PERMITS .	1 Obtain and pay for all permi licenses as required by Muni Federal and other Authoritie	icipal, Provincial,
	2 Provide appropriate notifica municipal and provincial ins	
	Obtain compliance certificat legislative and regulatory p provincial and federal autho the performance of work.	provisions of municipal,
	4 Submit to Departmental Repre application submissions and received for above reference	approval documents
•	5 Submit to Departmental Repre- quarry permit, if applicable quarry operations.	
•	6 Comply with all requirements advise by all regulatory aut otherwise agreed in writing Representative. Make request these requirements sufficier	thorities unless by Departmental as for such deviations to

related work.

Slipway Reconstructs River of Ponds, NL	lon ·	GENERAL INSTRUCTIONS	Section 01 10 10 Page 7
PN: 722303			April 2019
1.18 CUTTING, FITTING AND PATCHING	.1	Execute cutting, including patching required to make w	
	.2	Where new work connects with existing work is altered, of to match existing work. The openings in existing work at existing services.	cut, patch and make good is includes patching of
	.3	Do not cut, bore, or sleeve	e load-bearing members.
	. 4	Make cuts with clean, true, patches inconspicuous in f	
1.19 EXISTING SUB- SURFACE CONDITIONS	.1	Information pertaining to to conditions may be available Departmental Representative	e by contacting the
	.2	Contractors are cautioned to investigations that may be were intended to provide go only. Any interpolation and relative to any previous in Contractor's responsibility	available for review, eneral site information d/or assumptions made nvestigations is the
1.20 LOCATION OF EQUIPMENT	.1	Location of cleats, ladders pedestals, and utility light or specified shall be constactual location shall be as conditions at time of instareasonable. Obtain approval Representative.	nt poles, fixtures, shown idered as approximate. s required to suit allation and as is
	.2	Inform Departmental Represeinstallation conflicts with components. Follow directive	n other new or existing
	.3	Submit field drawings to in of various services and equal Departmental Representative	uipment when required by
1.21 FISH HABITAT	.1	This work is being conducted habitat may be affected. Per with rules and regulations and in accordance with authoritakings affecting fish	erform work to conform governing fish habitat norization for work or

Slipway Reconstruction	GENERAL INSTRUCTIONS	Section 01 10 10
River of Ponds, NL		Page 8
PN: 722303		April 2019
		•
1.21 FISH HABITAT .2(Cont'd)	Contact the Department of F. Protection Program and Infra 772-3521 at least 10 days is work on site.	astructure Unit at (709)
1.22 NOTICE TO .1 SHIPPING/MARINERS	Notify the Marine Communication Services' Centre, of Fisher (709) 695-2168, ten (10) day and upon completion of the for the issuance of Notices	ies and Oceans Canada, at ys prior to commencement work, in order to allow
.2	During construction any ves- must be marked in accordance the Canada Shipping Act Col	e with the provisions of
1.23 ACCEPTANCE .1	Prior to the issuance of the Substantial Performance, in Departmental Representative work. Correct all discrepaninspection and acceptance.	company with , make a check of all
1.24 WORKS .1 COORDINATION	Responsible for coordinating trades, where the work of swith each other.	
.2	Convene meetings between trainterfaces and ensure that the areas and the extent of required. Provide each tradspecifications of the interrequired, to assist them in out their respective work.	they are fully aware of where interfacing is e with the plans and facing trade, as
.3	Canada will not be responsible accountable for any extra confidence of the failure to carry out Disputes between the various those trades not being info	osts incurred as a result coordination work. s trades as a result of

those trades not being informed of the areas and

responsibility of the General Contractor and shall

extent of interface work shall be the sole

be resolved at no extra cost to Canada.

Slipway Reconstruction GENERAL INSTRUCTIONS Section 01 10 10 River of Ponds, NL Page 9
PN: 722303 April 2019

1.25 CONTRACTOR'S USE OF SITE

- .1 Construction operations, including storage of materials for this contract, not to interfere with the fishing activity and/or operations at this harbour facility.
- .2 Responsible for arranging the storage of materials on or off site, and any materials stored at the site which interfere with any of the day to day activities at or near the site will be moved promptly at the Contractor's expense, upon request by Departmental Representative.
- .3 Contractor will take adequate precautions to protect existing concrete decks and asphalt when operating tracked equipment.
- .4 Exercise care so as not to obstruct or damage public or private property in the area.
- .5 At completion of work, restore area to its original condition. Damage to ground and property will be repaired by Contractor. Remove all construction materials, residue, excess, etc., and leave site in a condition acceptable to Departmental Representative.

1.26 WORK COMMENCEMENT

- .1 Mobilization to project site is to commence immediately after acceptance of bid and submission of Site Specific Safety Plan, unless otherwise agreed by Departmental Representative.
- .2 Project work on site is to commence as soon as possible, with a continuous reasonable work force, unless otherwise agreed by Departmental Representative.
- .3 Weather conditions, short construction season, delivery challenges and the location of the work site may require the use of longer working days and additional work force to complete the project within the specified completion time.
- .4 Make every effort to ensure that sufficient material and equipment is delivered to site at the earliest possible date after acceptance of bid and replenished as required.

1.27 FACILITY SMOKING ENVIRONMENT

.1 Comply with smoking restrictions.

Slipway Reconstruction	GENERAL INSTRUCTIONS	Section 01 10 10
River of Ponds, NL		Page 10
PN: 722303		April 2019

1.28 INTERPRETATION .1 OF DOCUMENTS

Supplementary to the Order of Precedence article of the General Conditions of the Contract, the Division 01 sections take precedence over the technical specification sections in other Divisions of the Specification Manual. Slipway Reconstruction PAYMENT PROCEDURES: TESTING Section 01 29 83
River of Ponds, NL LABORATORY SERVICES Page 1
PN: 722303 April 2019

PART 1 - GENERAL

1.1 SECTION INCLUDES

.1 Inspecting and testing by inspecting firms or testing laboratories designated by Departmental Representative.

1.2 RELATED REQUIREMENTS SPECIFIED ELSEWHERE

Particular requirements for inspection and testing to be carried out by testing laboratory designated by Departmental Representative are specified under various sections.

1.3 APPOINTMENT AND PAYMENT

- Departmental Representative will appoint and pay for services of testing laboratory except for the following:
 - .1 Inspection and testing required by laws, ordinances, rules, regulations or orders of public authorities.
 - .2 Inspection and testing performed exclusively for Contractor's convenience.
 - .3 Mill tests and certificates of compliance.
- .4 Tests specified to be carried out by Contractor under the supervision of Departmental Representative.
- .5 Tests requested by Departmental Representative to confirm material specifications when the applicable manufacturer's documentation or test results are unavailable.
- .6 Additional tests specified in the following paragraph.
- .2 Where tests or inspections by designated testing laboratory reveal Work not in accordance with contract requirements, pay costs for additional tests or inspections as required by Departmental Representative to verify acceptability of corrected work.

1.4 CONTRACTOR'S RESPONSIBILITIES

- .1 Provide labour, equipment and facilities to: testing.
 - .1 Provide access to Work to be inspected and tested.
 - .2 Facilitate inspections and tests.
 - .3 Make good Work disturbed by inspection and test.

			•
Slipway Reconstruction River of Ponds, NL PN: 722303		PAYMENT PROCEDURES: TESTING LABORATORY SERVICES	Section 01 29 83 Page 2 April 2019
1.4 CONTRACTOR'S . RESPONSIBILITIES (Cont'd)		(Cont'd) .4 Provide storage on site fo exclusive use to store equipmen samples.	-
	.2	Notify Departmental Representat advance of operations to allow laboratory personnel and schedu	for assignment of
	.3	Where materials are specified to deliver representative samples quantity to testing laboratory.	in required
	. 4	Pay costs for uncovering and ma is covered before required insp is completed and approved by De Representative.	ection or testing
PART 2 - PRODUCTS			
2.1 NOT USED	.1	Not Used.	
PART 3 - EXECUTION			
3.1 NOT USED	.1	Not Used.	

Slipway Reconstruction SUBMITTAL PROCEDURES Section 01 33 00
River of Ponds, NL Page 1
PN: 722303 April 2019

PART 1 - GENERAL

1.1 SECTION INCLUDES

- .1 Shop drawings and product data.
- .2 Samples.
- .3 Certificates.

1.2 SUBMITTAL GENERAL

- .1 Submit to Departmental Representative for review
 REQUIREMENTS submittals listed, including shop drawings, sar
 certificates and other data, as specified in other
 sections of the Specifications.
- .2 Submit with reasonable promptness and in orderly sequence so as to allow for Departmental Representative's review and not cause delay in Work. Failure to submit in ample time will not be considered sufficient reason for an extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .3 Do not proceed with Work until relevant submissions are reviewed by Departmental Representative.
- .4 Present shop drawings, product data, samples and mock-ups in SI Metric units.
- .5 Where items or information is not produced in SI Metric units, provide soft converted values.
- Review submittals prior to submission to
 Departmental Representative. Ensure during review
 that necessary requirements have been determined and
 verified, required field measurements or data have
 been taken, and that each submittal has been checked
 and co-ordinated with requirements of Work and
 Contract Documents.
 - .1 Submittals not stamped, signed, dated and identified as to specific project will be returned unexamined by Departmental Representative and considered rejected.
- .7 Notify Departmental Representative, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .8 Verify field measurements and affected adjacent Work are co-ordinated.

Slipway Reconstruction	SUBMITTAL PROCEDURES	Section 01 33 00
River of Ponds, NL		Page 2
PN: 722303		April 2019

1.2 SUBMITTAL GENERAL (Cont'd)

- .9 Contractor's responsibility for errors and omissions in submission is not relieved by Departmental Representative's review of submittals.
- .10 Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Departmental Representative's review.
- .11 Submit format: paper originals, or alternatively clear and fully legible photocopies of originals. Facsimiles are not acceptable, except in special circumstances pre-approved by Departmental Representative. Poorly printed non-legible photocopies or facsimiles will not be accepted and be returned for resubmission.
- .12 Make changes or revision to submissions which
 Departmental Representative may require, consistent
 with Contract Documents and resubmit as directed by
 Departmental Representative. When resubmitting,
 notify Departmental Representative in writing of any
 revisions other than those requested.
- .13 Keep one reviewed copy of each submittal document on site for duration of Work.

1.3 SHOP DRAWINGS AND PRODUCT DATA

- .1 The term "shop drawings" means drawings, diagrams, illustrations, schedules, performance charts, product data, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work.
- Number of Shop Drawings: submit sufficient copies of shop drawings which are required by the General Contractor and sub-contractors plus (2) copies which will be retained by Departmental Representative. Ensure sufficient numbers are submitted to enable one complete set to be included in each of the maintenance manuals specified, if applicable.
- .3 Shop Drawings Content and Format:
 - .1 Indicate materials, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of Work. Where items or equipment attach or connect to other items or equipment, confirm that all interrelated work have been coordinated, regardless of section or trade from which the adjacent work is being supplied and installed.

Slipway Reconstruction	SUBMITTAL PROCEDURES	Section 01 33 00
River of Ponds, NL		Page 3
PN: 722303		April 2019

1.3 SHOP DRAWINGS AND PRODUCT DATA (Cont'd)

.3 (Cont'd)

- .2 Shop Drawings Format:
 - .1 Opaque white prints or photocopies of original drawings or standard drawings modified to clearly illustrate work specific to project requirements. Maximum sheet size to be 1000 x 707 mm.
 - .2 Product Data from manufacturer's standard catalogue sheets, brochures, literature, performance charts and diagrams, used to illustrate standard manufactured products, to be original full colour brochures, clearly marked indicating applicable data and deleting information not applicable to project.
 - .3 Non or poorly legible drawings, photocopies or facsimiles will not be accepted and returned not reviewed.
- .3 Supplement manufacturer's standard drawings and literature with additional information to provide details applicable to project.
- .4 Delete information not applicable to project on all submittals.
- .4 Allow 15 calendar days for Departmental Representative's review of each submission.
- .5 Adjustments or corrections made on shop drawings by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, advise Departmental Representative in writing prior to proceeding with Work.
- .6 If upon review by Departmental Representative, no errors or omissions are discovered or if only minor corrections and comments are made, fabrication and installation may proceed upon receipt of shop drawings. If shop drawings are rejected and noted to be Resubmitted, do not proceed with that portion of work until resubmission and review of corrected shop drawings, through same submission procedures indicated above.
- .7 Accompany submissions with transmittal letter, containing:
 - .1 Date.
 - .2 Project title and number.
 - .3 Contractor's name and address.
 - .4 Identification and quantity of each shop drawing, product data and sample.
 - .5 Other pertinent data.
- .8 Submissions include:
 - .1 Date and revision dates.

Slipway Reconstruction SUBMITTAL PROCEDURES Section 01 33 00
River of Ponds, NL Page 4
PN: 722303 April 2019

1.3 SHOP DRAWINGS AND PRODUCT DATA (Cont'd)

.8 (Cont'd)

.3

- .2 Project title and number.
 - Name and address of:
 - .1 Subcontractor.
 - .2 Supplier.
 - .3 Manufacturer.
- .4 Contractor's stamp, signed by Contractor's authorized representative certifying approval of submissions, verification of field measurements and compliance with Contract Documents.
- .5 Cross references to particular details of contract drawings and specifications section number for which shop drawing submission addresses.
- .6 Details of appropriate portions of Work as applicable:
 - .1 Fabrication.
 - .2 Layout, showing dimensions, including identified field dimensions, and clearances.
 - .3 Setting or erection details.
 - .4 Capacities.
 - .5 Performance characteristics.
 - .6 Standards.
 - .7 Operating weight.
 - .8 Wiring diagrams.
 - .9 Single line and schematic diagrams.
 - .10 Relationship to adjacent work.
- .9 After Departmental Representative's review, distribute copies.
- The review of shop drawings by the Departmental Representative or their delegated representative is for sole purpose of ascertaining conformance with general concept. This review shall not mean that the Departmental Representative approves the detail design inherent in the shop drawings, responsibility for which shall remain with Contractor submitting same, and such review shall not relieve Contractor of responsibility for errors or omissions in shop drawings or of responsibility for meeting requirements of the construction and Contract Documents. Without restricting generality of foregoing, Contractor is responsible for dimensions to be confirmed and correlated at job site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for co-ordination of Work of all sub-trades.

Slipway Reconstruction River of Ponds, NL PN: 722303		SUBMITTAL PROCEDURES	Section 01 33 00 Page 5 April 2019	
1.4 SCHEDULE, PERMITS AND CERTIFICATES	.1	Upon acceptance of bid, sub Representative copy of Work other schedules, permits, of and project management plan sections of the Specificati	k Schedule and various certification documents ns as specified in other	
	.2	Submit copy of permits, not Certificates received by Re jurisdiction and as applica	egulatory Agencies having	
	.3	Submission of above documer with Submittal General Requirection		

Slipway Reconstructi River of Ponds, NL PN: 722303	on	SPECIAL PROCEDURES ON FIRE SAFETY REQUIREMENTS	Section 01 35 24 Page 1 April 2019
PART 1 - GENERAL			·
1.1 SECTION INCLUDES	.1	Fire Safety Requirements.	
INCHODES	.2	Hot Work Permit.	
1.2 RELATED WORK	.1	Section 01 35 25 - Special Proce Requirements.	dures on Lockout
	.2	Section 01 35 29 - Health and Sa	fety Requirements.
1.3 REFERENCES	.2	Fire Protection Standards issued Services of Human Resources Deverollows: .1 FCC No. 301-June 1982 Stand Operations (http://ccinfoweb2.ccohs.ca/legifcstde/fc301_e.htm)2 FCC No. 302-June 1982 Stand Cutting (http://ccinfoweb2.ccohs.ca/legifcstde/fc302_e.htm). National Fire Code 2015. National Building Code 2015.	lopment Canada as ard for Construction slation/documents/fp ard for Welding and
1.4 DEFINITIONS	.1	Hot Work defined as: .1 Welding work2 Cutting of materials by use open flame devices3 Grinding with equipment whi. 4 Use of open flame torches swork.	ch produces sparks.
1.5 SUBMITTALS	.1	Submit copy of Hot Work Procedur Work permit to Departmental Repreview, within 14 calendar days of acceptance of bid.	esentative for
	.2	Submit in accordance with the Su Requirements specified in Section Procedures.	

Slipway Reconstruction	SPECIAL PROCEDURES ON	Section 01 35 24
River of Ponds, NL	FIRE SAFETY REQUIREMENTS	Page 2
PN: 722303		April 2019

1.6 FIRE SAFETY REQUIREMENTS

- .1 Implement and follow fire safety measures during Work. Comply with following:
 - .1 National Fire Code, 2015
 - .2 Fire Protection Standards FCC 301 and FCC 302.
 - .3 Federal and Provincial Occupational Health and Safety Acts and Regulations as specified in Section 01 35 29 Health and Safety Requirements.
- .2 In event of conflict between any provisions of above authorities the most stringent provision will apply. Should a dispute arise in determining the most stringent requirement, Departmental Representative will advise on the course of action to be followed.

1.7 HOT WORK AUTHORIZATION

- .1 Obtain Departmental Representative's written "Authorization to Proceed" before conducting any form of Hot work on site.
- .2 To obtain authorization submit to Departmental Representative:
 - .1 Contractor's typewritten Hot Work Procedures to be followed on site as specified below.
 - .2 Description of the type and frequency of Hot Work required.
 - .3 Sample Hot Work Permit to be used.
- .3 Upon review and confirmation that effective fire safety measures will be implemented during performance of hot work, Departmental Representative will provide authorization to proceed as follows:
 - .1 Issue one written "Authorization to Proceed" covering the entire project for duration of work or;
 - .2 Separate work, or segregate certain parts of work, into individual entities. Each entity requiring a separately written "Authorization to Proceed" from Departmental Representative. Follow Departmental Representative's directives in this regard.
- .4 Requirement for individual authorization based on:
 - .1 Nature or phasing of work;
 - .2 Risk to Facility operations;
 - .3 Quantity of various trades needing to perform hot work on project or;
 - .4 Other situation deemed necessary by Departmental Representative to ensure fire safety on premises.
- .5 Do not perform any Hot Work until receipt of Departmental Representative's written "Authorization to Proceed" for that portion of work.

Slipway Reconstruction SPECIAL PROCEDURES ON Section 01 35 24
River of Ponds, NL FIRE SAFETY REQUIREMENTS Page 3
PN: 722303 April 2019

1.8 HOT WORK PROCEDURES

.1 Develop and implement safety procedures and work practices to be followed during the performance of Hot Work.

.2 Procedures to include:

- .1 Requirement to perform hazard assessment of site and immediate hot work area for each hot work event in accordance with Hazard Assessment and Safety Plan requirements of Section 01 35 29 -Health and Safety Requirements.
- .2 Use of a Hot Work Permit system for each hot work event.
- .3 The step by step process of how to prepare and issue permit.
- .4 Permit shall be issued by Contractor's site Superintendent, or other authorized person designated by Contractor, granting permission to worker or subcontractor to proceed with hot work.
- .5 Provision of a designated person to carryout a Fire Safety Watch for a minimum of 60 minutes immediately upon completion of the hot work.
- .6 Compliance with fire safety codes and standards specified herein and occupational health and safety regulations specified in Section 01 35 29 Health and Safety Requirements.
- .3 Generic procedures, if used, must be edited and supplemented with pertinent information tailored to reflect specific project conditions. Clearly label as being the Hot Work Procedures applicable to this contract.
- .4 Hot Work Procedures shall clearly establish worker instructions and allocate responsibilities of:
 - .1 Worker(s),
 - .2 Authorized person issuing the Hot Work Permit,
 - .3 Fire Safety Watcher,
 - .4 Subcontractors and Contractor.
- .5 Brief all workers and subcontractors on Hot Work Procedures and Permit system established for project. Stringently enforce compliance.
 - .1 Failure to comply with the established procedures may result in the issuance of a Non-Compliance Notification at Departmental Representative's discretion with possible disciplinary measures imposed as specified in Section 01 35 29 Health and Safety Requirements.

1.9 HOT WORK PERMIT

.1 Hot Work Permit to include, as a minimum, the following data:

Slipway Reconstruction SPECIAL PROCEDURES ON Section 01 35 24 River of Ponds, NL FIRE SAFETY REQUIREMENTS Page 4 PN: 722303 April 2019 1.9 HOT WORK . 1 (Cont'd) PERMIT Project name and project number. . 1 (Cont'd) . 2 Building name, address and specific room or area where hot work will be performed. . 3 Date when permit issued. . 4 Description of hot work type to be performed. .5 Special precautions required, including type of fire extinguisher needed. Name and signature of person authorized to . 6 issue the permit. Name of worker (clearly printed) to which the permit is being issued. Time Duration that permit is valid (not to exceed 8 hours). Indicate start time and date, and completion time and date. Worker signature with date and time upon hot work termination. .10 Specified time period requiring safety watch. .11 Name and signature of designated Fire Safety Watcher, complete with time and date when safety watch terminated, certifying that surrounding area was under continual surveillance and inspection during the full watch time period specified in Permit and commenced immediately upon completion of Hot Work. Permit to be typewritten form. Industry Standard . 2 forms shall only be used if all data specified above is included on form. . 3 Each Hot Work Permit to be completed in full and signed as follows: Authorized person issuing Permit before hot work commences. Worker upon completion of Hot Work. .3 Fire Safety Watcher upon termination of safety watch.

.4 Returned to Contractor's Site Superintendent for safe keeping.

1.10 FIRE PROTECTION AND ALARM SYSTEMS

- .1 Fire protection and alarm systems shall not be:
 - .1 Obstructed.
 - .2 Shut-off, unless approved by Departmental Representative.
 - .3 Left inactive at the end of a working day or shift.
- .2 Do not use fire hydrants, standpipes and hose systems for purposes other than firefighting.

Slipway Reconstruction River of Ponds, NL		SPECIAL PROCEDURES ON	Section 01 35 24
		FIRE SAFETY REQUIREMENTS	Page 5
PN: 722303			April 2019
1.10 FIRE	.3	Costs incurred, from the fire	department, Facility
PROTECTION AND		owner (and tenants), resulting	
ALARM SYSTEMS		setting off false alarms will	3
(Cont'd)		Contractor in the form of fina	
		reductions and holdback assess	ments against the
•		Contract.	
1.11 DOCUMENTS ON	.1	Keep Hot Work Permits and Haza	ard assessment
SITE		documentation on site for dura	
	.2	Upon request, make available t	o Departmental
		Representative or to authorize	ed safety
		representative for inspection.	

Slipway Reconstruction SPECIAL PROCEDURES ON Section 01 35 25 River of Ponds, NL LOCKOUT REQUIREMENTS Page 1 PN: 722303 April 2019 PART 1 - GENERAL 1.1 SECTION . 1 Procedures to isolate and lockout electrical facility or other equipment from energy source. INCLUDES 1.2 RELATED WORK . 1 Section 01 35 24 - Special Procedures On Fire Safety Requirements. . 2 Section 01 35 29- Health and Safety Requirements. 1.3 REFERENCES . 1 C22.1-15 - Canadian Electrical Code, Part 1, Safety Standard for Electrical Installations. . 2 CAN/CSA C22.3 No. 1-15 - Overhead Systems. CAN/CSA C22.3 No. 7-15 - Underground Systems. .3 . 4 COHS, Canada Occupational Health and Safety Regulations made under Part II of the Canada Labour Code. 1.4 DEFINITIONS . 1 Electrical Facility: means any system, equipment, device, apparatus, wiring, conductor, assembly or part thereof that is used for the generation, transformation, transmission, distribution, storage, control, measurement or utilization of electrical energy, and that has an amperage and voltage that is dangerous to persons. . 2 Guarantee of Isolation: means a guarantee by a competent person in control or in charge that a particular facility or equipment is isolated. .3 De-energize: in the electrical sense, that a piece of equipment is isolated and grounded, e.g. if the equipment is not grounded, it cannot be considered de-energized (DEAD). . 4 Guarded: means that an equipment or facility is covered, shielded, fenced, enclosed, inaccessible

by location, or otherwise protected in a manner

person who might touch or go near such item.

practicable, will prevent or reduce danger to any

that, to the extent that is reasonably

Slipway Reconstruc River of Ponds, NL PN: 722303		SPECIAL PROCEDURES ON LOCKOUT REQUIREMENTS	Section 01 35 25 Page 2 April 2019
1.4 DEFINITIONS (Cont'd)	.5 —	Isolate: means that an electric mechanical equipment or machine disconnected from every source mechanical, hydraulic, pneumation energy that is capable of making	ery is separated or of electrical, ic or other kind of
	.6	Live/alive: means that an electroduces, contains, stores or connected to a source of altern current of an amperage and volt dangerous or contains any hydra other kind of energy that is cafacility dangerous to persons.	is electrically nating or direct tage that is aulic, pneumatic or
1.5 COMPLIANCE REQUIREMENTS	.1	Perform lockouts in compliance .1 Canadian Electrical Code 2 .2 Federal and Provincial Occ and Safety Acts and Regulations Section 01 35 29 - Health and 3 .3 Regulations and code of property applicable to mechanical equipment machinery being de-energized4 Procedures specified here:	2015. cupational Health s as specified in Safety Requirements. ractice as ment or other
	.2	In event of conflict between an above authorities the most striwill apply. Should a dispute at the most stringent requirement Representative will advise on to be followed.	ingent provision rise in determining , Departmental
1.6 SUBMITTALS	1	Submit copy of proposed Lockous sample form of lockout permit or review.	
	.2	Submit documentation within 7 acceptance of bid. Do not procession submittal has been reviewed by Representative.	eed with work until
	.3	Submit above documents in accor submittal requirements specific 01 33 00- Submittal Procedures	ed in Section

review.

Resubmit Lockout Procedures with noted revisions as may result from Departmental Representative's

Slipway Reconstruction SPECIAL PROCEDURES ON Section 01 35 25 River of Ponds, NL LOCKOUT REQUIREMENTS Page 3 April 2019

1.7 ISOLATION OF EXISTING SERVICES

- .1 Obtain Departmental Representative's written authorization prior to conducting work on an existing active, energized service or facility required as part of the work and before proceeding with lockout of such services or facility.
- .2 To obtain authorization, submit to Departmental Representative the following documentation:
 - .1 Written Request for Isolation of the service or facility and;
 - .2 Copy of Contractor's Lockout Procedures.
- .3 Make a Request for Isolation for each event, unless directed otherwise by Departmental Representative, and as follows:
 - .1 Fill-out standard forms in current use at the Facility when so directed by Departmental Representative or;
 - .2 Where no form exist at Facility, make request in writing identifying:
 - .1 Identification of system or equipment to be isolated, including it's location;
 - .2 Time duration, indicating Start time and date, and Completion time and date when isolation will be in effect;
 - .3 Voltage of service feed to system or equipment being isolated;
 - .4 Name of person making the request.
 - .3 Document to be in typewritten format.
- .4 Do not proceed until receipt of written notification from Departmental Representative granting the Isolation Request and authorizating to proceed with the isolation of designated equipment or facility. Departmental Representative may designate other individual at the Facility as the person authorized to grant the Isolation Request.
- .5 Conduct safe, orderly shut down of equipment or facilities, de-energize and isolate power and other sources of energy and lockout items in accordance with requirement of clause 1.8 below.
- .6 Plan and schedule shut down of existing services in consultation with the Departmental Representative and the Facility Manager. Minimize impact and downtime of facility operations.

Slipway Reconstruction River of Ponds, NL PN: 722303		SPECIAL PROCEDURES ON LOCKOUT REQUIREMENTS	Section 01 35 25 Page 4 April 2019
1.7 ISOLATION OF EXISTING SERVICES (Cont'd)	.7	Determine in advance, as much cooperation with the Departmenthe type and frequency of sit require a Request for Isolation Departmental Representative's regard.	ental Representative, cuations which will ion. Follow
	.8	Conduct hazard assessment as process of isolating existing facilities. Hazard Assessment requirements of Health and Sa-Health and Safety Requirements	g equipment and as to conform with afety Section 01 35 29
1.8 LOCKOUTS .	.1	Isolate and lockout electrical mechanical equipment and mach potential energy sources prices such items.	ninery from all
	.2	Develop and implement lockout followed on site as an integr	-
	.3	Use energy isolation lockout designed and appropriate for equipment being locked out.	
	. 4	Use industry standard lockout	t tags.
	.5	Provide appropriate safety gr	rounding and guards as
	.6	Prepare Lockout Procedures in safe work practices, work fur of activities to be followed isolate all potential energy lockout/tagout facilities and	nctions and sequence on site to safely sources and
	.7	Include within procedures a strequest and issuance of individual by a person, employed by Contibe "in-charge" and being resp. 1 Controlling issuance of workers. 2 Determining permit durated. 3 Maintaining record of periods and a submitting a Request for Departmental Representative was accordance with Clause 1.7 and accordance with Clause	vidual lockout permit tractor, designated to consible for: permits or tags to tion. ermits and tags relation to when required in

accordance with Clause 1.7 above.

.5 Designating a Safety Watcher, when one is required based on type of work.

Slipway Reconstruction SPECIAL PROCEDURES ON Section 01 35 25
River of Ponds, NL LOCKOUT REQUIREMENTS Page 5
PN: 722303 April 2019

1.8 LOCKOUTS (Cont'd)

.7 (Cont'd)

- .6 Ensuring equipment or facility has been properly isolated, providing a Guarantee of Isolation to worker(s) prior to proceeding with work.
- .7 Collecting and safekeeping lockout tags, returned by workers, as a record of the event.
- .8 Clearly establish, describe and allocate, within procedures, the responsibilities of:
 - .1 Workers.
 - .2 Designated person controlling issuance of lockout tags/permits.
 - .3 Safety Watcher.
 - .4 Subcontractors and General Contractor.
- .9 Procedures shall meet the requirements of Codes and Regulations specified in clause 1.5 above.
- .10 Generic procedures, if used, must be edited, supplemented with pertinent information and tailored to reflect specific project conditions. Clearly label as being the procedures applicable to this contract.
 - .1 Incorporate site specific rules and procedures established by Facility Manager and in force at site. Obtain such procedures through Departmental Representative.
- .11 Procedures to be in typewritten format.
- .12 Submit copy of Lockout Procedures to Departmental Representative, in accordance with submittal requirements of clause 1.6 herein, prior to commencement of work.

1.9 CONFORMANCE

- .1 Ensure that lockout procedures, as established for project on site, are stringently followed. Enforce use and compliance by all workers.
- .2 Brief all persons working on electrical facilities, mechanical and other equipment fed by an energy source on requirements of this section.
- .3 Failure to perform lockouts in accordance with regulatory requirements or follow procedures specified herein may result in the issuance of a Non-Compliance Notification at Departmental Representative's discretion with possible disciplinary measures imposed as specified in Section 01 35 29 Health and Safety Requirements.

Slipway Reconstruction River of Ponds, NL	n	SPECIAL PROCEDURES ON LOCKOUT REQUIREMENTS	Section 01 35 25
PN: 722303		HOCKOOI KEQUIKEMENIS	Page 6 April 2019
1.10 DOCUMENTS ON .1 SITE		Post Lockout Procedures on for viewing by workers.	site in common location
	. 2	Keep copies of Request for Departmental Representative tags issued to workers durit for full project duration.	and lockout permits or
	.3	Upon request, make such dat. Departmental Representative	or to authorized

safety representative for inspection.

Slipway Reconstruction HEALTH AND SAFETY Section 01 35 29 River of Ponds, NL REQUIREMENTS Page 1 PN: 722303 April 2019 PART 1 - GENERAL . 1 1.1 RELATED WORK Section 01 35 24 - Special Procedures on Fire Safety Requirements. .2 Section 01 35 25 - Special Procedures on Lockout Requirements. 1.2 DEFINITIONS .1 COHS: Canada Occupational Health and Safety Regulations made under Part II of the Canada Labour Code. . 2 Competent Person: means a person who is: Qualified by virtue of personal knowledge, training and experience to perform assigned work in a manner that will ensure the health and safety of persons in the workplace, and; Knowledge about the provisions of occupational health and safety statutes and regulations that apply to the Work and; Knowledgeable about potential or actual danger to health and safety associated with the Work. Medical Aid Injury: any minor injury for which medical treatment was provided and the cost of which is covered by Workers' Compensation Board of the province in which the injury was incurred. PPE: personal protective equipment. . 4 . 5 Work Site: where used in this section shall mean areas, located at the premises where Work is undertaken, used by Contractor to perform all of the activities associated with the performance of the Work.

1.3 SUBMITTALS

- Make submittals in accordance with Section 01 33 . 1 00 - Closeout Submittals.
- .2 Submit site-specific Health and Safety Plan prior to commencement of Work.
 - Submit within 10 work days of notification of Bid Acceptance. Provide 3 copies. Allow for 5-10 days for Departmental Review and recommendations prior to the commencement of work.

Slipway Reconstruct River of Ponds, NI PN: 722303		HEALTH AND SAFETY REQUIREMENTS	Section 01 35 29 Page 2 April 2019
			•
1.3 SUBMITTALS (Cont'd)	2	(Cont'd) .2 Departmental Represent Health and Safety Plan and .3 Revise the Plan as app within 5 work days after re .4 Departmental Represent comments made of the Plan s as an endorsement, approval any kind by Canada and does Contractor's overall respon Occupational Health and Saf	provide comments. ropriate and resubmit ceipt of comments. ative's review and hall not be construed or implied warranty of not reduce sibility for
	.3	Submit name of designated H Representative and support in the Safety Plan.	
	. 4	Submit building permit, com and other permits obtained.	
	.5	Submit copy of Letter in Go Provincial Workers Compensa department of labour organi .1 Submit update of Lette whenever expiration date oc of Work.	tion or other zation. r of Good Standing
	.6	Submit copies of reports or Federal, Provincial and Ter safety inspectors.	
	.7	Submit copies of incident r	eports.
	.8	Submit WHMIS MSDS - Materia	l Safety Data Sheets.
1.4 COMPLIANCE REQUIREMENTS	.1	Comply with the Occupationa for the Province of Newfoun the Occupational Health and made pursuant to the Act.	dland and Labrador, and
	.2	Comply with Canada Labour C Occupational Health and Saf Occupational Safety and Hea as well as any other regula the Act1 The Canada Labour Code http://laws.justice.gc.ca/e.2 COSH can be viewed at:	ety) and the Canada lth Regulations (COSH) tions made pursuant to can be viewed at: ng/L-2/.

.gc.ca/eng/SOR-86-304/ne.html.

Slipway Reconstructi River of Ponds, NL PN: 722303	on	HEALTH AND SAFETY REQUIREMENTS	Section 01 35 29 Page 3 April 2019
1.4 COMPLIANCE .2 REQUIREMENTS (Cont'd)		(Cont'd) 3 A copy may be obtained a Government Publishing Public Services Canada Ottawa, Ontar (819) 956-4800 (1-800-635-794 L31-85/2000 E or F).	& Works & Government rio, K1A 0S9 Tel:
	.3	Treasury Borad of Canada Secr. 1 Treasury Board, Fire Pro April 1, 2010 www.tbs-sct.gc.ca/pol/doc-eng=text.	otection Standard
•	. 4	Canadian Standards Association .1 CSA S350-M1980 (R2003), Safety in Demolition of Structure	Code of Practice for
	.5	Observe construction safety m .1 Part 8 of National Build .2 Provincial Worker's Comp .3 Municipal by-laws and or	ding Code 2015. Densation Board.
	.6	In case of conflict or discrespecified requirements, the mapply.	
	.7	Maintain Workers Compensation standing for duration of Cont of clearance through submissi Standing.	ract. Provide proof
	.8	Medical Surveillance: Where plegislation or regulation, obworker medical surveillance of	otain and maintain
1.5 RESPONSIBILITY		Be responsible for health and site, safety of property and persons and environment adjace extent that they may be affect Work.	for protection of cent to the site to
	.2	Comply with and enforce complesub-contractors and other per to work site with safety requirements, applicable Federal local by-laws, regulations, a with site specific Health and	rsons granted access airements of Contract A., Provincial, and and ordinances, and

Slipway Reconstruction HEALTH AND SAFETY Section 01 35 29
River of Ponds, NL REQUIREMENTS Page 4
PN: 722303 April 2019

1.6 SITE CONTROL AND ACCESS

- .1 Control the work and entry points to Work Site.
 Approve and grant access only to workers and
 authorized persons.
 - .1 Departmental Representative will provide names of those persons authorized by Departmental Representative to enter onto Work Site and will ensure that such authorized personnel have the required knowledge and training on Health and Safety pertinent to their reason for being at the site, however, Contractor remains responsible for the health and safety of authorized persons while at the Work Site.
- .2 Isolate work site from other areas of the premises by use of appropriate means.
 - .1 Erect fences, hoarding, barricades and temporary lighting as required to effectively delineate the Work Site, stop non-authorized entry, and to protect pedestrians and vehicular traffic around and adjacent to the Work and create a safe environment.
 - .2 Post signage at entry points and other strategic locations indicating restricted access and conditions for access.
 - .3 Use professionally made signs with bilingual message in the 2 official languages or international know graphic symbols.
- .3 Provide safety orientation session to persons granted access to Work site. Advise of hazards and safety rules to be observed while on site.
- .4 Ensure persons granted site access wear appropriate personal protective equipment (PPE). Supply PPE to inspection authorities who require access to conduct tests or perform inspections.
- .5 Secure Work Site against entry when inactive or unoccupied and to protect persons against harm. Provide security guard where adequate protection cannot be achieved by other means.

1.7 PROTECTION

.1 Give precedence to safety and health of persons and protection of environment over cost and schedule considerations for Work.

Slipway Reconstruction River of Ponds, NL PN: 722303		HEALTH AND SAFETY REQUIREMENTS	Section 01 35 29 Page 5 April 2019
1.7 PROTECTION (Cont'd)	.2	Should unforseen or peculiar safety related hazard or condition become evident during performance of work, immediately take measures to rectify the situation and prevent damage or harm. Advise Departmental Representative verbally and in writing.	
1.8 FILING OF NOTICE	.1	File Notice of Project with health and safety authoriti of Work1 Departmental Represent locating address if needed.	es prior to beginning
1.9 PERMITS	.1	Post permits, licenses and certificate, specified in se site.	-
	.2	Where particular permit or cannot be obtained, notify Representative in writing a proceed prior to carrying o of work.	Departmental nd obtain approval to
1.10 HAZARD ASSESSMENTS	.1	Perform site specific healt assessment of the work and	
	.2	Carry out initial assessmen commencementof work with fu needed during progress of w trades and subcontractors a	rther assessments as ork, including when new
	.3	Record results and address Plan.	in Health and Safety
	. 4	Keep documentation on site the Work.	for entire duration of
1.11 PROJECT/SITE CONDITIONS	.1	The following are known or related safety hazards at s .1 The following are know related safety hazards at s .1 Working in close .2 Wet and slippery .3 Inclement weather	ite: n or potential project ite: proximity of water. conditions.

Slipway Reconstruction River of Ponds, NL PN: 722303	n	HEALTH AND SAFETY REQUIREMENTS	Section 01 35 29 Page 6 April 2019
1.11 PROJECT/SITE CONDITIONS (Cont'd)	.1	(Cont'd) .1 (Cont'd) .4 Rock moving activities armour stone5 Heavy equipment activit .6 Heavy lifting7 Working at heights8 Cutting tools and other power tools9 Overhead and undergroun lines10 Risk of electric shock11 Vehicular and pedestria .12 Hot/cold temperature ex13 Work with hazardous pro-	construction d power/utility in traffic.
	. 2	Above list shall not be construed complete and inclusive of potenti safety hazards encountered during	al health, and
	.3	Include above items into hazard a process.	ssessment
	. 4	MSDS Data sheets of pertinent haz controlled products stored on sit from Departmental Representative.	e can be obtained
1.12 MEETINGS	.1	Attend pre-construction health and convened and chaired by Department Representative, prior to commence time, date and location determined Representative. Ensure attendance of Superintendent of work. 2 Designated Health and Safety Representative. 3 Subcontractors.	tal ement of Work, at ed by Departmental e of:
	.2	Conduct regularly schedule tool be meetings during the work in confooccupational Health and Safety Re	rmance with
	. 3	Keep documents on site.	
1.13 HEALTH AND SAFETY PLAN	.1	Prior to commencement of Work, de Health and Safety Plan specific to Implement, maintain, and enforce duration of Work and until final from site.	to the work. Plan for entire

Slipway Reconstruction HEALTH AND SAFETY Section 01 35 29
River of Ponds, NL REQUIREMENTS Page 7
PN: 722303 April 2019

1.13 HEALTH AND SAFETY PLAN (Cont'd)

- .2 Health and Safety Plan shall include the following components:
 - .1 List of health risks and safety hazards identified by hazard assessment.
 - .2 Control measures used to mitigate risks and hazards identified.
 - .3 On-Site Contingency and Emergency Response Plan as specified below.
 - .4 On-Site Communications Plan as specified below.
 - .5 Name of Contractor's designated Health & Safety Site Representative and information showing proof of his/her competence and reporting relationship in Contractor's company.
 - .6 Names, competence and reporting relationship of other supervisory personnel used in the Work for occupational health and safety purposes.
- .3 On-site Contingency and Emergency Response Plan shall include:
 - .1 Operational Procedures, evacuation measures and communication process to be implemented in the event of an emergency.
 - .2 Evacuation Plan: site and floor plan layouts showing escape routes, marshaling areas. Details on alarm notification methods, fire drills, location of fire fighting equipment and other related data.
 - .3 Name, duties and responsibilities of persons designated as Emergency Warden(s) and deputies.
 - .4 Emergency Contacts: name and telephone number of officials from:
 - .1 General Contractor and subcontractors.
 - .2 Pertinent Federal and Provincial Departments and Authorities having jurisdiction.
 - .3 Local emergency resource organizations.
 - .5 Harmonize Plan with Facility's Emergency Response and Evacuation Plan. Departmental Representative will provide pertinent data including name or DFO and Facility Management Contacts.
- .4 On-site Communication Plan:
 - .1 Procedures for sharing of work related safety information to workers and subcontractors, including emergency and evacuation measures.
 - .2 List of critical work activities to be communicated with Facility manager which have a risk of endangering health and safety of Facility users.

Slipway Reconstruction River of Ponds, NL PN: 722303	n	HEALTH AND SAFETY REQUIREMENTS	Section 01 35 29 Page 8 April 2019
1.13 HEALTH AND .5 SAFETY PLAN (Cont'd) .6	. 5	Address all work activities of those of subcontractors.	the work including
	.6	Review Health and Safety Plan re Work. Update as conditions warra emerging risks and hazards, such trade or subcontractor arrive at	ant to address n as whenever new
	.7	Departmental Representative will writing, where deficiencies or and may request re-submission of correction of deficiencies or co	concerns are noted f the Plan with
• •	. 8	Post copy of Plan and updates, psite.	prominently on work
1.14 SAFETY . SUPERVISION	. 1	Employ Health & Safety Site Representation of the Work.	
	.2	Health & Safety Site Representate Superintendent of the Work or of designated by Contractor and sharesponsibility and authority to: .1 Implement, monitor and enforcempliance withy health and safethe Work2 Monitor and enforce Contractive-specific Health and Safety3 Conduct site safety orients persons granted access to Work and Ensure that persons allowed knowledgeable and trained in heapertinent of their activities are escorted by a competent person site5 Stop the Work as deemed need of health and safety.	ther person all be assigned the orce daily ety requirements of ctor's Plan. ation session to Site. d site access are alth and safety t the site of are while on the Work
	. 3	Health & Safety Site Representation. 1 Be qualified and competent occupational health and safety. 2 Have site-related working to activities of the Work. 3 Be on Work Site at all time of the Work. 4 All supervisory personnel and Work shall also be competent personnel. 5 Inspections:	person in experience specific es during execution assigned to the

Slipway Reconstructi River of Ponds, NL PN: 722303	on	HEALTH AND SAFETY REQUIREMENTS	Section 01 35 29 Page 9 April 2019
1.14 SAFETY SUPERVISION (Cont'd)	.3	(Cont'd) .5 (Cont'd) .1 Conduct regularly schedinspections of the Work on a bi-weekly basis. Record defiremedial action taken2 Conduct formal inspection monthly basis. Use standardinspection forms. Distribute subcontractors3 Follow-up and ensure comeasuresare taken6 Cooperate with Facility's Od and Safety representative should by Departmental Representative7 Keep inspection reports and related documentation on site.	a minimum iciencies and lons on a minimum ized safety e to crrective ccupational Health one be designated
1.15 TRAINING	.1	Use only skilled workers on Work effectively trained in occupation safety procedures and practices passigned task.	nal health and
	.2	Maintain employee records and ever received. Make data available to Representative upon request.	-
	.3	When unforeseen or peculiar safet or condition occur during perform follow procedures in place for Er Refuse Work in accordance with Ac Regulations of Province having justified advise Departmental Representative writing.	mance or Work, mployee's Right to cts and urisdiction and
1.16 MINIMUM SITE SAFETY RULES	.1	Notwithstanding the requirement of federal and provincial health and regulations, ensure the following rules are obeyed by persons grant site: .1 Wear appropriate personnel pequipment (PPE) pertinent to the task; minimum being hard hat, satisfiety glasses and hearing protect. 2 Immediately report unsafe conear-miss accident, injury and data. 3 Maintain site and storage at condition free of hazards causing. 4 Obey warning signs and safe	d safety g minimum safety ted access to Work protective work or assigned fety footwear, ction. ondition at site, amage. reas in a tidy g injury.

Slipway Reconstructi River of Ponds, NL PN: 722303	lon	HEALTH AND SAFETY REQUIREMENTS	Section 01 35 29 Page 10 April 2019
1.16 MINIMUM SITE SAFETY RULES (Cont'd)	.2	Brief persons of disciplina taken for non-compliance. F	
1.17 CORRECTION OF .1 NON-COMPLIANCE		Immediately address health non-compliance issues ident having jurisdiction or by I Representative.	tified by authority
	.2	Provide Departmental Representation taken to of action taken to of health and safety issues	correct non-compliance
	.3	Departmental Representative non-compliance of health ar not corrected in a timely m	nd safety regulations is
1.18 INCIDENT REPORTING	.1	Investigate and report the Departmental Representative .1 Incidents requiring no Provincial Department of Och Health, Workers Compensation regulatory Agency2 Medical aid injuries3 Property damage in exc4 Interruptions to Facilities resulting in an operational Department in excess of \$500	e: Otification to Occupational Safety and On Board or to other Cess of \$10,000.00. Lity operations Loss to a Federal
	.2	Submit report in writing.	
1.19 HAZARDOUS PRODUCTS	.1	Comply with requirements of Materials Information Syste	
	.2	Keep MSDS data sheets for a to site. .1 Post on site. .2 Submit copy to Departm	-
1.20 TOOLS AND EQUIPMENT SAFETY	.1	Routinely check and maintai machinery for safe operation	
	.2	Conduct checks as part of s When requested, submit prod maintenance have been carri	of that checks and

Slipway Reconstructi River of Ponds, NL PN: 722303	on	HEALTH AND SAFETY REQUIREMENTS	Section 01 35 29 Page 11 April 2019
1.20 TOOLS AND EQUIPMENT SAFETY (Cont'd)	.3	Tag and immediately remove from faulty or defective.	site items found
1.21 BLASTING .1		Blasting or other use of explosi permitted on site without prior permission and instructions from Representative.	receipt of written
	.2	Do blasting operations in accordand provincial codes.	ance with local
1.22 POWDER ACTUATED DEVICES	.1	Use powder actuated fastening de receipt of written permission fr Representative.	-
1.23 CONFINED .:	.1	Abide by occupational health and regulations regarding work in co	-
	.2	Obtain an Entry Permit in accord of the Canada Occupational Healt Regulations for entry into an exconfined space located at the Fa of Work. 1 Obtain permit from Facility. 2 Keep copy of permit issued. 3 Safety for Inspectors: 1 Provide PPE and training Representative and other permit inspections. 2 Be responsible for efficient and safety of persons during occupancy in the confined seconds.	ch and Safety disting identified acility of premises Manager. Ing to Departmental ersons who require to perform Gicacy of equipment ag their entry and
1.24 SITE RECORDS	.1	Maintain on work site a copy of documentation and reports stipul produced in compliance with Acts of authorities having jurisdicti documents specified herein.	ated to be and Regulations
	.2	Upon request, make available to Representative, or authorized sainspection.	=

Slipway Reconstruct River of Ponds, NL PN: 722303	ion	HEALTH AND SAFETY REQUIREMENTS	Section 01 35 29 Page 12 April 2019
DOCUMENTS S: P1 .2 Pc in		Ensure applicable items, a orders are posted in conspisite in accordance with Accordance having jurisdict:	picuous location on Work cts and Regulations of
		Post other documents as spincluding: .1 Site specific Health .2 WHMIS data sheets.	
1.26 DIVING .1 OPERATIONS	.1	All diving work to comply requirements of CSA Z275.2 Safety Code for Diving Ope "Competency Standards for CSA Z180.1-13, "Compressed Systems."	2-11, "Occupational erations", CSA Z275.4-12, Diving Operations" and
.3		Dive personnel must meet requirements of the CSA ZZ must possess a valid Categor an Unrestricted Surface	275.4-12 and all divers gory 1 Diving Certificate
		Diving in free-swim mode work site.	is not permitted at the
	. 4	Divers must have a current validated medical examination	- · · · - · · · · · · · · · · · · · · ·

a licensed Diving Physician in Newfoundland and Labrador who is knowledgeable and competent in diving and hyperbaric medicine, for all dives.

PART 1 - GENERAL

1.1 RELATED SECTIONS

.1 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

1.2 DEFINITIONS .1

.1 Hazardous Material: Product, substance, or organism that is used for its original purpose; and that is either dangerous goods or a material that may cause adverse impact to the environment or adversely affect health of persons, animals, or plant life when released into the environment.

1.3 FIRES

.1 Fires and burning of rubbish on site are not permitted.

1.4 DISPOSAL OF WASTES AND HAZARDOUS MATERIALS

- .1 All creosote/CCA or preservative treated timber obtained from the demolition of the existing structure is to be transported and disposed of at an approved Waste Disposal Facility and in accordance with applicable federal/provincial and municipal legislation and regulations. Refer to Appendix A Project Effects Determination Report.
- .2 Reuse/storage of creosote/CCA or preservative treated timbers outside of the work site is strictly prohibited.
- .3 Dispose of construction waste materials and demolition debris, resulting from work, at approved landfill sites only. Carryout such disposal in strict accordance with provincial and municipal rules and regulations. Separate out and prevent improper disposal of items banned from landfills.
- .4 Do not bury rubbish and waste materials on site.
 Dispose at approved landfill sites as specified in
 Section 01 74 21 Construction/Demolition Waste
 Management and Disposal.
- .5 Do not dispose of hazardous waste or volatile materials, such as mineral spirits, paints, thinners, oil or fuel into waterways, storm or sanitary sewers or waste landfill sites.

Slipway Reconstruction	ENVIRONMENTAL PROCEDURES	Section 01 35 43
River of Ponds, NL		Page 2
PN: 722303		April 2019

1.4 DISPOSAL OF WASTES AND HAZARDOUS MATERIALS (Cont'd)

- .6 Store, handle and dispose of hazardous materials and hazardous waste in accordance with applicable federal and provincial laws, regulations, codes and guidelines.
- .7 Establish methods and undertake construction practices which will minimize waste and optimize use of construction materials. Separate at source all construction waste materials, demolition debris and product packaging and delivery containers into various waste categories in order to maximize recycling abilities of various materials and avoid disposal of debris at landfill site(s) in a "mixed state". Where recycling firms, specializing in recycling of specific materials exist, transport such materials to the recycling facility and avoid disposal at landfill sites.
- Communicate with landfill operator prior to commencement of work, to determine what specific construction, demolition and renovation waste materials have been banned from disposal at the landfill and at transfer stations.

1.5 DRAINAGE

- .1 Provide temporary drainage and pumping as necessary to keep excavations and site free from water.
- .2 Do not pump water containing suspended materials into waterways, sewer or drainage systems.
- .3 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with governing regulations and requirements.
- .4 Pumped water must meet applicable federal, provincial, and municipal standards before it can be discharged to a surface water body. If regulatory guidelines exceedences are noted, the Departmental Representative has the right to issue stop pumping instructions to the Contractor. Contractor will not be compensated for any delays associated with retrofitting equipment to meet guidelines.
- .5 Provide control devices such as filter fabrics, sediment traps and settling ponds to control drainage and prevent erosion of adjacent land.

 Maintain in good order for duration of work.

Slipway Reconstruction River of Ponds, NL		ENVIRONMENTAL PROCEDURES	Section 01 35 43 Page 3
PN: 722303			April 2019
1.6 PERMIT	.1	All guidelines and instruction must be strictly adhered to.	ns stated on permits
1.7 WORK ADJACENT TO WATERWAYS	. 1	Do not operate construction ed waterways.	quipment in
	.2	Do not use waterway beds for k	oorrow material.
	.3	Do not dump excavated fill, wadebris in waterways.	aste material or
	. 4	At borrow sites, design and cocrossings to minimize erosion strict conformance with proving environmental regulations.	to waterways in
	.5	Do not skid logs or construct: waterways.	ion materials across
	.6	Do not refuel any type of equal of a water body. Maintain equal working condition with no flue or fittings.	ipment in good
1.8 POLLUTION CONTROL	.1	Maintain temporary erosion and features installed under this	
	.2	Control emissions from equipme local authorities' emission re	-
	.3	Prevent sandblasting and other materials from contaminating a application area, by providing enclosures.	air beyond
	. 4	Cover or wet down dry material prevent blowing dust and debricontrol for temporary roads and construction site.	is. Provide dust
	.5	Maintain inventory of hazardou hazardous waste stored on site product name, quantity and dat	e. List items by

began.

Slipway Reconstruction River of Ponds, NL PN: 722303		ENVIRONMENTAL PROCEDURES	Section 01 35 43 Page 4 April 2019
1.8 POLLUTION CONTROL (Cont'd)	. 6	Have emergency spill response clean-up kit, appropriate to adjacent to work and where has stored. Provide personal proterequired for clean-up.	work, at site. Locate zardous materials are
	.7	Report, to Federal and Province the Environment, spills of perhaps hazardous materials as well as potential of polluting the environment, performental Representative within 24 hours.	troleum and other s accidents having vironment. Also ative and submit a tmental
	.8	Provide a floating debris conwhenever any of the Contractorallow for the potential of floating	rs methods of work
1.9 WILDLIFE PROTECTION	.1	Should nests of migratory birduring work, immediately noting Representative for directives on the control of the control of the complete complete commendations of Canadian Western Canadian Ca	fy Departmental to be followed. and neighbouring completed. y adjacent to such ted. ollowing

PART 1 - GENERAL

1.1 SECTION INCLUDES

- .1 Inspection and testing, administrative and enforcement requirements.
- .2 Tests and mix designs.
- .3 Mock-ups.
- .4 Mill tests.
- .5 Equipment and system adjust and balance.

1.2 RELATED SECTIONS

- .1 Section 01 33 00 Submittal Procedures.
- .2 Section 01 78 00 Closeout Submittals.

1.3 INSPECTION

- .1 Facilitate Departmental Representative's access to Work. If part of Work is being fabricated at locations other than construction site, make preparations to allow access to such Work whenever it is in progress.
- .2 Give timely notice requesting inspection of Work designated for special tests, inspections or approvals by Departmental Representative or by inspection authorities having jurisdiction.
- .3 If Contractor covers or permits to be covered Work designated for special tests, inspections or approvals before such is made, uncover Work until particular inspections or tests have been fully and satisfactorily completed and until such time as Departmental Representative gives permission to proceed. Pay costs to uncover and make good such Work.
- .4 In accordance with the General Conditions,
 Departmental Representative may order part of Work
 to be examined if Work is suspected to be not in
 accordance with Contract Documents.

Slipway Reconstruction	QUALITY CONTROL	Section 01 45 00
River of Ponds, NL		Page 2
PN: 722303		April 2019

1.4 INDEPENDENT INSPECTION AGENCIES

. 1

- Departmental Representative will engage and pay for service of Independent Inspection and Testing Agencies for purpose of inspecting and testing portions of Work except for the following which remain part of Contractor's responsibilities:
 - .1 Inspection and testing required by laws, ordinances, rules, regulations, or orders of public authorities.
 - .2 Inspection and testing performed exclusively for Contractor's convenience.
 - .3 Testing, adjustment and balancing of conveying systems, mechanical and electrical equipment and systems.
 - .4 Mill tests and certificates of compliance.
 - .5 Tests as specified within various sections designated to be carried out by Contractor under the supervision of Departmental Representative.
 - .6 Additional tests specified in Clause 1.4.2.
- .2 Where tests or inspections by designated Testing Agency reveal work not in accordance with contract requirements, Contractor shall pay costs for additional tests or inspections as Departmental Representative may require to verify acceptability of corrected work.
- .3 Employment of inspection and testing agencies by Departmental Representative does not relax responsibility to perform Work in accordance with Contract Documents.

1.5 ACCESS TO WORK

- .1 Furnish labour and facility to provide access to the work being inspected and tested.
- .2 Co-operate to facilitate such inspections and tests.
- .3 Make good work disturbed by inspections and tests.

1.6 PROCEDURES

.1 Notify Departmental Representative sufficiently in advance of when work is ready for tests, in order for Departmental Representative to make attendance arrangements with Testing Agency. When directed by Departmental Representative, notify such Agency directly.

Slipway Reconstruct: River of Ponds, NL PN: 722303	ion	QUALITY CONTROL	Section 01 45 00 Page 3 April 2019
1.6 PROCEDURES (Cont'd)	.2	Submit representative samples specified to be tested. Delive quantities to Testing Agency. reasonable promptness and in a so as not to cause delay in Wo	er in required Submit with an orderly sequence
	.3	Provide labour and facilities samples on site. Provide suffifor Testing Agency's exclusive equipment and cure test sample	cient space on site use to store
1.7 REJECTED WORK	.1	Remove and replace defective Woof poor workmanship, use of deproducts and whether incorporate which has been identified by Representative as failing to Concomments.	efective or damaged ated in Work or not, Departmental
	.2	Make good damages to existing including work of other Contraremoval or replacement of defe	acts, resulting from
1.8 TESTING BY CONTRACTOR	.1	Provide all necessary instrumed qualified personnel to perform Contractor's responsibilities in the Contract Documents.	n tests designated as
	.2	At completion of test, turn or documented test reports to Dep Representative. Additionally, in sufficient quantities to erset of test reports to be place maintenance manuals specified of Closeout Submittals.	partmental obtain other copies nable one complete ced in each of the
	.3	Submit mill test certificates certificates as specified in v	
	. 4	Furnish test results and mix of in various sections.	designs as specified
1.9 MOCK-UPS	.1	Prepare mock-ups for Work specin various trade sections. Incall related work components refinal assembly.	clude in each mock-up

Slipway Reconstruction	QUALITY CONTROL	Section 01 45 00
River of Ponds, NL		Page 4
PN: 722303		April 2019

1.9 MOCK-UPS (Cont'd)

- .2 Construct in locations acceptable to Departmental Representative.
- .3 Prepare mock-ups for Departmental Representative's review with reasonable promptness and in orderly sequence, so as not not to cause any delay in Work.
- .4 Failure to prepare mock-ups in ample time is not considered sufficient reason for extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .5 If requested, Departmental Representative will assist in preparing schedule fixing dates for preparation.
- .6 Remove mock-up at conclusion of Work or when acceptable to Departmental Representative unless approval is given to remain as part of Work.

Slipway Reconstruction River of Ponds, NL PN: 722303		TEMPORARY FACILITIES	Section 01 50 00 Page 1 April 2019	
PART 1 - GENERAL	-			
1.1 ACCESS .1		Provide and maintain adequate site.	access to project	
	.2	Maintain access roads for dura make good damage resulting fro		
1.2 CONTRACTOR'S SITE OFFICE	.1	Be responsible for and provide required, including electricit telephone. Locate site office Departmental Representative.	ty, heat, lights and	
1.3 DEPARTMENTAL .1 REPRESENTATIVE'S SITE OFFICE		Provide or construct a separatuse of the Departmental Representative. The building representative of work.	sentative and the Site	
	.2	Provide heating system to main temperature at -20°C outside to		
	.3	The building will be approximated 3600 mm. It will have a suitable a weatherproof siding and line other approved material. The statick material. It will be provided with at least 1 m² of growide at least 0.5 m² of screen door will be fitted with a local screen and the statement of the screen and the statement of the screen and the statement of the screen and the screen are screen as a screen and the screen are screen as a screen as a screen and the screen are screen as a screen are screen as a	ole frame covered with ed with plywood or floor will be of 19 mm ovided with suitable class and arranged to be eened opening. The	

The office will be equipped with a drafting chair and a 900 mm x 1500 mm table having a hinged, smooth

Install electrical lighting system to provide minimum 750 lux using surface mounted, shielded commercial fixtures with 10% upward light component.

wooden top suitable for drafting.

Maintain office in clean condition.

.5

Slipway Reconstruction River of Ponds, NL PN: 722303		TEMPORARY FACILITIES	Section 01 50 00 Page 2 April 2019
1.3 DEPARTMENTAL .7 REPRESENTATIVE'S SITE OFFICE(Cont'd)		Arrange and pay for telephone, facsimile machine in the Departmentative's Office for Stexclusive use. Long distance on this phone by the Departmental Representative will Departmental Representative.	rtmental ite Representative's calls or faxes placed ntal Representative or
	.8	Contractor may, on approval of Representative, provide cellular approval to use cellular or mobe responsible for all service and network access fees, and a charges required to utilize the manufacturer.	lar or mobile phone. If obile phone is granted, es, airtime, license all other fees or
1.4 SANITARY FACILITIES	.1	Provide sanitary facilities for accordance with governing regularization ordinances.	
	.2	Post notices and take such proby local health authorities. In sanitary condition.	-
1.5 POWER	.1	Arrange, pay for and maintain power supply in accordance with regulations and ordinances.	
	.2	Supply and install all temporations power such as pole lines and approval of local power supply	underground cables to
1.6 WATER SUPPLY	.1	Arrange, pay for and maintain in accordance with governing ordinances.	
1.7 SCAFFOLDING	.1	Design, construct and maintain secure and safe manner in according (R2014).	
	.2	Erect scaffolding independent no longer required.	of walls. Remove when

Slipway Reconstruction River of Ponds, NL		TEMPORARY FACILITIES	Section 01 50 00 Page 3
PN: 722303			April 2019
1.8 CONSTRUCTION SIGN AND NOTICES	.1	Contractor or subcontractor are not permitted on site.	advertisement signboards
.2		Only notices of safety or instructions are permitted on site.	
	.3 Safety and Instruction Signs and Notices: .1 Signs and notices for safety and instruction shall be in both official languages. Graphic shall conform to CAN/CSA-Z321-96 (R2006).		safety and instruction anguages. Graphic symbols
	. 4	Maintenance and Disposal of .1 Maintain approved signs condition for duration of posite on completion of project by Departmental Representation.	s and notices in good roject and dispose of off ct or earlier if directed
1.9 REMOVAL OF TEMPORARY FACILITIES	.1	Remove temporary facilities by Departmental Representat	i de la companya del companya de la companya del companya de la co

Slipway Reconstruction River of Ponds, NL PN: 722303		TEMPORARY BARRIERS AND ENCLOSURES	Section 01 56 00 Page 1 April 2019
PART 1 - GENERAL			
1.1 SECTION INCLUDES	.1	Barriers.	
:	.2	Traffic Controls.	
1.2 INSTALLATION AND REMOVAL	.1	Provide temporary controls in o expeditiously.	order to execute Work
	.2	Remove from site all such work	after use.
1.3 HOARDING	.1	Erect temporary site enclosures 2.4 m long welded wire galvaniz end post of 32 mm dia. galvaniz shall have a "hook" end of clam the top of the adjoining panel base plate of 12 ga. galvanized double "stems" to engage and su ends.	red mesh panel with red tubes. Each panel up system to engage post. Panel support is steel plate with
	.2	Provide (2) swing frame gates us tube 50 mm and vertical and hor frame wire mesh to match fence to structurally support all gate deformation gravity system that Provide one drop bar to secure and padlock for night security. to Departmental Representative.	rizontal bars rigid panels. Provide hinge es without is self-latching. in closed position Keys to be supplied
	.3	Secure fencing at established be property lines as shown on draw determined by Departmental Represses plates to ground with 15 men plate) lag screws placed in After removal, fill holes with	rings and/or resentative. Second nm x 250 mm long (2 nto existing asphalt.
1.4 GUARD RAILS AND BARRICADES	.1	Provide secure, rigid guard rai	ls and barricades
	.2	Provide barricades along wharf wheelguard is not in place.	structure when

Provide as required by governing authorities.

.3

Slipway Reconstruction River of Ponds, NL PN: 722303		TEMPORARY BARRIERS AND ENCLOSURES	Section 01 56 00 Page 2 April 2019
1.5 ACCESS TO SITE .1		Provide and maintain access to adjacent harbour facilities.	
1.6 PUBLIC TRAFFIC FLOW	.1	Provide and maintain competent signal flag operators, traffic signals, barricades and flare lights, or lanterns as required to perform Work protect the public.	
1.7 FIRE ROUTES	.1	Maintain access to property inc clearances for use by emergency	_
1.8 PROTECTION FOR .1 OFF-SITE AND PUBLIC PROPERTY .2		Protect surrounding private and damage during performance of Wo	
		Be responsible for damage incur	red.

Slipway Reconstructi	on	INSPECTOR'S CAMP AND BOARD	Section 01 59 20	
River of Ponds, NL			Page 1	
PN: 722303			April 2019	
PART 1 - GENERAL				
		•		
1.1 DESCRIPTION	. 1	This section specifies requirem		
		lodgings and related services to be provided by the Contractor for the Inspector.		
		contractor for the inspector.		
	.2	Due to the location of this sit		
		requirement of this contract th		
		provide and pay for all board a	= = =	
		Inspector's sole use for the du project. Provide for and mainta		
		accommodations for the Inspecto	_	
		minimum requirement would be a		
		with private sleeping accommoda		
		bath or other arrangement appro	ved by the Inspector.	
1.2 BOARD AND	.1	For the purpose of this contrac	t board and lodgings	
LODGINGS		shall include but not necessari	=	
		sleeping accommodation, meals a		
		<pre>washroom facilities, laundry fa and heating service, linens and</pre>		
		any reasonable service as direct	<u> </u>	
		_	-	
	.2	Board and lodgings must be appr		
		and Contractor will cooperate i		
		services required to maintain a of living during construction p		
	-	of fiving during construction p	errod.	
	.3	The Contractor shall include al	l calendar days,	
		including weekends and statutor		
•		determining the cost.		
1.3 REQUIREMENTS OF	.1	Comply with any or all applicab		
REGULATORY AGENCIES		regulation of the Province of N	ewfoundland and	

PAYMENT

1.4 MEASUREMENT FOR .1

No measurement for payment to be made under this section including all cost of this section in the lump sum items of this contract.

Labrador, relating to the set up, servicing and maintenance of accommodations for the Inspector.

Climan Demonstration	COMMON PROPRIES PROMERRIAN	TC C1 C1 C2
Slipway Reconstruction	COMMON PRODUCT REQUIREMEN	TS Section 01 61 00
River of Ponds, NL		Page 1
PN: 722303		April 2019

PART 1 - GENERAL

1.1 GENERAL

- .1 Use new material and equipment unless otherwise specified.
- .2 Within 7 days of written request by Departmental Representative, submit following information for any materials and products proposed for supply:
 - .1 name and address of manufacturer;
 - .2 trade name, model and catalogue number;
 - .3 performance, descriptive and test data;
 - .4 manufacturer's installation or application instructions;
 - .5 evidence of arrangements to procure;
 - .6 evidence of manufacturer delivery problems or unforseen delays.
- .3 Provide material and equipment of specified design and quality, performing to published ratings and for which replacement parts are readily available.
- .4 Use products of one manufacturer for equipment or material of same type or classifications unless otherwise specified.
- .5 Permanent labels, trademarks and nameplates on products are not acceptable in prominent locations, except where required for operating instructions, or when located in mechanical or electrical rooms.

1.2 PRODUCT QUALITY .1 AND REFERENCED STANDARDS

- 1 Contractor shall be solely responsible for submitting relevant technical data and independent test reports to confirm whether a product or system proposed for use meets contract requirements and specified standards.
- .2 Final decision as to whether a product or system meets contract requirements rest solely with the Departmental Representative in accordance with the General Conditions.

1.3 ACCEPTABLE MATERIALS AND ALTERNATIVES

.1 Acceptable Materials: When materials specified include trade names or trade marks or manufacturer's or supplier's name as part of the material description, select and only use one of the names listed for incorporation into the Work.

Slipway Reconstruction River of Ponds, NL PN: 722303		COMMON PRODUCT REQUIREMENTS	Section 01 61 00 Page 2 April 2019
1.3 ACCEPTABLE MATERIALS AND ALTERNATIVES (Cont'd)	MND materials to trade names or manufacturer's names specified must be done during the bidding period		facturer's names e bidding period
	.3	Substitutions: After acceptance of a specified material will be change to the Work in accorance we Conditions of the Contract.	dealt with as a
1.4 MANUFACTURERS INSTRUCTIONS	,		structions for ds to be used. Do provided with
	.2	Notify Departmental Representative conflict between these specificate manufacturers instructions, so the Representative will designate while be followed.	cions and nat Departmental
1.5 AVAILABILITY	.1	Immediately notify Departmental E writing of unforseen or unanticip delivery problems by manufactures documentation as per Clause 1.1.2	pated material . Provide support
1.6 WORKMANSHIP .1		Ensure quality of work is of high executed by workers experienced a respective duties for which they	and skilled in
		Remove unsuitable or incompetent workers from site as stipulated in General Conditions.	
	.3	Ensure cooperation of workers in Maintain efficient and continuous site at all times.	
	. 4	Coordinate work between trades ar	nd subcontractors.
	.5	Coordinate placement of openings, accessories.	sleeves and

Slipway Reconstruct River of Ponds, NL PN: 722303	ion	COMMON PRODUCT REQUIREMENTS	Section 01 61 00 Page 3 April 2019
1.7 FASTENINGS - GENERAL	.1	1 Provide metal fastenings and accessories in texture, colour and finish as base metal in they occur. Prevent electrolytic action betw dissimilar metals. Use non-corrosive fastene anchors and spacers for securing exterior wo in humid areas.	
	.2	Space anchors within limits of capacity and ensure that they p permanent anchorage. Wood or or not acceptable.	provide positive
	.3	Keep exposed fastenings to mini lay out neatly.	mum, space evenly and
	. 4	Fastenings which cause spalling material to which anchorage is acceptable.	
	.5	Do not use explosive actuated funless approved by Departmental Section 01 35 29 - Health and Sthis regard.	Representative. See
1.8 FASTENINGS EQUIPMENT	.1	Use fastenings of standard comm patterns with material and fini service.	
	.2	Use heavy hexagon heads, semi-footherwise specified.	finished unless
	.3	Bolts may not project more than nuts.	n one diameter beyond
	. 4	Use plain type washers on equip soft gasket lock type washers w occur. Use resilient washers wi	where vibrations
1.9 STORAGE, HANDLING AND PROTECTION	.1	Deliver, handle and store mater prevent deterioration and soili with manufacturer's instruction	ing and in accordance
	.2	Store packaged or bundled mater undamaged condition with manufalabels intact. Do not remove from bundling until required in Work cover where manufacturer's pack to provide adequate protection.	acturer's seal and com packaging or c. Provide additional caging is insufficient

Slipway Reconstruction River of Ponds, NL PN: 722303		COMMON PRODUCT REQUIREMENTS	Section 01 61 00 Page 4 April 2019
1.9 STORAGE, .3 HANDLING AND PROTECTION		Store products subject to damage weatherproof enclosures.	ge from weather in
(Cont'd)	4	Store cementitious products cle concrete floors, and away from	
	.5	Keep sand, when used for grout or mortar materials, clean and dry. Store sand on wooden platforms and cover with waterproof tarpaulins during inclement weather.	
	.6	Store sheet materials and lumbe supports and keep clear of groumoisture.	*
	.7	Store and mix paints in heated Remove oily rags and other comb site daily. Take every precauts prevent spontaneous combustion	oustible debris from ion necessary to
	.8.	Immediately remove damaged or a from site.	rejected materials
. 9		Touch-up damaged factory finish Departmental Representative's stouch-up materials to match or: over name plates.	satisfaction. Use

Slipway Reconstruction River of Ponds, NL PN: 722303		CLEANING	Section 01 74 11 Page 1 April 2019
PART 1 - GENERAL			
1.1 GENERAL	.1	Conduct cleaning and disposal op with local ordinaces and anti-po	
	.2	Store volatile waste in covered metal containers, and remove from premises at end of each working day.	
	.3	Prevent accumulation of wastes w hazardous conditions.	hich create
	. 4	Provide adequate ventilation dur or noxious substances.	ing use of volatile
1.2 MATERIALS	.1	Use only cleaning materials recommanufacturer of surface to be cleaning material	eaned, and as
1			
1.3 CLEANING DURING CONSTRUCTION	.1	Maintain project grounds and pub tidy condition, free from accumu material and debris. Clean areas	lations of waste
	.2	Provide on-site garbage containe waste materials and debris.	rs for collection of
	.3	Remove waste materials and debri daily basis.	s from site on a
1.4 FINAL CLEANING	.1	In preparation for acceptance of final cleaning.	the Work perform

- final cleaning.
- Inspect finishes, fitments and equipment. Ensure .2 specified workmanship and operation.
- Broom clean exterior paved and concrete surfaces; rake clean other surfaces of grounds.

Slipway Reconstruction River of Ponds, NL PN: 722303		CONSTRUCTION/DEMOLITION WASTE MANAGEMENT AND DISPOSAL	Section 01 74 21 Page 1 April 2019
PART 1 - GENERAL			
1.1 RELATED SECTIONS	.1	Section 01 35 43 - Environmental	Procedures.
BHOLLOND	.2	Section 02 41 16 - Sitework, Dem	olition and Removal.
1.2 WASTE MANAGEMENT PLAN	.1	Prior to commencement of work, p Management Workplan.	repare waste
	.2	Workplan to include: .1 Waste audit2 Waste reduction practices3 Material source separation .4 Procedures for sending recy facilities5 Procedures for sending non- and waste to approved waste proc landfill site6 Training and supervising wo management at site.	clables to recycling salvageable items essing facility or
	.3	Workplan to incorporate waste marequirements specified herein and of the Specifications.	-
	. 4	Develop Workplan in collaboration subcontractors to ensure all was and opportunities are addressed.	te management issues
1.3 WASTE AUDIT .1		At project start-up, conduct was .1 Site conditions identifying non-salvageable items and waste demolition and removal work2 Projected waste resulting for packaging and from material left installation work.	salvageable and resulting from from
	.2	Develop written list. Record typ quantity of various salvageable anticipated, reasons for waste g operational factors which contri	items and waste generation and
1.4 WASTE REDUCTION	.1	Based on waste audit, develop wa program.	ste reduction

Slipway Reconstruction	CONSTRUCTION/DEMOLITION	Section 01 74 21
River of Ponds, NL	WASTE MANAGEMENT AND	Page 2
PN: 722303	DISPOSAL	April 2019

1.4 WASTE REDUCTION (Cont'd)

- .2 Structure program to prioritize actions, with waste reduction as first priority, followed by salvage and recycling effort, then disposal as solid waste.
 - .3 Identify materials and equipment to be:
 - .1 Protected and turned over to Departmental Representative when indicated.
 - .2 Salvaged for resale by Contractor.
 - .3 Sent to recycling facility.
 - .4 Sent to waste processing/landfill site for their recycling effort.
 - .5 Disposed of in approved landfill site.
 - .4 Reduce construction waste during installation work.
 Undertake practices which will minimize waste and
 optimize full use of new materials on site, such as:
 - .1 Use of a central cutting area to allow for easy access to off-cuts;
 - .2 Use of off-cuts for blocking and bridging elsewhere.
 - .3 Use of effective and strategically placed facilities on site for storage and staging of left-over or partially cut materials to allow for easy incorporation into work whenever possible avoiding unnecessary waste.
 - .5 Develop other strategies and innovative procedures to reduce waste such as minimizing the extent of packaging used for delivery of materials to site, etc.

1.5 MATERIALS SOURCE SEPARATION PROCESS

- .1 Develop and implement material source separation process at commencement of work as part of mobilization and waste management at site.
- .2 Provide on-site facilities to collect, handle, and store anticipated quantities of reusable, salvageable and recyclable materials.
 - .1 Use suitable containers for individual collection of items based on intended purpose.
 - .2 Locate to facilitate deposit but without hindering daily operations of existing building tenants.
 - .3 Clearly mark containers and stockpiles as to purpose and use.
- .3 Perform demolition and removal of existing components and equipment following a systematic deconstruction process.

Slipway Reconstruction River of Ponds, NL PN: 722303		CONSTRUCTION/DEMOLITION WASTE MANAGEMENT AND DISPOSAL	Section 01 74 21 Page 3 April 2019
1.5 MATERIALS SOURCE SEPARATION PROCESS (Cont'd)	.3	(Cont'd) .1 Separate materials and e carefully dismantling, labell alike items for the following .1 Reinstallation into indicated2 Salvaging resusable project which Contractor parties. Sale of such it site3 Sending as many ite locally available recycl .4 Segregating remaini into various individual disposal in a "non-mixed by waste processing/land	ing and stockpiling purposes: the work where items not needed in may sell to other ems not permitted on ms as possible to ing facility. ng waste and debris waste categories for state" as recommended
	. 4	Isolate product packaging and from general waste stream. Se facility or return to supplie	nd to recycling
	.5	Send leftover material result work for recycling whenever p	-
	.6	Establish methods whereby haz materials, and their containe in the course work are proper site and disposed in accordan and regulations from authorit jurisdiction.	rs, encountered or used ly isolated, stored on ce with applicable laws
	.7	Isolate and store existing ma identified for re-incorporati Protect against damage.	- -
1.6 WORKER TRAINING AND SUPERVISION	.1	Provide adequate training to meetings and demonstrations, and worker responsibilities i Waste Management Plan.	to emphasize purpose

Management Plan to:

.1 work.

Waste Management Coordinator: designate full-time person on site, experienced in waste management and having knowledge of the purpose and content of Waste

Oversee and supervise waste management during

Provide instructions and directions to all

workers and subcontractors on waste reduction,

source separation and disposal practices.

Slipway Reconstruction River of Ponds, NL PN: 722303		CONSTRUCTION/DEMOLITION WASTE MANAGEMENT AND	Section 01 74 21 Page 4
PN: 122303		DISPOSAL	April 2019
1.6 WORKER TRAINING AND SUPERVISION (Cont'd)	.3	Post a copy of Plan in a promin for review by workers.	ent location on site
1.7 CERTIFICATION OF MATERIAL DIVERSION	.1	Submit to Departmental Represent certified weigh bills from authorocessing sites and sale received recycling/reuse facilities confibuilding materials and quantity from landfill.	orized waste pts from Firming receipt of
	.2	Submit data at pre-determined project milestones and determined by Departmental Representative.	
	.3	Compare actual quantities diver with projections made during wa	
1.8 DISPOSAL REQUIREMENTS	.1	All creosote/CCA or preservative obtained from the demoltiion of structure is to be transported approved Waste Disposal Facilitation applicable federal/province legislation and regulations. Reproject Effects Determination	the existing and disposed of at an ay and in association aid and municipal after to Appendix A -
	.2	Reuse/storage of creosote/CCA of treated timbers outside of the prohibited.	-
·	.3	Contact the authority having judicommencement of work, to determ demolition and construction was been banned from disposal in laterals for stations. Take approprisolate such banned materials addispose in strict accordance with municipal regulations.	nine what, if any, ste materials have andfills and at riate action to at site of work and
	. 4	Transport waste intended for la condition, following rules and Landfill Operator in support of divert, recycle and reduce amount placed in landfill.	recommendations of their effort to
	. 5	Dispose of waste only at approve facility or landfill sites approve having jurisdiction.	

Slipway Reconstruction	CONSTRUCTION/DEMOLITION	Section 01 74 21
River of Ponds, NL	WASTE MANAGEMENT AND	Page 5
PN: 722303	DISPOSAL	April 2019

1.8 DISPOSAL REQUIREMENTS (Cont'd)

- .6 Dispose of treated wood, end pieces, wood scraps and sawdust at a sanitary landfill.
- .7 Do not dispose of preservative treated wood through incineration.
- .8 Disposal of waste, volatile materials, mineral spirits, oil, paint, paint thinner or unused perservative material into waterways, storm, or sanitary sewers is prohibited.
- .9 Burying or burning of rubbish and waste materials is prohibited.
- .10 Collect, bundle and transport salvaged materials to be recycled in separated categories and condition as directed by recycling facility. Ship materials only to approved recycling facilities.
- .11 Sale of salvaged items by Contractor to other parties not permitted on site.

Slipway Reconstruction CLOSEOUT SUBMITTALS Section 01 78 00
River of Ponds, NL Page 1
PN: 722303 April 2019

PART 1 - GENERAL

1.1 SECTION INCLUDES

- .1 Project Record Documents as follows:
 - .1 As-built drawings;
 - .2 As-built specifications;
 - .3 Reviewed shop drawings.

1.2 PROJECT RECORD DOCUMENTS

- .1 Departmental Representative will provide two white print sets of contract drawings and two copies of Specifications Manual specifically for "as-built" purposes.
- .2 Maintain at site one set of the contract drawings and specifications to record actual as-built site conditions.
- .3 Maintain up-to-date, real time as-built drawings and specifications in good condition and make available for inspection by the Departmental Representative at any time during construction.
- .4 As-Built Drawings:
 - .1 Record changes in red ink on the prints. Mark only on one set of prints and at completion of project and prior to final inspection, neatly transfer notations to second set (also by use of red ink). Submit both sets to Departmental Representative. All drawings of both sets shall be stamped "As-Built Drawings" and be signed and dated by Contractor.
 - .2 Show all modifications, substitions and deviations from what is shown on the contract drawings or in specifications.
 - .3 Record following information:
 - .1 Horizontal and vertical location of various elements in relation to CHS Chart Datum.
 - .2 Field changes of dimension and detail.
 - .3 All design elevations, sections, and details dimensioned and marked-up to consistently report finished installation conditions.
 - .4 Any details produced in the course of the contract by the Departmental Representative to supplement or to change existing design drawings must also be marked-up and dimensioned to reflect final as-built conditions and appended to the as-built drawing document.

Slipway Reconstruction CLOSEOUT SUBMITTALS Section 01 78 00 River of Ponds, NL Page 2 PN: 722303 April 2019 1.2 PROJECT RECORD (Cont'd) . 4 (Cont'd) .3 DOCUMENTS (Cont'd) All change orders issued over the course of the contract must be documented on the finished as-built documents, accurately and consistently depicting the changed condition as it applies to all affected drawing details. As-built Specifications: legibly mark in red each . 5 item to record actual construction, including: Manufacturer, trade name, and catalogue number of each product actually installed, particularly items substituted from that specified. . 2 Changes made by Addenda and Change Orders. Mark up both copies of specifications; stamp "as-built", sign and date similarly to drawings as per above clause. Maintain As-built documents current as the contract progresses. Departmental Representative will conduct reviews and inspections of the documents on a regular basis. Frequency of reviews will be subject to Departmental Representative's discretion. Failure to maintain as-builts current and complete to satisfaction of the Departmental Representative shall be subject to financial penalties in the form of progress payment reductions and holdback assessments. Record information concurrently with construction . 7 progress. .1 Do not conceal Work until required information is recorded. Provide digital photos, if requested, for site .8 records. 1.3 EQUIPMENT AND For each item of equipment and each system include .1 description of unit or system and component SYSTEMS specifications. .2 Panel board circuit directories: provide electrical service characteristics, controls, and

communication.

Include installed colour coded wiring diagrams.

.3

Slipway Reconstruction River of Ponds, NL		CLOSEOUT SUBMITTALS	Section 01 78 00
			Page 3
PN: 722303		April 2	
1.3 EQUIPMENT AND SYSTEMS (Cont'd)	. 4	Operating Procedures: include and routine normal operating in sequences. 1 Include regulation, control shut-down, and emergency instructions.	nstructions and ol, stopping, uctions.
	.5	Maintenance Requirements: incluprocedures and guide for troubdisassembly, repair, and reasseand alignment, adjusting, balaninstructions.	<pre>le-shooting; embly instructions;</pre>
	.6	Provide servicing and lubrication schedule, and list of lubricants required.	
	.7	Include manufacturer's printed maintenance instructions.	operation and
	.8	Provide original manufacturer's illustrations, assembly drawing required for maintenance.	
	.9	Provide installed control diagramanufacturer.	rams by controls
	.10	Provide list of original manufaparts, current prices, and rect to be maintained in storage.	-
	.11	Additional requirements: as specification section	
1.4 WARRANTIES AND BONDS	.1	Develop warranty management plainformation relevant to Warran	
	.2	Warranty management plan to inactions and documents to assure Representative receives warrantentitled.	e that Departmental
	. 3	Submit Warranty information mag	de available during

- .3 Submit Warranty information made available during construction phase to Departmental Representative for approval prior to each monthly pay estimate.
- .4 Assemble approved information in binder, submit upon acceptance of work and organize binder as follows:
 - .1 Separate each warranty or bond with index tab sheets keyed to Table of Contents listing.

Slipway Reconstruction	CLOSEOUT SUBMITTALS	Section 01 78 00
River of Ponds, NL		Page 4
PN: 722303		April 2019

1.4 WARRANTIES AND .4 BONDS

(Cont'd)

4 (Cont'd)

- .2 List subcontractor, supplier and manufacturer with name, address, and telephone number of responsible principal.
- .3 Obtain warranties and bonds, executed in duplicate by subcontractors, suppliers, and manufacturers, within ten days after completion of applicable item of work.
- .4 Retain warranties and bonds until time specified for submittal.
- .5 Except for items put into use with Owner's permission, leave date of beginning of time of warranty until Date of Substantial Performance is determined.
- .6 Respond in a timely manner to oral or written notification of required construction warranty repair work.

1.5 REVIEWED SHOP DRAWINGS

.1 Compile 2 full sets of all reviewed shop drawings.

Slipway Reconstructi River of Ponds, NL PN: 722303	on	SITEWORK, DEMOLITION AND REMOVAL	Section 02 41 16 Page 1 April 2019
PART 1 - GENERAL			
1.1 RELATED SECTIONS	.1	Section 01 35 43 - Environmental	Procedures.
BECTIONS	.2	Section 01 74 21 - Construction/Demolition Waste Management and Disposal.	
1.2 DESCRIPTION	.1	This section specifies requiremen and removing wholly or in part va designated to be removed or parti	rious items
1.3 GENERAL .1 REQUIREMENTS		A Notice to Shipping is to be issued prior to commencement and upon completion of work.	
	.2	During construction, any vessels must be marked in accordance with the Canada Shipping Act Collision	the provisions of
	.3	Upon completion of the project, a Mariners must be issued.	written Notice to
1.4 PROTECTION .1		Protect existing objects designat event of damage, immediately repl to approval of and at no addition	ace or make repairs
	.2	Place a floating boom around entito prevent loss of any materials.	re demolition site
	.3	Remove all floating debris from w and timely basis.	ater on a routine
1.5 MEASUREMENT FOR PAYMENT	.1	All cost for items in this section in fixed price items including all material required to complete this on drawings and specifications.	l plant, labour,

Slipway Reconstruction SITEWORK, DEMOLITION AND REMOVAL Section 02 41 16
River of Ponds, NL Page 2
PN: 722303 April 2019

PART 3 - EXECUTION

3.1 EXECUTION

- .1 Inspect site and verify with Departmental Representative objects designated for removal.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.

3.2 REMOVAL

- .1 Demolition, removal and disposal of all existing hardwood timber decking members and PT support beams.
- .2 Demolition of all concrete supports and reuse these supports in the backfilling of the new work to be completed.
- .3 Demolition, removal and disposal of existing steel support beams, brackets and associated steel items as indicated on drawings.
- .4 Demolition, removal and disposal of the existing asphalt that is indicated for removal on the accompanying drawings.

3.3 DISPOSAL OF MATERIAL

- .1 All demolished materials, except materials designated to be reused or turned over to owner, will become property of contractor and will be removed from site and disposed of to satisfaction of Departmental Representative and in accordance with environmental guidelines. It is the sole responsibility of the contractor to dispose of all demolished materials at an approved disposal site. Ensure that disposal site is approved and willing to accommodate any materials disposed of from work site. Refer to Sections 01 35 43 Environmental Procedures and Section 01 74 21 Construction/Demolition Waste Management and Disposal for disposal requirements.
- .2 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.

Slipway Reconstruction	SITEWORK,	DEMOLITION	AND	REMOVAL	Section 02 41 16
River of Ponds, NL					Page 3
PN: 722303					April 2019

3.4 RESTORATION

- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.

Slipway Reconstruction	CONCRETE FORMING AND	Section 03 10 00
River of Ponds, NL	ACCESSORIES	Page 1
PN: 722303		April 2019

PART 1 - GENERAL

1.1 RELATED SECTIONS

- .1 Section 03 20 00 Concrete Reinforcing.
- .2 Section 03 30 00 Cast-in-Place Concrete.
- .3 Section 07 92 10 Joint Sealing.

1.2 REFERENCES

- .1 Canadian Standards Association (CSA)
 - .1 CAN/CSA-A23.1-14/A23.2-14, Concrete Materials and Methods of Concrete Construction.
 - .2 CAN/CSA-086-14, Engineering Design in Wood.
 - .3 CSA O121-08 (R2013), Douglas Fir Plywood.
 - .4 CSA 0151-09 (R2014), Canadian Softwood Plywood.
 - .5 CSA O153-M13, Poplar Plywood.
 - .6 CAN3-0188.0-M78, Standard Test Methods for Mat-Formed Wood Particleboards and Waferboard.
 - .7 CSA 0437 Series-93 (R2011), Standards for OSB and Waferboard.
 - .8 CSA S269.1-16, Formwork and Falsework.

1.3 SHOP DRAWINGS

- .1 Submit shop drawings for formwork and falsework in accordance with Section 01 33 00 Submittal Procedures.
- .2 Indicate method and schedule of construction, shoring, stripping and re-shoring procedures, materials, arrangement of joints, special architectural exposed finishes, ties, liners, and locations of temporary embedded parts. Comply with CSA S269.1-16, for falsework drawings Comply with CAN/CSA-S269.1-16 for formwork drawings.
- .3 Indicate formwork design data, such as permissible rate of concrete placement, and temperature of concrete, in forms.
- .4 Indicate sequence of erection and removal of formwork/falsework as directed by Departmental Representative.
- .5 Each shop drawing submission shall bear stamp and signature of qualified Professional Engineer registered or licensed in Province of Newfoundland and Labrador, Canada.

Slipway Reconstruct River of Ponds, NL PN: 722303	ion	CONCRETE FORMING AND ACCESSORIES	Section 03 10 00 Page 2 April 2019
1.4 WASTE MANAGEMENT AND DISPOSAL	.1	Separate and recycle waste mater with Section 01 74 21 - Construct Waste Management and Disposal an Reduction Workplan.	tion/Demolition
	.2	Place materials defined as hazar in designated containers.	dous or toxic waste
	.3	Ensure emptied containers are se safely for disposal away from ch	
•	. 4	Use sealers, form release and stare non-toxic, biodegradable and VOC's.	
PART 2 - PRODUCTS			
2.1 MATERIALS	. 1	Formwork materials: .1 Use formwork materials to C	AN/CSA-A23.1-16.
	.2	Form ties: .1 Removable or snap-off metal adjustable length, free of device larger than 25 mm diameter in co	es leaving holes
. <i>'</i>	.3	Form release agent: non-toxic, or release agents containing compout free lime present in concrete to insoluble soaps, preventing set in contact with form.	nds that react with provide water
	. 4	Falsework materials: to CSA-S269.1 Materials required to bear accompanied with certificates, to proof of conformity.	grade marks, or be
	.5	Premoulded joint fillers: .1 Bituminous impregnated fibe D1751.	rboard to ASTM
	.6	Bond Breaker: .1 Impermeable tube formed of rubber or similar material to the Departmental Representative. Into dowels.	e approval of the

.7 Sealant: to Section 07 92 10 - Joint Sealing.

Slipway Reconstruction CONCRETE FORMING AND Section 03 10 00 River of Ponds, NL ACCESSORIES Page 3 April 2019

PART 3 - EXECUTION

3.1 FABRICATION AND ERECTION

- .1 Verify lines, levels and centres before proceeding with formwork/falsework and ensure dimensions agree with drawings.
- .2 Obtain Departmental Representative's approval for use of earth forms framing openings not indicated on drawings.
- .3 Hand trim sides and bottoms and remove loose earth from earth forms before placing concrete.
- .4 Fabricate and erect falsework in accordance with CSA S269.1-16.
- .5 Fabricate and erect formwork in accordance with CAN/CSA-S269.1-16 to produce finished concrete conforming to shape, dimensions, locations and levels indicated within tolerances required by CAN/CSA-S269.1-16.
- .6 Align form joints and make watertight. Keep form joints to minimum.
- .7 Use 25 mm chamfer strips on external corners and/or 25 mm fillets at interior corners, joints, unless specified otherwise.
- .8 Form chases, slots, openings, drips, recesses, expansion and control joints as indicated.
- .9 Build in anchors, sleeves, and other inserts required to accommodate Work specified in other sections. Assure that all anchors and inserts will not protrude beyond surfaces designated to receive applied finishes, including painting.
- .10 Clean formwork in accordance with CAN/CSA-A23.1/A23.2, before placing concrete.

3.2 REMOVAL AND RESHORING

.1 Leave formwork in place for following minimum periods of time after placing concrete.

.1 5 days, slabs, supports, decks and other structural members, or 3 days when replaced immediately with adequate shoring to standard specified for falsework.

Slipway Reconstruction River of Ponds, NL PN: 722303		CONCRETE FORMING AND ACCESSORIES	Section 03 10 00 Page 4 April 2019	
3.2 REMOVAL AND .2 RESHORING (Cont'd) .3		Remove formwork when concrete design strength or minimum pe whichever comes later, and readequate reshoring.	eriod noted above,	
		Provide all necessary reshoring of members where early removal of forms may be required or where members may be subjected to additional loads during construction as required.		
		Space reshoring in each princ more than 3000 mm apart.	cipal direction at not	
	.5	Re-use formwork and falsework requirements of CAN/CSA-A23.1		
3.3 JOINT FILLERS .1		Locate and form expansion joi Intall joint filler in all jo		
	.2	Use 13 mm thick joint filler slab-on-grade and extend join slab to within 25 mm of finis indicated otherwise.	nt filler from bottom of	
3.4 JOINT SEALANT	.1	Fill expansion and control jomanufacturer instructions.	oints with sealer as per	

Slipway Reconstruction CONCRETE REINFORCING Section 03 20 00 River of Ponds, NL PN: 722303 Page 1 April 2019

PART 1 - GENERAL

1.1 RELATED SECTIONS

- .1 Section 03 10 00 Concrete Forming and Accessories.
- .2 Section 03 30 00 Cast-in-Place Concrete.

1.2 REFERENCES

- .1 American Concrete Institute (ACI)
 - .1 SP-66-04, ACI Detailing Manual 2004.
 - .1 ACI 315-99, Details and Detailing of Concrete Reinforcement.
 - .2 ACI 315R-04, Manual of Engineering and Placing Drawings for Reinforced Concrete Structures.

.2 ASTM International

- .1 ASTM A1064/A1064M-16b, Standard for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete.
- .2 ASTM A143/A143M-07(2014), Standard Practice for Safeguarding Against Embrittlement of Hot-Dip Galvanized Structural Steel Products and Procedure for Detecting Embrittlement.
- .3 ASTM A775/A775M-16, Standard Specification for Epoxy-Coated Reinforcing Steel Bars.
- .4 ASTM-A123/A123M-15, Standard Specification for Zinc (Hot Dip Galvanized) Coatings on Iron and Steel Products.

.3 CSA International

- .1 CSA-A23.1-14/A23.2-14, Concrete Materials and Methods of Concrete Construction/Test Methods and Standard Practices for Concrete.
- .2 CSA-A23.3-14, Design of Concrete Structures.
- .3 CSA G30.18-09, Carbon Steel Bars for Concrete Reinforcement.
- .4 CSA G40.20-13/G40.21-13, General Requirement for Rolled or Welded Structural Quality Steels/Structural Quality Steel.
- .5 CSA W186-M1990 (R2012), Welding of Reinforcing Bars in Reinforced Concrete Construction.
- .4 Reinforcing Steel Institute of Canada (RSIC) .1 RSIC-2004, Reinforcing Steel Manual of Standard Practice.

Slipway Reconstructi River of Ponds, NL PN: 722303	on	CONCRETE REINFORCING	Section 03 20 00 Page 2 April 2019
1.3 ACTION AND INFORMATIONAL SUBMITTALS	.1	Submit in accordance with Section Submittal Procedures.	n 01 33 00 -
		Prepare reinforcement drawings in withRSIC Manual of Standard Pract	
	.3	Shop Drawings: .1 Submit drawings stamped and professional engineer registered Newfoundland and Labrador1 Indicate placing of rei .1 Bar bending detail .2 Lists3 Quantities of reir .4 Sizes, spacings, I reinforcement and mecha approved by Departmenta Representative, with ide marks to permit correct without reference to st drawings5 Indicate sizes, spacings, spangers2 Detail lap lengths and lengths to CSA-A23.3.	or licensed in inforcement and: is. inforcement. inforcement. inforcement inforcement.
1.4 QUALITY ASSURANCE	.1	Submit in accordance with Section Quality Control and as described SOURCE QUALITY CONTROL. 1 Mill Test Report: Upon request Departmental Representative with mill test report of reinforcing sweeks prior to beginning reinforced. Upon request submit in writing Departmental Representative proper reinforcement material to be supported.	in PART 2 - est, provide certified copy of steel, minimum 4 cing work. Ing to esed source of
1.5 DELIVERY, STORAGE AND HANDLING	.1	Deliver, store and handle materia with Section 01 61 00 - Common Pr Requirements and with manufacture instructions.	roduct
	.2	Delivery and Acceptance Requirement materials to site in original fac- labelled with manufacturer's name	ctory packaging,
	.3	Storage and Handling Requirements	s:

Slipway Reconstruction River of Ponds, NL PN: 722303		CONCRETE REINFORCING	Section 03 20 00 Page 3 April 2019
1.5 DELIVERY, STORAGE AND HANDLING (Cont'd)	.3	(Cont'd) .1 Store materials off ground location, and in accordance with recommendations in clean, dry, area2 Replace defective or damainew.	th manufacturer's well-ventilated
1.6 WASTE MANAGEMENT AND DISPOSAL	.1	Separate and recycle waste mat with Section 01 74 21 - Constr Waste Management and Disposal Reduction Workplan.	uction/Demolition
PART 2 - PRODUCTS			
2.1 MATERIALS	.1	Substitute different size bars in writing by Departmental Rep	
	.2	Reinforcing steel: billet stee deformed bars to CAN/CSA-G30.1 otherwise.	
	.3	Reinforcing steel: weldable lo deformed bars to CAN/CSA-G30.1	_
	. 4	Cold-drawn annealed steel wire	ties: to CSA G30.3.
	.5	Welded steel wire fabric: to C flat sheets only.	SA G30.5. Provide in
	.6	Chairs, bolsters, bar supports CAN/CSA-A23.1.	, spacers: to
	.7	Mechanical splices: subject to Departmental Representative.	approval of
2.2 FABRICATION	.1	Fabricate reinforcing steel in CAN/CSA-A23.1, ANSI/ACI 315, a Manual of Standard Practice by Steel Institute of Canada. ACI Engineering and Placing Drawin Concrete Structures unless ind	nd Reinforcing Steel the Reinforcing 315R, Manual of gs for Reinforced
	.2	Obtain Departmental Representa locations of reinforcement spl those shown on placing drawing	ices other than

Slipway Reconstruction River of Ponds, NL		CONCRETE REINFORCING	Section 03 20 00 Page 4
PN: 722303			April 2019
2.2 FABRICATION .3 (Cont'd)		Upon approval of Departmental Represent in accordance with	
	. 4	Ship bundles of bar reinforcement identified in accordance with bar and lists.	
2.3 SOURCE QUALITY CONTROL	.1	Provide Departmental Representate copy of mill test report of reins showing physical and chemical and weeks prior to commencing reinform	forcing steel, alysis, minimum 2
	.2	Upon request inform Departmental proposed source of material to be	
PART 3 - EXECUTION			
3.1 FIELD BENDING	.1	Do not field bend or field weld a except where indicated or author. Departmental Representative.	
	.2	When field bending is authorized heat, applying slow and steady page 1	
	.3	Replace bars, which develop crac	ks or splits.
3.2 PLACING REINFORCEMENT	.1	Place reinforcing steel as indicaplacing drawings and in accordance CAN/CSA-A23.1.	
	.2	Use approved type chairs to locasteel at the proper grade.	te the reinforcing
	.3	Tie reinforcement where spacing is:	in each direction
		.1 Less than 300 mm: tie at alintersections..2 300 mm or more: tie at each	
	. 4	Prior to placing concrete, obtain Representative's approval of reinand placement.	-
	.5	Ensure cover to reinforcement is concrete pour.	maintained during

Slipway Reconstruction	CONCRETE REINFORCING	Section 03 20 00
River of Ponds, NL		Page 5
PN: 722303		April 2019

3.3 CLEANING .1 Clean reinforcing before placing concrete to CAN/CSA-A23.1.

Slipway Reconstruction CAST-IN-PLACE CONCRETE Section 03 30 00
River of Ponds, NL Page 1
PN: 722303 April 2019

PART 1 - GENERAL

1.1 DESCRIPTION

.1 This section specifies requirements for supply, placing, finishing, protecting and curing cast-in-place concrete or reinforced concrete apron, concrete support piers, and concrete boat launch ramp.

1.2 RELATED SECTIONS

- .1 Section 03 10 00 Concrete Forming and Accessories.
- .2 Section 03 20 00 Concrete Reinforcing.
- .3 Section 32 11 23 Aggregate Base Course.
- .4 Section 03 37 26 Underwater Placed Concrete.

1.3 REFERENCES

.1 ASTM International

- .1 ASTM C109/C109M-16a, Standard Test Method for Compressive Strength of Hydraulic Cement Mortars (Using 2 in. or 50 mm Cube Specimens).
- .2 ASTM C260/C260M-10a(2016), Standard Specification for Air-Entraining Admixtures for Concrete.
- .3 ASTM C494/C494M-16, Standard Specification for Chemical Admixtures for Concrete.
- .4 ASTM C1017/C1017M-e1, Standard Specification for Preformed Chemical Admixtures for Use in Producing Flowing Concrete.
- .5 ASTM D1751-04 (2013e1), Standard Specification for Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Nonextruding and Resilient Bituminous Types).
- .6 ASTM D1752-04a (2013), Standard Specification for Preformed Sponge Rubber Cork and Recycled PVC Expansion Joint Fillers for Concrete Paving and Structural Construction.
- .2 Canadian Standards Association (CSA International)
 - .1 CAN/CSA-A23.1-14/A23.2-14, Concrete Materials and Methods of Concrete Construction/Methods of Test for Concrete.
 - .2 CSA A283-06 (R2016), Qualification Code for Concrete Testing Laboratories.
 - .3 CSA-A3000-13, Cementitious Materials Compendium (Consists of A3001, A3002, A3003, A3004 and A3005).
 - .1 CSA-A3001-03, Cementitious Materials for Use in Concrete.

Slipway Reconstruct River of Ponds, NL PN: 722303	ion	CAST-IN-PLACE CONCRETE	Section 03 30 00 Page 2 April 2019
1.4 CERTIFICATES	1	Submit certificates in accordant 00 Submittal Procedures.	nce with Section 01 33
	.2	Minimum 2 weeks prior to starts submit to Departmental Representest data and certification by inspection and testing laborate materials will meet specified: 1 Portland cement. 2 Blended hydraulic cement. 3 Supplementary cementing made of the substitution of the sub	ntative manufacturer's qualified independent ory that following requirements:
	.3	Provide certification that mix will produce concrete of qualitas specified in concrete mixes CAN/CSA-A23.1.	ty, yield and strength
	. 4	Provide certification that plan materials to be used in concre requirements of CAN/CSA-A23.1.	
	.5	Shop Drawings: .1 Submit shop drawings for tobe reviewed and approved pricincluding product literature acconcrete mix design, character finishes.	or to manufacturing nd data sheets for the
1.5 STORAGE OF MATERIALS	.1	Store materials to prevent condeterioration.	tamination or
	.2	Provide adequate storage faciliensure a continuous supply of batching operations.	
	.3	Store cement in weathertight for	acility.
	. 4	Deliver and store concrete pandlocation and protect from damade	

Replace any defective or damaged panels with new.

. 5

Slipway Reconstructic River of Ponds, NL PN: 722303	on	CAST-IN-PLACE CONCRETE Section 03 30 00 Page 3 April 2019		
1.6 QUALITY ASSURANCE	.1	Minimum 2 weeks prior to starting concrete work, submit proposed quality control procedures to Departmental Representative for the following items: 1 Cold weather concrete. 2 Curing. 3 Finishes. 4 Formwork removal. 5 Joints.		
1.7 WASTE MANAGEMENT AND	.1	Use trigger operated spray nozzles for water hoses.		
DISPOSAL	.2	Designate a cleaning area for tools to limit water use and runoff.		
	.3	Carefully coordinate the specified concrete work with weather conditions.		
	. 4	Ensure emptied containers are sealed and stored safely for disposal away from children.		
		Prevent plasticizers, water-reducing agents and air-entraining agents from entering drinking water supplies or streams. Using appropriate safety precautions, collect liquid or solidify liquid with an inert, noncombustible material and remove for disposal. Dispose of all waste in accordance with applicable local, provincial and national regulations.		
	.6	Choose least harmful, appropriate cleaning method which will perform adequately.		
1.8 MEASUREMENT FOR PAYMENT	.1	Reinforced Concrete Apron: Supply and installation of reinforced concrete to be measured in square meters (m²) calculated from actual field measurement. Contractor to provide all plant, equipment, material, and labour including concrete, reinforcing steel, expansion and control joints.		
	.2	Reinforced Concrete Footings: Supply and installation of reinforced concrete footings to be measured in (LM) linear meters. Contractors to provide all plant, equipment, materials and labour including concrete reinforcement and control joints.		

Slipway Reconstruction CAST-IN-PLACE CONCRETE Section 03 30 00 River of Ponds, NL Page 4
PN: 722303 April 2019

1.8 MEASUREMENT FOR PAYMENT (Cont'd)

Reinforced Concrete Piers: Supply and installation of reinforced concrete piers to be measured by the unit. Contractors to provide all plant, equipment, materials and labour including concrete reinforcement, anchor bolts and filler.

.4 Boat Launchway

.3

- .1 Reinforced cast-in-place launchway: Supply and installation of reinforced concrete cast-in-place boat launchway to be measured in square meters (m²) calculated from actual field measurements as specified, including reinforcing steel, anchor bolts, composite decking, control joints, false work, form work cement, plant and labour will be included in the price items for measurement purposes.
- Reinforced concrete panels: Supply, placement, installation of reinforced concrete panels to be measured by the (unit). Size of each panel as identified in project drawings which includes reinforcing steel, steel bars, slab openings, grouting, composite decking, anchor bolts and panel anchoring system as detailed on project drawings.

 Reinforced Concrete curb: Supply, placement,
- installation of reinforced concrete curb: Supply, placement, installation of reinforced concrete curb at the toe of the boat launchway to be measured by lump sum (LS). Work to include form work, false work, reinforcements, dowels, anchor rebar and tremie concrete to complete work as shown in construction drawings.
- .5 No separate payment will be made for any other ingredient or feature of concrete work, and all factors, including cold weather placement, reinforcing steel, formwork and falsework anchor bolts, joint filler for control joints, cement, plant and labour will be considered as being included in the unit price for item.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Cement: to CAN/CSA-A3001, Type GU.
- .2 Supplementary cementing materials: to CAN/CSA-A3001.
- .3 Cementitious hydraulic slag: to CAN/CSA-A3001.
- .4 Water: to CAN/CSA-A23,1,

Slipway Reconstru River of Ponds, N PN: 722303		CAST-IN-PLACE CONCRETE	Section 03 30 00 Page 5 April 2019
2.1 MATERIALS (Cont'd)	.5	Aggregates: to CAN/CSA-A23.1. normal density.	Coarse aggregate to be
	.6	Air entraining admixture: to A	STM C260.
	.7	Chemical admixtures: to ASTM C Departmental Representative to or set retarding admixtures du weather placing.	approve accelerating
	.8	Concrete retarders: to ASTM C4 moisture of any kind to come i retarder film.	
	.9	Curling compound: curing compoused.	ounds are not to be
	.10	Premoulded joint fillers: .1 Sponge rubber: to ASTM D1 grade.	752, Type I, flexible
2.2 MIXES	1	Proportion concrete in accorda CAN/CSA-A23.1.	nce with
	.2	Proportion concrete to comply Table 2 in CAN/CSA-A23.1 and f .1 Cement:	e aggregate. ete in range of 2240
	.3	When the Contractor wishes to a ready mix concrete supplier, the supplier certifying the form of the supplier of the concrete of the specified qual supplier of the specified qual supplier of the specified qual supplier of the strengths will concrete of the strengths will be strengths.	submit a letter from pllowing: is certified and all proceed comply with the selected will produce ity and yield. sources of all

Slipway Reconstruct: River of Ponds, NL PN: 722303	ion -	CAST-IN-PLACE CONCRETE	Section 03 30 00 Page 6 April 2019
2.2 MIXES (Cont'd)	. 4	When the Contractor wishes to identify the source of aggregates of fine and coarse aggregates laboratory for testing and tradetermine a suitable mix designation and tradetermine a suitable mix designation and tradetermine a suitable mix designation at Contractor's contractory, at Contractor's contract mix for slump, air contistrength. The results of these submitted to the Departmental reviewed for compliance with review must be completed before concrete is given. 1. The sand, gravel, water agent should be mixed prior to cement and water reducer.	ates and submit samples to a testing ial mixes in order to gn. The testing ost, will test the ent, density and e tests will be Representative to be the specification. This re permission to place and air entraining
	.5	Weigh aggregates, cement, waterbatching. No alternative methology be permitted.	
	.6	Do not use calcium chloride.	
2.3 PANEL FABRICATED	.1	Fabricate to CSA A23.A 4880 mtthick as indicated on drawing	
	.2	Finish: broom finish concrete traffic direction.	perpendicular to
	.3	Provide precast anchor holes, panels as indicated on projec	
	. 4	Supply and install composite drawings.	decking as indicated on
PART 3 - EXECUTION			
3.1 PREPARATION	.1	Obtain Departmental Represent placing concrete. Provide 24 placing of concrete.	
	.2	Pumping of concrete is permit of equipment and mix.	ted only after approval

during concrete placement.

Ensure reinforcement and inserts are not disturbed

.3

Slipway Reconstruct River of Ponds, NL PN: 722303	ion	CAST-IN-PLACE CONCRETE	Section 03 30 00 Page 7 April 2019
3.1 PREPARATION (Cont'd)	. 4	Prior to placing of concrete ob Representative's approval of pr protection of concrete during p adverse weather.	oposed method for
	.5	Maintain accurate records of po to indicate date, location of p temperature and test samples ta	our, quality, air
	.6	Do not place load upon new conc by Departmental Representative.	
	.7	Place tremie concrete to Sectio Underwater Placed Concrete.	n 03 37 26 –
3.2 CONSTRUCTION .1 .2 .3	.1	Comply with additional requirem CAN/CSA-A23.1, Clause 4.1.1.5, to seawater environments.	
	.2	Minimum concrete cover over rei to be 75 mm.	nforcing steel bars
	.3	Place concrete in hot weather t	o CAN/CSA-A23.1.
	. 4	Place concrete in cold weather	to CAN/CSA-A23.1.
	.5	Keep concrete surfaces moist co protection stage.	ntinually during
	.6	Place, consolidate, finish, cur concrete to CAN/CSA-A23.1.	e and protect
	.7	Do not commence placing concret Representative has inspected an foundations, reinforcing steel, spreading, consolidation and fi curing and protective methods.	d approved forms, joints, conveying,
	.8	Install panels as indicated on	drawings.
.9		Secure panels in position by pr holes and using adhesive capsul stainless steel anchor rods (va required). Cut top of rods flus Grout all anchor holes above L.	es and 19 mm diameter rious lengths as h with top of panels.
	.10	Replace damaged or defective pa Departmental Representative.	nels as directed by

.11 Concrete curb to be installed after placement of the first concrete panel.

Slipway Reconstructi River of Ponds, NL PN: 722303	.on	CAST-IN-PLACE CONCRETE	Section 03 30.00 Page 8 April 2019
3.2 CONSTRUCTION (Cont'd)	.12	Place tremie concrete to Section Underwater Placed Concrete.	n 03 37 26 -
	.13	Remove form work 7 days after coconcrete placement.	ompletion of the
3.3 FORMWORK	.1	Install and strip formwork to CA Section 03 10 00 - Concrete Form	
3.4 INSERTS	.1	Position and secure anchor bolts maintain line and grades.	s in formwork to
3.5 CONCRETE PANELS ANCHOR ROD	.1	To be 25 mm diameter HAS-R-316 sthreaded rod complete with 100 mstainless steel washer and stain required. Use epoxy adhesive caprod to bedrock. Heavy duty two anchor consisting of a self-contagsule. Install to manufactures	nm diameter x 5 mm hless steel nuts as psule for anchorage compound adhesive tained adhesive
3.6 CONCRETE PIER ANCHOR ROD	.1	To be 19 mm diameter HAS-R-316 or rod x 500 mm long, 300 mm embedrater. Rods to be complete with and washers. Countersink nuts in fill with elastromeric filler. Solution - Joint Filler.	ment into concrete stainless steel nuts nto timberbeam and
3.7 REBAR INSERTS AND ANCHORING	.1	Rebar for anchoring concrete picturbto bedrock to be 20 m rebar (galvanized) with minimum embedrated pre-drill hole and use heavy duadhesive capsules. Use to manufainstructions.	x 600 mm long ment of 300 mm. ty two compound
3.8 CONTROL JOINTS	.1	Construct control joints in local drawings or directed by Department	
	,2	All joints will be centered over will be made in a perfectly stra	
	.3	Cut control joint when concrete	has hardened.

Slipway Reconstructi River of Ponds, NL	on	CAST-IN-PLACE CONCRETE	Section 03 30 00 Page 9
PN: 722303			April 2019
3.8 CONTROL JOINTS (Cont'd)	. 4	Fill saw cut with joint sealer as	s specified.
3.9 PLACING CONCRETE	.1	Place and consolidate concrete to	can/csa-a23.1.
	.2	Do not place concrete on or again	nst frozen material.
	.3	Place concrete continuously from	joint to joint.
	. 4	Place concrete in a uniform head: centreline. Limit rate of placing be finished before beginning of	g to that which can
3.10 STRIKE OFF AND . CONSOLIDATION		High speed internal poker vibrate consolidate the concrete during procession of the surfaces shall beam-type vibratory air screed as Departmental Representative. A supproximately 65 mm of concrete at the screed face during consolidations.	placing. Final be done by s approved by archarge of will be maintained
	.2	Strikeoff and consolidation must excess water bleeds to the surface	_
	.3	Ensure that the concrete deck concelevations and slopes as shown or that satisfactory drainage will	n the drawings so
3.11 FINISHING	.1	Only ACI certified or other pre- finishers are to be utilized in a concrete works. All work is to be CAN/CSA-A23.1, and as specified by	finishing all e finished to
	.2	The surface will be brought to the by means of darbying or bull flow carried out immediately following be completed before any bleed was the surface. Surface tolerance to metre straight edge.	ating which will be g screeding and must ter is present on
	.3	Provide slope as shown on the draproper drainage of the concrete of	_
	. 4	Finish slabs to elevations indica	ated on drawings.
	.5	Strike off the surface with a st	raight edge.

Slipway Reconstruction	CAST-IN-PLACE CONCRETE	Section 03 30 00
River of Ponds, NL		Page 10
PN: 722303		April 2019

3.11 FINISHING (Cont'd)

- .6 Hand tamp low slump concrete with jitterbug.
- .7 Darby or bull float the surface to smooth and level the concrete.
- .8 Allow bleed water or sheen to disappear.
- .9 Float the surface by means of power and/or hand float where the concrete has hardened enough for a man to leave only slight footprints on the surface.
- .10 Do not bring water and fines to the surface by over floating. Where extra floating is required the floating operation shall be repeated after the time interval necessary for any sheen to disappear and for concrete to set further.
- .11 Steel trowel the concrete surfaces by means of power and/or hand trowel. Do not leave any hard, smooth, polished or burnished surface area.
- .12 Do not bring water and fines to the surface by overtrowelling.
- .13 After slight interval necessary for concrete to further harden, repeat the trowelling operation.
- .14 Lightly broom surface with a soft bristle broom obtaining a fine and even textured finish with a non-slip finish. All brush strokes to be perpendicular to the wharf face across the full width of deck to promote free draining of the deck finish.
- .15 The surface shall be true and accurate to a maximum tolerance of 1 mm in 500 mm.

Slipway Reconstruction	CAST-IN-PLACE CONCRETE	Section 03 30 00
River of Ponds, NL		Page 11
PN: 722303		April 2019

3.12 PROTECTION AND CURING

- .1 Cure to CAN/CSA-A23.1.
- Cure concrete by protecting it against loss of moisture, rapid temperature change and mechanical injury for at least 7 days after placement. After finishing operations have been completed, the entire surface of the newly placed concrete shall be covered by whatever curing medium is applicable to local conditions and approved by the Departmental Representative. The edges of concrete slabs exposed by removal of forms shall be protected with continuous curing treatment equal to the method selected for curing the slab and curb surfaces. Cure to CAN/CSA-A23.1. Have the equipment needed for adequate curing at hand and ready to install before actual concrete placement begins.
- .3 When air temperature is at or below 5°C or when there is a probability of its falling to that limit within 24 hours of placing (as forecast by the nearest official meteorological office) cold weather protection as per CAN/CSA-A23.1 will be provided and the following:
 - .1 Housing Protect concrete by a windproof shelter of canvas or other material to allow free circulation of inside air around fresh touch formwork and provide sufficient space for removal of formwork for finishing. Supply approved heating equipment capable of keeping inside air at a constant temperature sufficiently high to maintain concrete at following curing temperatures.
 - .1 For initial 3 days at a temperature of not less than 15°C nor more than 27°C at surface.
 - .2 Maintain concrete at 10°C for an extra 4 days plus the initial 3 days.
 - .3 In addition to the protective housing, the concrete must be cured as outlined in Clause 3.9.2 above.

3.13 TESTING

- .1 Departmental Representative will appoint a concrete testing company to test all work under this section of specification as per CAN/CSA-A23.1.
- .2 Cost of compressive strength tests shall be paid for by the Departmental Representative.
- .3 Testing company shall issue reports to Departmental Representative on quality of test cylinders.

Slipway Reconstruction	CAST-IN-PLACE CONCRETE	Section 03 30 00
River of Ponds, NL		Page 12
PN: 722303		April 2019

3.13 TESTING (Cont'd)

- .4 Notify Departmental Representative at least 7 days prior to start of placing concrete. Provide for testing purposes an adequate quantity of approved test cyclinders.
- .5 At least 1 set of 3 cylinders each shall be taken from 25 m³ or fraction thereof of each day's pour, whichever is less. 1 cylinder shall be tested at 7 days and other 2 tested at 28 days.
- .6 Crate cylinders and deliver to the testing laboratory within 48 hours after casting in accordance with CAN/CSA-A23.1. Contractor will pay for crating and delivery of cylinders to the laboratory.
- .7 If strength tests of test cylinder for any portion of the work falls below the specified compressive strength at 28 days, the Departmental Representative reserves the right to determine the acceptability of the concrete by performing additional field testing as outlined in CAN/CSA-A23.1.
- .8 If concrete does not conform to drawings or specifications, take measures as directed to correct the deficiency. All costs of correctional measures will be at the expense of the Contractor.

Slipway Reconstruct: River of Ponds, NL PN: 722303	Lon	UNDERWATER PLACED CONCRETE	Section 03 37 26 Page 1 April 2019
PART 1 - GENERAL			
1.1 RELATED REQUIREMENTS	.1	Section 03 30 00 - Cast-in-Place	Concrete.
1.2 REFERENCE STANDARDS	.1	American Concrete Institute (ACI) .1 ACI 304R-00, Guide for Measu Transporting and Placing Concrete	ıring, Mixing,
	.2	CSA International .1 CSA A23.1/A23.2-09, Concrete Methods of Concrete Construction, Standard Practices for Concrete.	
1.3 DEFINITIONS	.1	Tremie concrete: concrete placed through tube called tremie pipe.	underwater
	.2	Tremie pipe: pipe has hopper at ube open ended or may have foot vatravelling plug to control flow of has diameter of 200 mm minimum, osections with flange couplings figaskets. 1. Concrete is placed in hopper head of concrete is maintained in provide desired rate of flow.	alve, plug or of concrete. Pipe constructed from itted with
	.3	Pumped concrete method: method or underwater uses concrete pump with used in similar manner to tremie	th discharge line
	.4	Bottom-dump bucket method: method concrete underwater requires use designed to discharge from bottom contacted foundation or surface oplaced concrete.	of bucket m after it has
	.5	Bagged concrete method: method of underwater concrete consists of a partially filled with dry concrete	diver placing bags
1.4 ADMINISTRATIVE REQUIREMENTS	.1	Concrete pre-placement meeting; of pre-placement meeting [2] weeks of tremie operation.	

Slipway Reconstruction River of Ponds, NL PN: 722303		UNDERWATER PLACED CONCRETE	Section 03 37 26 Page 2 April 2019
1.4 ADMINISTRATIVE REQUIREMENTS (Cont'd)	.1	(Cont'd) .1 Ensure meeting includes as ras follows: .1 General contractor2 Ready-mix concrete supp3 Admixture supplier4 Placing/formwork sub-co5 Reinforcing sub-contractor6 Testing agency representative.	plier. ontractor. ctor.
	.2	Distribute minutes to attendees of concrete mix designs, aggregate properties, placing schedule, rattesting program, and, contingency and breakdown.	te physical te of delivery,
1.5 ACTION AND INFORMATIONAL SUBMITTALS	.1	Submit in accordance with Section Submittal Procedures. Product Data: .1 Submit manufacturer's instruction of the submit of the submitted include product characterists.	uctions, printed ts for concrete
1.6 DELIVERY, STORAGE AND HANDLING	.1	Deliver, store and handle materia with Section 01 61 00 - Common P: Requirements and with manufacture	and limitations. als in accordance roduct
	.2	instructions. Delivery and Acceptance Requirement materials to site in original facturer's name	ctory packaging,
	.3	Storage and Handling Requirements. 1 Store materials indoors in accordance with manufacturer's in clean, dry, well-ventilated as .2 Replace defective or damaged new.	dry location and s recommendations rea.
	. 4	Develop Construction Waste Manage Reduction Workplan related to Work Section.	

Slipway Reconstruction River of Ponds, NL		UNDERWATER PLACED CONCRETE	Section 03 37 26 Page 3
PN: 722303			April 2019
1.6 DELIVERY, STORAGE AND HANDLING (Cont'd)	.5	Packaging Waste Management: remeturn by manufacturer of palls padding, and packaging material Construction Waste Management Reduction Workplan in accordance of 74 21 - Construction/Demolish Management and Disposal.	ets, crates, ls as specified in Plan, Waste ce with Section
PART 2 - PRODUCTS			
•		•	
2.1 MATERIALS	.1	Concrete materials: to Section Cast-in-Place Concrete.	03 30 00 -
2.2 CONCRETE MIXES	.1	Use type GU cement.	
	.2	Minimum compressive strength a	t 28 days: 35 MPa.
	.3	Class of exposure: C2.	
	. 4	Maximum water cement ratio by m	mass: 0.45.
	.5	Nominal size of coarse aggrega	te: 20 mm.
	.6	Cement content for mixtures: 3	85 kg/m³ minimum.
.7		Slump at point and time of subsection 65 to 110 mm.	mergence discharge:
	.8	Air dry density: 2240 kg/m³.	
	.9	Admixtures: as approved in writuse admixtures to correct deficient to improve placement of concret. Consultant may withdraw productions or admixture if conditions or approximations.	ciencies in mix or te. rior approval of

admixture if conditions encountered during course

Do not use calcium chloride or materials

of work indicate unsatisfactory results.

consolidating concrete to Departmental

Submit admixtures to produce self

containing calcium chloride.

Representative for review.

Slipway Reconstruction UNDERWATER PLACED CONCRETE Section 03 37 26
River of Ponds, NL Page 4
PN: 722303 April 2019

PART 3 - EXECUTION

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for concrete placement installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 PREPARATION

- .1 Where concrete must bond to existing surfaces, clean surfaces before starting concrete placement.
 - .1 Use water jets, mechanical scrapers or other means, and when quantities of mud or rock cuttings are present, remove by air lift.

3.3 INSTALLATION

- .1 Do concrete work in accordance with Section 03 30 00 Cast-in-Place Concrete and Section 03 20 00 Concrete Reinforcing and to CSA A23.1/A23.2. Testing for concrete to CSA A23.1/A23.2.
- .2 Where concrete placement extends above water surface, protect concrete from direct contact with air at temperature below 5 degrees C for 7 days.
- .3 Place concrete in one continuous operation to full depth required.
 - .1 Supply complete equipment for every phase of operation.
 - .2 Provide sufficient supply of concrete to complete pour without interruption.

.4 Tremie method:

- .1 Provide water-tight tremie pipe sized to allow free flow of concrete. Diameter of tremie pipe to be minimum 200 mm and minimum eight times maximum size of coarse aggregate.
- .2 Provide hopper at top of tremie pipe and means to raise and lower tremie pipe.

Slipway Reconstruction UNDERWATER PLACED CONCRETE Section 03 37 26 River of Ponds, NL Page 5
PN: 722303 April 2019

3.3 INSTALLATION (Cont'd)

.4 (Cont'd)

- .3 Provide plug or foot valve at bottom of tremie pipe to permit filling pipe with concrete initially.
- .4 Provide minimum of one tremie pipe for every $30~\text{m}^2$ of plan area and to maximum spacing of 6~m centre to centre. Do not move tremie pipes laterally through concrete.
- .5 Start placement with tremie pipe full of concrete. Keep bottom of pipe buried minimum 300 mm in freshly placed concrete.
- .6 If seal is lost, allowing water to enter pipe, withdraw pipe immediately. Refill pipe, and continue placing as specified.
- .7 If tremie operation is interrupted so that horizontal construction joint has to be made, cut surface laitance by jetting, within 24 to 36 hours and remove loose material by pumping or air lifting before placing next lift.
- .8 Do not place concrete in flowing water when current exceeds 3 m/min. Do not vibrate, disturb or puddle concrete after placement.
- .5 Pumped concrete method:
 - .1 Follow procedures as for tremie method in placing concrete using discharge line from concrete pump as tremie pipe.
 - .2 Pump discharge line diameter: 125 mm minimum.
- .6 Bottom-dump bucket method:
 - .1 Fill bucket with concrete, cover top surface and lower slowly through water to prevent backwash.
 - .2 Discharge concrete only when bucket is in contact with surface on which concrete is to be deposited.
 - .3 Withdraw bucket until it is above concrete to maintain still water at point of discharge to approval of Departmental Representative.

3.4 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 Cleaning.

Slipway Reconstruction	UNDERWATER PLACED CONCRETE	Section 03 37 26
River of Ponds, NL		Page 6
PN: 722303		April 2019
N: /22303		April 2019

- 3.4 CLEANING (Cont'd)
- .3 Waste Management: separate waste materials for reuse and recycling in accordance with Section 01 74 21 Construction/Demolition Waste Management.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

Slipway Reconstruction WOOD TREATMENT Section 06 05 73
River of Ponds, NL Page 1
PN: 722303 April 2019

PART 1 - GENERAL

1.1 REFERENCES

- .1 American Wood-Preservers' Association (AWPA)
 - .1 AWPA M2-16, Standard Inspection of Treated Wood Products.
 - .2 AWPA M4-15, Standard for the Care of Preservative-Treated Wood Products.
- .2 Canadian Standards Association (CSA)
 - .1 CSA 080 Series-15 Wood Preservation.
 - .2 CSA 080.201-97, Standard for Hydrocarbon Solvents for Preservatives. This Standard covers hydrocarbon solvents for preparing solutions of preservatives. This is not stand alone specification.
 - .3 CSA 0322-15, Procedure for Certification of Pressure-Treated Wood Materials for Use in Preserved Wood Foundations.

1.2 QUALITY ASSURANCE

- .1 Testing of products treated with preservative by pressure impregnation will be carried out by the manufacturer's testing laboratory to AWPA M2, and revisions specified in CSA O80 Series, Supplementary Requirements to AWPA M2.
- .2 Inspection and testing of timber materials will be carried out by the manufacturer.

1.3 CERTIFICATES AND ASSAY RETENTION RESULTS

- .1 Submit certificates and assay retention results in accordance with Section 01 33 00 Submittal Procedures.
- .2 For products treated with preservative by pressure impregnation submit following information certified by authorized signing officer of treatment plant:
 - .1 Information listed in AWPA M2 and revisions specified in CSA 080 Series, Supplementary Requirement to AWPA M2 applicable to specified treatment.
 - .2 Moisture content after drying following treatment with water-borne preservative.
 - .3 Assay retentions results representing each treated batch of supplied timber.
 - .4 Acceptable types of paint, stain, and clear finishes that may be used over treated materials to be finished after treatment.

Slipway Reconstruct River of Ponds, NL PN: 722303	tion	WOOD TREATMENT	Section Page 2 April 20	
1.4 WASTE MANAGEMENT AND DISPOSAL	.1	Do not dispose of perservat incineration.	ive treated wood	d through
	.2	Do not dispose of preservat other materials destined fo		
	.3	Dispose of treated wood, en sawdust at sanitary landfil Departmental Representative	l approved by	scraps and
	. 4	Dispose of unused wood pres official hazardous material approved by Departmental Re	collections si	
	.5	Do not dispose of unused pr sewer system, into streams, other location where they w environmental hazard.	lakes, onto gr	ound or in
PART 2 - PRODUCTS				
2.1 MATERIALS	1	Preservative: to CSA-080 Se	ries.	
	.2	Solvent: to CSA-080.201.		
2.2 PRESERVATIVE TREATMENTS	.1	Treat to CSA 080, commodity and its referenced standard minimum assay retentions:		
		-	CCA	ACA
		Species	kg/m³	kg/m³
		Dimension Timber		
		-Coast Douglas Fir	24	24
		-Western/Eastern Hemlock -Hemlock, Douglas Fir Wheelguard, Wheelguard	24	24
		Blocking)	10	10
		District Annual Control		-

-Birch or Maple

Note: Birch or maple must be air dried for six (6) months in weather protected environment or kiln dried.

Treat to Refusal

Slipway Reconstruction	WOOD TREATMENT	Section 06 05 73
River of Ponds, NL		Page 3
PN: 722303		April 2019

PART 3 - EXECUTION

3.1 FIELD TREATMENT

- .1 Handle pressure treated material in a manner that will avoid damage which may expose untreated material. Rejection of any damaged material may result and replacement will be at the Contractor's expense.
- .2 Fill all bored bolt holes with preservative immediately after boring. Use a pressurized container with hose to apply preservative, or some alternate method acceptable to the Departmental Representative.
- .3 Fill all unused bored holes and spike holes with tight fitting treated wooden plugs.

3.2 CUTTING

.1 Field cuts, if authorized, are to receive three (3) liberal coats of the applicable preservative applied to dry wood on each application.

3.3 FIELD QUALITY

- .1 Timber which contain rot, splits exposing untreated wood, excessive wane, or timbers which cannot be fastened in the work so as to be structurally sound are unacceptable.
- .2 The Departmental Representative reserves the right to carry out field testing of treated timber for penetration and retention of preservative. Timber not meeting the requirements of the specification may be rejected for use under the contract.

Slipway Reconstruction River of Ponds, NL PN: 722303		JOINT SEALING	Section 07 92 10 Page 1 April 2019	
PART 1 - GENERAL				
1.1 SECTION INCLUDES	.1	Materials, preparation and applic caulking and sealants.	cation for	
1.2 RELATED SECTIONS	.1	Section 01 33 00 - Submittal Prod	cedures.	
<u> </u>	.2	Section 01 45 00 - Quality Contro	ol.	
	.3	Section 01 61 00 - Common Product	Requirements.	
	. 4	Section 01 74 21 - Construction/I Management and Disposal.	Demolition Waste	
	.5	Section 03 10 00 - Concrete Formation Accessories.	ing and	
	.6	Section 03 30 00 - Cast-in-Place	Concrete.	
1.3 REFERENCES	1	Canadian General Standards Board	(CGSB)	
	.2	CAN/CGSB-19.24-M90, Multi-compone Curing Sealing Compound.	ent, Chemical	
	.3	Department of Justice Canada (Justice Canada (Justice Canadian Environmental Prote (CEPA).		
	. 4	Health Canada/Workplace Hazardous Information System (WHMIS) .1 Material Safety Data Sheets		
	.5	Transport Canada (TC) .1 Transportation of Dangerous (TDGA).	Goods Act, 1992	
1.4 SUBMITTALS	.1	Submit product data in accordance 33 00 - Submittal Procedures.	e with Section 01	
	.2	Manufacturer's product to described. 1 Caulking compound. 2 Primers. 3 Sealing compound, each type compatibility when different seal contact with each other.	, including	

Slipway Reconstruct	ion	JOINT SEALING	Section 07 92 10
River of Ponds, NL PN: 722303			Page 2 April 2019
			-
1.4 SUBMITTALS (Cont'd)	.3	Submit manufacturer's instructions in accordance with Section 01 33 00 - Submittal Procedures. .1 Instructions to include installation instructions for each product used.	
1.5 DELIVERY, STORAGE, AND HANDLING	.1 Deliver, handle, store and protect materials in accordance with Section 01 61 00 - Common Product Requirements.		
·	.2	Deliver and store materials in o and containers with manufacturer labels, intact. Protect from fre- water and contact with ground or	's seals and ezing, moisture,
1.6 WASTE MANAGEMENT AND DISPOSAL	.1	Separate waste materials for reu in accordance with Section 01 74 Construction/Demolition Waste Mar Disposal.	21 -
	.2	Remove from site and dispose of materials at appropriate recycli	
	.3	Collect and separate for disposa polystyrene, corrugated cardboar material, in appropriate on-site recycling in accordance with Was Plan.	d, packaging bins, for
	. 4	Place materials defined as hazar designated containers.	dous or toxic in
	.5	Handle and dispose of hazardous accordance with the CEPA, TDGA, Municipal regulations.	
	.6	Unused sealant material must not into sewer system, into streams, ground or in other location wher health or environmental hazard.	lakes, onto
	.7	Divert unused joint sealing mate to official hazardous material c approved by Departmental Represe	ollections site
	.8	Empty plastic joint sealer conta recyclable. Do not dispose of em with plastic materials destined	pty containers

Slipway Reconstruction River of Ponds, NL PN: 722303		JOINT SEALING	Section 07 92 10 Page 3 April 2019
1.6 WASTE MANAGEMENT AND DISPOSAL (Cont'd)	.9	Fold up metal banding, flatten, designated area for recycling.	and place in
1.7 PROJECT CONDITIONS	.1	Environmental Limitations: .1 Do not proceed with install sealants under following condit: .1 When ambient and substitutions are outside limit joint sealant manufacturer degrees C2 When joint substrates	ions: trate temperature its permitted by or are below 4.4
	.2	Joint-Width Conditions: .1 Do not proceed with install sealants where joint widths are allowed by joint sealant manufacapplications indicated.	less than those
	.3	Joint-Substrate Conditions: .1 Do not proceed with install sealants until contaminants capinterferring with adhesion are substrates.	able of
1.8 ENVIRONMENTAL REQUIREMENTS	.1	Comply with requirements of Work Materials Information System (Winuse, handling, storage, and dispendentials; and regarding labell of Material Safety Data Sheets to Labour Canada.	HMIS) regarding posal of hazardous ing and provision
	.2	Conform to manufacturer's recommendative humidity moisture content for application sealants including special conduse.	, and substrate n and curing of
1.9 MEASUREMENT FOR PAYMENT	.1	No measurement for payment to be section. Include costs in unit which joint sealing is required	prices for items in

Slipway Reconstructi River of Ponds, NL PN: 722303	on	JOINT SEALING	Section 07 92 10 Page 4 April 2019
PART 2 - PRODUCTS			
2.1 SEALANT MATERIALS	.1	Where sealants are qualified wit these primers.	h primers use only
2.2 SEALANT .1 MATERIAL DESIGNATIONS		Polyurethane Sealant: .1 Self-Leveling one part poly to CAN/CGSB-19.13 M87, Classific Premium Grade, colour to match c .2 Non-Sag to CAN/CGSB-19.24, concrete3 Temperature range of -44 to	ation C-1-25-B-N, oncrete. colour to match
	.2	Preformed Compressible and Non-Coback-up materials. 1 Polyethylene or Neoprene Fo. 1 Extruded closed cell f. 2 Size: oversize 30 to 5.2 Neoprene or Butyl Rubber. 1 Round solid rod, Shore. 3 High Density Foam. 1 Extruded closed cell p. (PVC), extruded polyethylen. Shore A hardness 20, tensil. 200 kPa, extruded polyolefication density, or neoprene foam b. recommended by manufacturer. 4 Bond Breaker Tape. 1 Polyethylene bond break will not bond to sealant.	am. oam backer rod. 0%. A hardness 70. olyvinyl chloride e, closed cell, e strength 140 to n foam, 32 kg/m³ acker, size as .
2.3 SEALANT SELECTION	.1	Expansion and control joints in of poured-in-place concrete: Sea terpolymer, elastomeric polyuret	lant type: acrylic
	.2	Control and expansion joints in of walls: Sealant type: elastome	
2.4 JOINT CLEANER	.1	Non-corrosive and non-staining twith joint forming materials and recommended by sealant manufactu	sealant
	.2	Primer: as recommended by manufa	cturer.

Slipway Reconstructio River of Ponds, NL PN: 722303	n	JOINT SEALING	Section 07 92 10 Page 5 April 2019
PART 3 - EXECUTION			
3.1 PROTECTION	.1	Protect installed Work of other t staining or contamination.	rades from
3.2 SURFACE PREPARATION	.1	Examine joint sizes and condition correct depth to width relationshinstallation of backup materials	nip for
	.2	Clean bonding joint surfaces of h substances including dust, rust, other matter which may impair Won	oil grease, and
	.3	Do not apply sealants to joint so with sealer, curing compound, wat other coatings unless tests have ensure compatibility of materials as required.	ter repellent, or been performed to
	. 4	Ensure joint surfaces are dry and	d frost free.
	.5	Prepare surfaces in accordance widirections.	th manufacturer's
3.3 PRIMING	.1	Where necessary to prevent stains surfaces prior to priming and cau	
	.2	Prime sides of joints in accordar manufacturer's instructions immediately caulking.	
3.4 BACKUP MATERIAL	.1	Apply bond breaker tape where red manufacturer's instructions.	quired to
	.2	Install joint filler to achieve depth and shape, with approximate compression.	=
3.5 MIXING	.1	Mix materials in strict accordance manufacturer's instructions.	ce with sealant

Slipway Reconstruction	JOINT SEALING	Section 07 92 10
River of Ponds, NL		Page 6
PN: 722303		April 2019

3.6 APPLICATION

.1 Sealant.

- .1 Apply sealant in accordance with manufacturer's written instructions.
- .2 Mask edges of joint where irregular surface or sensitive joint border exists to provide neat joint.
- .3 Apply sealant in continuous beads.
- .4 Apply sealant using gun with proper size nozzle.
- .5 Use sufficient pressure to fill voids and joints solid.
- .6 Form surface of sealant with full bead, smooth, free from ridges, wrinkles, sags, air pockets, embedded impurities.
- .7 Tool exposed surfaces before skinning begins to give slightly concave shape.
- .8 Remove excess compound promptly as work progresses and upon completion.

.2 Curing.

- .1 Cure sealants in accordance with sealant manufacturer's instructions.
- .2 Do not cover up sealants until proper curing has taken place.

.3 Cleanup.

- .1 Clean adjacent surfaces immediately and leave Work neat and clean.
- .2 Remove excess and droppings, using recommended cleaners as work progresses.
- .3 Remove masking tape after initial set of sealant.

Slipway Reconstruction CORRECTED MAXIMUM DRY Section 31 05 10 River of Ponds, NL DENSITY FOR FILL Page 1 April 2019

PART 1 - GENERAL

1.1 SUMMARY

This section defines correction to maximum dry density to take into account aggregate particles larger than 19 mm.

1.2 REFERENCES

.1 American Society for Testing and Materials (ASTM)
.1 ASTM C127-12 (2001), Standard Test Method for
Specific Gravity and Absorption of Coarse Aggregate.
.2 ASTM D698-12a, Standard Test Methods for
Laboratory Compaction Characteristics of Soil Using
Standard Effort (12,400 ft-lbf/ft³ (600 kN-m/m³)).
.3 ASTM D1557-12, Standard Test Method for
Laboratory Compaction Characteristics of Soil Using
Modified Effort (56,000 ft-lbf/ft³ (2,700 kN-m/m³)).
.4 ASTM D4253-00 (2006), Standard Test Methods for
Maximum Index Density and Unit Weight of Soils Using
a Vibratory Table.

1.3 DEFINITIONS

.1 Corrected maximum dry density is defined as:

- .1 $D = (D1xD2) / ((F1 \times D2) + (F2 \times D1))$
- .2 $D = (F1 \times D1) + (0.9 \times D2 \times F2)$
- .3 Where: D = corrected maximum dry density kg/m^3 .
 - .1 F1 = fraction (decimal) of total field sample passing 19 mm sieve
 - .2 F2 = fraction (decimal) of total field sample retained on 19 mm sieve (equal to 1.00 F1)
 - .3 D1 = maximum dry density, kg/m^3 of material passing 19 mm sieve determined in accordance with Method A of ASTM D698.
 - .4 D2 = bulk density, kg/m^3 , of material retained on 19 mm sieve, equal to 1000G where G is bulk specific gravity (dry basis) of material when tested to ASTM C127.
- .4 For free draining aggregates, determine D1 (maximum dry density) to ASTM D4253 dry method when directed by Departmental Representative.

1.4 MEASUREMENT FOR .1 PAYMENT

All work covered under this specification is considered to be incidental to the project and will not be measured for payment under the fixed price items.

	•	
Slipway Reconstruction	CORRECTED MAXIMUM DRY	Section 31 05 10
River of Ponds, NL	DENSITY FOR FILL	Page 2
PN: 722303		April 2019
PART 2 - PRODUCTS		
2.1 NOT USED .1	Not Used.	
. I	Not obea.	
PART 3 - EXECUTION		

3.1 NOT USED .1 Not Used.

Slipway Reconstructs River of Ponds, NL PN: 722303	ion	AGGREGATE MATERIALS	Section 31 05 17 Page 1 April 2019
PART 1 - GENERAL			
1.1 RELATED SECTIONS	.1	Section 01 33 00 - Submittal Pro	ocedures.
DECITONS	.2	Section 01 74 21 - Construction, Management and Disposal.	Demolition Waste
1.2 REFERENCES	.1	American Society for Testing and .1 ASTM D4791-10, Standard Test Particles, Elongated Particles, Elongated Particles in Coarse Ag	st Method for Flat or Flat and
1.3 SAMPLES	.1	Submit samples in accordance wit Submittal Procedures.	th Section 01 33 00 -
	.2	Allow continual sampling by Depa Representative during production	
	.3	Provide Departmental Representat source and processed material for	
	. 4	Install sampling facilities at of production conveyor, to allow De Representative to obtain representative being produced. Stop converguested by Departmental Representation cross section sampling.	epartmental entative samples of eyor belt when
	.5	Pay cost of sampling and testing fail to meet specified requirement	
1.4 WASTE MANAGEMENT AND DISPOSAL	.1	Divert unused granular materials local quarry facility as approve Representative.	
PART 2 - PRODUCTS			
2.1 MATERIALS	.1	Aggregate quality: sound, hard, free from soft, thin, elongated particles, organic material, claor other substances that would a manner for use intended.	or laminated ay lumps or minerals,

Slipway Reconstructi	lon	AGGREGATE MATERIALS	Section 31 05 17
River of Ponds, NL	LOH	COUNTY LWITEVING	Page 2
PN: 722303			April 2019
			110111 2015
2.1 MATERIALS (Cont'd)	.2	Flat and elongated particles of ASTM D47911 Greatest dimension to exclude dimension.	•
	.3	Fine aggregates satisfying recapplicable section to be one, .1 Natural sand2 Manufactured sand3 Screenings produced in crock, boulders, gravel or slag	or blend of following:
	. 4	Coarse aggregates satisfying applicable section to be one of following: .1 Crushed rock2 Gravel and crushed gravel formed particles of stone3 Light weight aggregate, expanded shale.	of or blend of
2.2 SOURCE QUALITY .1		Inform Departmental Representations source of aggregates and prove at least 2 weeks prior to communications.	ide access for sampling
	.2	If, in opinion of Departmental materials from proposed source cannot reasonably be processed requirements, locate an altern demonstrate that material from can be processed to meet specific	e do not meet, or d to meet, specified native source or m source in question
	.3	Advise Departmental Representa advance of proposed change of	
	. 4	Acceptance of material at sour future rejection if it fails trequirements specified, lacks field performance is found to	to conform to uniformity, or if its
PART 3 - EXECUTION			

.1 Aggregate source preparation

3.1 PREPARATION

Slipway Reconstruction	AGGREGATE MATERIALS	Section 31 05 17
River of Ponds, NL		Page 3
PN: 722303		April 2019

3.1 PREPARATION (Cont'd)

.1 (Cont'd)

- .1 Prior to excavating materials for aggregate production, clear area to be worked, and strip unsuitable surface materials. Dispose of cleared unsuitable materials as directed by Departmental Representative.
- .2 Where clearing is required, leave screen of trees between cleared area and roadways as directed.
- .3 Clear, grub and strip area ahead of quarrying or excavating operation sufficient to prevent contamination of aggregate by deleterious materials.
- .4 When excavation is completed dress sides of excavation to nominal 1.5:1 slope, and provide drains or ditches as required to prevent surface standing water.
- .5 Trim off and dress slopes of waste material piles and leave site in neat condition.

.2 Processing

- .1 Process aggregate uniformly using methods that prevent contamination, segregation and degradation.
- .2 Blend aggregates, if required, to obtain gradation requirements, percentage of crushed particles, or particle shapes, as specified. Use methods and equipment approved by Departmental Representative.
- .3 Wash aggregates, if required to meet specifications. Use only equipment approved by Departmental Representative.
- .4 When operating in stratified deposits use excavation equipment and methods that produce uniform, homogeneous aggregate.

.3 Handling

.1 Handle and transport aggregates to avoid segregation, contamination and degradation.

.4 Stockpiling

- .1 Stockpile aggregates on site in locations as indicated unless directed otherwise by Departmental Representative. Do not stockpile on completed pavement surfaces.
- .2 Stockpile aggregates in sufficient quantities to meet Project schedules.
- .3 Stockpiling sites to be level, well drained, and of adequate bearing capacity and stability to support stockpiled materials and handling equipment.
- .4 Except where stockpiled on acceptably stabilized areas, provide compacted sand base not less than 300 mm in depth to prevent contamination of aggregate. Stockpile aggregates on ground but do not incorporate bottom 300 mm of pile into Work.

Slipway Reconstruction	AGGREGATE MATERIALS	Section 31 05 17
River of Ponds, NL		Page 4
PN: 722303		April 2019

3.1 PREPARATION (Cont'd)

.4 (Cont'd)

- .5 Separate different aggregates by strong, full depth bulkheads, or stockpile far enough apart to prevent intermixing.
- .6 Do not use intermixed or contaminated materials. Remove and dispose of rejected materials as directed by Departmental Representative within 48 hours of rejection.
- .7 Stockpile materials in uniform layers of thickness as follows:
 - .1 Max 1.5 m for coarse aggregate and base course materials.
 - .2 Max 1.5 m for fine aggregate and sub-base materials.
 - .3 Max 1.5 m for other materials.
- .8 Uniformly spot-dump aggregates delivered to stockpile in trucks and build up stockpile as specified.
- .9 Do not cone piles or spill material over edges of piles.
- .10 Do not use conveying stackers.
- .11 During winter operations, prevent ice and snow from becoming mixed into stockpile or in material being removed from stockpile.

3.2 CLEANING

- .1 Leave aggregate stockpile site in tidy, well drained condition, free of standing surface water.
- .2 Leave any unused aggregates in neat compact stockpiles as directed by Departmental Representative.
- .3 For temporary or permanent abandonment of aggregate source, restore source to condition meeting requirements of authority having jurisdiction.

Slipway Reconstruction	ROUGH GRADING	Section 31 22 13
River of Ponds, NL		Page 1
PN: 722303		April 2019

PART 1 - GENERAL

- 1.1 DESCRIPTION .1 This section specifies supply, placement and compaction of rockfill and common fill as required or as directed by Departmental Representative.
- 1.2 RELATED REQUIREMENTS
- .1 Section 31 23 33.01 Excavating, Trenching and Backfilling.
- .2 Section 31 32 19.01 Geotextiles.
- 1.3 REFERENCES
- .1 ASTM International
 .1 ASTM D 698-07e1, Test Method for Laboratory
 Compaction Characteristics of Soil Using Standard
 Effort (600 kN-m/m 3).
- .2 Underwriters' Laboratories of Canada (ULC)

1.4 MEASUREMENT FOR .1 PAYMENT

- Rock Fill (38 mm 75 mm): Supply, placement, and compaction of rock fill will be measured by the cubic metre placed measure (CMPM). The volume of material will be determined in place from measurements taken prior to and at completion of the work. Include the cost of all plant, labour, equipment, and materials required to complete the work as specified.
- Rock Fill (75 mm 150 mm): Supply, placement, and compaction of rock fill will be measured by the cubic metre placed measure (CMPM. The volume of material will be determined in place from measurements taken prior to and of completion of the work. Include the cost of all plant, labour, equipment, and materials required to complete the work as specified.
- Rock Fill (100 mm minus): Supply, placement of rock fill will be measured by the cubic metre placed measure (CMPM). Materials required for the backfill will be approved prior to supply and placement. The volume of material will be determined in place from measurements taken prior to and at completion of the work. Include the cost of all plant, equipment, and materials required to complete the work as specified.

Slipway Reconstruction	ROUGH GRADING	Section 31 22 13
River of Ponds, NL		Page 2
PN: 722303		April 2019

1.4 MEASUREMENT FOR PAYMENT

(Cont'd)

- Rock Fill (100 mm 300 mm): Supply, placement, and compaction of rock fill will be measured by the cubic metre placed measure (CMPM). The volume of material will be determined in place from measurements taken prior to and at completion of the work. Include the cost of all plant, labour, equipment, and materials required to complete the work as specified.
- .5 Rock Fill (450 mm 850 mm): Supply and placement of rock fill will be measured by the cubic metre placed measure (CMPM). The volume of material will be determined in place from measurements taken prior to and at completion of the work. Include the cost of all plant, labour, equipment and materials required to complete the work as specified.

PART 2 - PRODUCTS

2.1 ROCK FILL

- .1 Rock fill (38 75 mm) material to following requirements:
 - .1 Crushed quarry stone consisting of hard durable particles free from clay lumps, frozen material and other deleterious materials, and free from splits, seams or defects likely to impair its soundness during handling or under action of water.
 - .2 Relative density: to ASTM C127, not less than 2.65.
 - .3 Rock size to be 85% 95%, 75 mm to 150 mm and with rock no greater than 200 mm dia.
- .2 Rock fill (75 mm 150 mm) material to following requirements:
 - .1 Crushed quarry stone consisting of hard durable particles free from clay lumps, frozen material and other deleterious materials, and free from splits, seams or defects likely to impair its soundness during handling or under action of water.
 - .2 Relative density: to ASTM C127, not less than 2.65.
 - .3 Rock size to be 85% 95% 75 mm 150 mm and with rock no greater than 200 mm dia.
- .3 Rock fill (100 mm minus):

Slipway Reconstruction	ROUGH GRADING	Section 31 22 13
River of Ponds, NL		Page 3
PN: 722303		April 2019

2.1 ROCK FILL (Cont'd)

.3 (Cont'd)

- .1 Crushed quarry stone consisting of hard durable particles free from clay lumps, frozen material and other deleterious materials, and free from splits, seams or defects likely to impair its soundness during handling or under action of water.
- .2 Relative density: to ASTM C127, not less than 2.65.
- .3 Having gradation which are within limits specified when tested to ASTM C136-84A and ASTM C117-87. Sieve size to CAN/CGSB-8.1-88.
- .4 When tested by means of laboratory sieves, it shall fulfill requirements as follows:

Sieve Size	% by Weight Passing
100 mm	85-100
75 mm	55-90
50 mm	35-65
38 mm	25-40
25 mm	15-25
19 mm	7-15
12 mm	3-15
10 mm	3

- .4 Rock fill (100 mm 300 mm) material to following requirements:
 - .1 Crushed quarry stone consisting of hard durable particles free from clay lumps, frozen material and other deleterious materials, and freefrom splits, seams or defects likely to impair its soundness during handling or under action of water.
 - .1 Relative density: to ASTM C127, not less 2.65.than
 - .2 Rock size to be 85% 95% 100 mm 300 mm and with rock no greater than 400 mm dia.
- .5 Rock fill (300 mm 600 mm) material to following requirements:
 - .1 Crushed quarry stone consisting of hard durable particles free from clay lumps, frozen material and other deleterious materials, and free from splits, seams or defects likely to impair its soundness during handling or under action of water.
 - .2 Relative density: to ASTM C127, not less than 2.65.
 - .3 Rock size to be 85% 95% 400 mm 600 mm and with rock no greater than 750 mm dia.

Slipway Reconstructi River of Ponds, NL PN: 722303	on	ROUGH GRADING	Section 31 22 13 Page 4 April 2019
2.1 ROCK FILL (Cont'd)	.6	Rock Fill (450 mm - 850 mm) mater requirements: .1 Crused quarry stone consisting particles free from clay lumps, for and other deleterious materials, splits, seams or defects likely to soundness during handling or underwater2 Relative density: to ASTM C12.653 Rock size to be 450 mm - 850 mo greater than 900 mm dia.	ing of hard frozen materials and free fom to impair its er action of
PART 3 - EXECUTION			
3.1 EXAMINATION	.1	Verification of Conditions: verification of substrate previously installed Sections or are acceptable for reinstallation. 1 Visually inspect substrate in Departmental Representative. 2 Inform Departmental Representative in acceptable conditions immediated discovery. 3 Proceed with installation or unacceptable conditions have been after receipt of approval to proceed to be a pr	d under other ough grading in presence of intative of ely upon after in remedied and
3.2 PLACING ROCK FILL	.1	Only rock fill material approved Representative will be placed. Maplaced uniformly across full crost layers not exceeding 300 mm loose	aterial will be ss-section in
	.2	Use suitable earth moving and sur equipment to place and spread roo continuous and uniform horizontal	ck fill in
	.3	Compact rock fill after each 300	mm lift.
	. 4	Place rock fill to 300 mm below k grade.	pottom of finished

.5 All side slopes to be one (1) vertical to one and one half (1.5) horizontal.

Slipway Reconstruction		ROUGH GRADING	Section 31 22 13
River of Ponds, NL PN: 722303			Page 5
			April 2019
3.3 GRADING .1		Rough grade to levels, profil allowing for surface treatmen	
	.2	Rough grade to following dept grades:	
		.1 50 mm for finished grade	r of Type I material.
	.3	Slope rough grade as indicate	d on drawings.
	. 4	Grade ditches to depth required for maximum run-off as directed.	
	.5	Prior to placing fill over ex scarify surface to depth of 3 placing fill over existing gr and existing surface at appromoisture content to facilitat	00 mm minimum before ound. Maintain fill ximately same
	.6	Compact filled and disturbed maximum dry density to ASTM D .1 95% under roadway and pa	698, as follows:
			•
3.4 TESTING	1	Inspection and testing of soi carried out by testing labora ULC. Costs of tests will be p Departmental Representative i Sections 01 29 83 - Payment P Laboratory Services.	tory designated by aid by Owner n accordance with
3.5 CLEANING .1		Progress Cleaning: clean in a Section 01 74 11 - Cleaning. .1 Leave Work area clean at	
		Final Cleaning: upon completi materials, rubbish, tools and accordance with Section 01 74	equipment in
	.3	Waste Management: separate wa reuse and recycling in accord 01 74 21 - Construction/Demol	ance with Section

facility.

Management and Disposal.

1 Remove recycling containers and bins from site and dispose of materials at appropriate

Slipway Reconstruction	ROUGH GRADING	Section 31 22 13
River of Ponds, NL		Page 6
PN: 722303		April_2019

3.6 PROTECTION

- .1 Protect bench marks, buildings, surface or underground utility lines which are to remain as directed by Departmental Representative. If damaged, restore to original or better condition unless directed otherwise.
- .2 Maintain access roads to prevent accumulation of construction related debris on roads.

Slipway Reconstruction River of Ponds, NL PN: 722303		ROCK REMOVAL	Sect 31 23 16.26 Page 1 April 2019
PART 1 - GENERAL			
1.1 RELATED .2SECTIONS	.1	Section 01 33 00 - Submitta	l Procedure.
	.2	Section 01 74 21 - Construc Management and Disposal.	tion/Demolition Waste
	.3	Section 01 56 00 - Temporar Enclosures.	y Barriers and
	. 4	Section 01 35 29 - Health a	nd Safety Requirements.
	.5	Section 03 30 00 - Cast-in-	Place Concrete.
	.6	Section 31 23 33.01 - Excav Backfilling.	ating, Trenching and
	.7	Section 31 22 13 - Rough Gr	ading.
1.2 MEASUREMENT OF PAYMENT	.1	Rock Removal - will be meas It is defined as all rock r the placement of the concre Quantities will be taken fr showing original rock surfa line as set by Departmental unit price for Rock Removal cost to place and compact a material as fill in accorda 13 - Rough Grading.	emoval carried out for te launchway. om cross-section ce and specified grade Representative. The - shall include the ll suitable excavated
1.3 DEFINITION	.1	Rock: any solid material in which cannot be removed by mechanical excavating equip m³ bucket. Frozen material	means of heavy duty ment with 0.95 to 1.15
	.2	PPV: peak particle velocity	·.
1.4 SUBMITTALS	.1	Blasting Operation .1 Submit to Departmental local authorities having ju approval, written proposal removal of rock by blasting Section 01 33 00 - Submitta	risdiction for of operations for , in accordance with

Slipway Reconstruction		ROCK REMOVAL Sect 31 23 16.26
River of Ponds, NL	511	Page 2
PN: 722303		April 2019
1.4 SUBMITTALS (Cont'd)	.1	(Cont'd) .2 Indicate proposed method of carrying out work, types and quantities of explosives to be used, loading charts and drill hole patterns, type of caps, blasting techniques, blast protection measures for items such as flying rock, vibration, dust and noise control. Include details on protective measures, time of blasting and other pertinent details3 Submit records to Departmental Representative at end of each shift. Maintain complete and accurate record of drilling and blasting operations.
1.5 QUALIFICATIONS	.1	Retain licensed explosives expert to program and supervise blasting work, and to determine precautions, preparation and operations techniques.
1.6 WASTE MANAGEMENT AND DISPOSAL	.1	Separate and recycle waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
	.2	Collect and separate plastic, paper packaging, corrugated cardboard in accordance with Waste Management Plan.
	.3	Place materials defined as hazardous or toxic in designated containers.
	. 4	Ensure emptied containers are sealed and stored safely.
1.7 BLASTING SURVEY AND MONITORING	.1	Departmental Representative will visit property holders of adjacent buildings and structures to determine existing conditions and describe blasting and seismic recording operations and obtain their permission for setting up seismographs.
	.2	Seismographic monitoring will be conducted during entire progress of blasting operations.
1.8 BLASTING AND VIBRATION CONTROL	.1	Reduce ground vibrations to avoid damage to structures or remaining rock mass.

Slipway Reconstructic River of Ponds, NL PN: 722303	n	ROCK REMOVAL	Sect 31 23 16.26 Page 3 April 2019
1.8 BLASTING AND VIBRATION CONTROL (Cont'd)	.2	Carry out trial blasting at the commencement of the blasting work in order to determine the amount of charge required to keep vibrations with safe limits, to the satisfaction of the Departmental Representative. Take seismograph recordings during such trial blastings and at an other time while blastings in contained, as considered necessary by the Contractor for his protection, or as may be directed by the Departmental Representative. Maximum acceleration during the blast must not exceed 50 mm per sec.	
	.3	No increase in charges will be perfurther trial blasting and seismon recordings, as described above.	
	.4.	Repair any damage caused by blast not be permitted or may be limite extent as to ensure the safety of considered necessary by the Depar Representative. For his own prote Contractor is advised to engage a inspection company to carry out a survey.	d to such an structures, if the structures if the structures if the structure is the structure in the structure is the structure is the structure in the structure is the structure is the structure in the structure is the structure is the structure in the structure is the struct
PART 2 - PRODUCTS			
2.1 MATERIALS	.1	Not used.	
PART 3 - EXECUTION			
3.1 PROTECTION	.1	Prevent damage to surroundings and persons in accordance with Section Temporary Barriers and Enclosures post guards, sound warnings and disblasting to take place.	n 01 56 00 - . Erect fencing,
3.2 ROCK REMOVAL	.1	Co-ordinate this Section with Sec Health and Safety Requirements.	etion 01 35 29 -
	.2	Remove rock to alignments, profil sections as indicated.	es, and cross
	.3	Explosive blasting is permitted a indicated.	it locations

Slipway Reconstruction River of Ponds, NL PN: 722303		ROCK REMOVAL Sect 31 23 16.26 Page 4 April 2019
3.2 ROCK REMOVAL (Cont'd)	.3	(Cont'd) .1 Do blasting operations in accordance with local and provincial codes.
	. 4	Use rock removal procedures to produce uniform and stable excavation surfaces. Minimize overbreak, and to avoid damage to adjacent structures.
	.5	Remove boulders and fragments which may slide or roll into excavated areas.
3.3 ROCK DISPOSAL	.1	Relocate rock to service area for fill purposes.

Slipway Reconstructi River of Ponds, NL PN: 722303	on.	EXCAVATING, TRENCHING AND BACKFILLING	Sect 31 23 33.01 Page 1 April 2019
PART 1 - GENERAL			
1.1 RELATED REQUIREMENTS	.1	Section 01 35 43 - Environmental	Procedures.
	.2	Section 01 74 21 - Construction/Management and Disposal.	Demolition Waste
	.3	Section 31 22 13 - Rough Grading	
	. 4	Section 31 32 19.01 - Geotextile:	s.
1.2 MEASUREMENT PROCEDURES	.1	No measurement for payment to be section. Include costs in unit powhich excavating, trenching, and required.	rices for item for
1.3 REFERENCES	.1	American Society for Testing and .1 ASTM C 117-04, Standard Test Material Finer than 0.075 mm (No Mineral Aggregates by Washing2 ASTM C136-05, Standard Test Analysis of Fine and Coarse Aggre .3 ASTM D422-63 (2002), Standard Particle-Size Analysis of Soils4 ASTM D698-12e, Standard Test Laboratory Compaction Characterist Using Standard Effort (12,400 ft kN-m/m³)5 ASTM D4318-05, Standard Test Liquid Limit, Plastic Limit, and of Soils.	t Method for .200) Sieve in Method for Sieve egates. rd Test Method for t Methods for stics of Soil -lbs/ft³) (600
	.2	Canadian General Standards Board .1 CAN/CGSB-8.1-88, Sieves, Testinch Series. .2 CAN/CGSB-8.2-M88, Sieves, Testince, Metric.	sting, Woven Wire,
1.4 DEFINITIONS	.1	Excavation classes: two classes of be recognized; common excavation excavation.	

Slipway Reconstruction	EXCAVATING, TRENCHING AND	Sect 31 23 33.01
River of Ponds, NL	BACKFILLING	Page 2
PN: 722303		April 2019

1.4 DEFINITIONS (Cont'd)

.1 (Cont'd)

- .1 Rock: any solid material in excess of 0.25 $\rm m^3$ and which cannot be removed by means of heavy duty mechanical excavating equipment with 0.95 to $1.15\rm m^3$ bucket. Frozen material not classified as rock.
- .2 Common excavation: excavation of materials of whatever nature, which are not included under definitions of rock excavation.
- .2 Waste material: excavated material unsuitable for use in Work or surplus to requirements.
- .3 Borrow material: material obtained from locations outside area to be graded, and required for construction of fill areas or for other portions of Work.
- .4 Unsuitable materials:
 - .1 Weak and compressive materials under excavated areas.
 - .2 Frost susceptible materials under excavated areas.
 - .3 Frost susceptible materials:
 - .1 Fine grained soils with plasticity index less than 10 when tested to ASTM D4318, and gradation within limits specified when tested to ASTM D422 and ASTM C136: Sieve sizes to CAN/CGSB-8.1.
 - .2 Table:

Sieve Designation	% Passing
2.00 mm	100
0.10 mm	45 - 100
0.02 mm	10 - 80
0.005 mm	0 - 45

- .3 Coarse grained soils containing more than 20% by mass passing 0.075 mm sieve.
- .5 Unshrinkable fill: very weak mixture of Portland cement, concrete aggregates and water that resists settlement when placed in utility trenches, and capable of being readily excavated.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Type 1 fill: to the following requirements:
 - .1 Crushed, pit run or screened stone, gravel or sand.
 - .2 Gradations to be within limits specified when tested to ASTM C136. Sieve sizes to CAN/CGSB-8.1.

Slipway Reconstruction	EXCAVATING, TRENCHING AND	Sect 31 23 33.01
River of Ponds, NL	BACKFILLING	Page 3
PN: 722303		April 2019

Sieve	% Passing	
Designation		
	Type 1	
101.6 mm	100	
50 mm	75-100	
4.75 mm	25-55	
1.2 mm	10-35	
0.3 mm	5-20	
0.075 mm	0-12	

PART 3 - EXECUTION

3.1 SITE PREPARATION

.1 Remove obstructions, ice and snow, from surfaces to be excavated within limits indicated.

3.2 EXCAVATION

- .1 Excavate to lines, grades, elevations and dimensions as indicated.
- .2 Remove all cribwork and other obstructions encountered during excavation in accordance with Section 02 41 16 Sitework, Demolition and Removal.
- .3 Excavation is required for the area shown at the existing parking lot as outlined in the project drawings.
- .4 Excavation for water line installation as shown on project drawings.
- .5 Excavation as required for the installation of new storm drainage system as shown on project drawings.
- .6 Excavation must not interfere with bearing capacity of adjacent foundations.
- .7 Dispose of surplus and unsuitable excavated material in approved location off site. Refer to Section 01 35 43 Environmental Procedures.
- .8 Do not obstruct flow of surface drainage.
- .9 Earth bottoms of excavations to be undisturbed soil, level, free from loose, soft or organic matter.

Slipway Reconstruction River of Ponds, NL		EXCAVATING, TRENCHING AND BACKFILLING	Sect 31 23 33.01 Page 4
PN: 722303			April 2019
3.2 EXCAVATION (Cont'd)	.10	Notify Departmental Representate excavation is reached.	rive's approval of
	.11	Obtain Departmental Representat completed excavation.	ive's approval of
•	.12	Excavated materials from the probe disposed of at an approved ponly.	-
3.3 FILL TYPES AND COMPACTION	.1	Use fill of types as indicated.	
3.4 BACKFILLING .1 .2 .3 .4		Do not proceed with backfilling Departmental Representative has approved installations.	-
		Areas to be backfilled to be fr snow, ice, water and frozen gro	
		Do not use backfill material who contains ice, snow or debris.	aich is frozen or
		Place backfill material in unif exceeding 150 mm compacted thic indicated. Compact each layer b succeeding layer.	kness up to grades
	.5	Backfilling around installation .1 Place bedding and surround specified elsewhere2 Do not backfill around or concrete within 24 hours after concrete3 Place layers simultaneous installed Work to equalize load to exceed 1.0 m.	over cast-in-place placing of
3.5 RESTORATION	.1	Upon completion of Work, remove and debris, trim slopes, and co directed by Departmental Repres	rrect defects as
	.2	Clean and reinstate areas affective directed by Departmental Representations	
	.3	Restore site to its normal state excavation.	te prior to

Slipway Reconstruction GEOTEXTILES Sect 31 32 19.01
River of Ponds, NL Page 1
PN: 722303 April 2019

PART 1 - GENERAL

1.1 SECTION INCLUDES

- .1 Materials and installation of polymeric geotextiles used in retaining wall structures, filtration, drainage structures and roadbeds, purpose of which is to:
 - .1 Separate and prevent mixing of granular materials of different grading.
 - .2 Act as hydraulic filters permitting passage of water while retaining soil strength of granular structure.

1.2 RELATED WORK

- .1 Section 01 33 00 Submittal Procedures.
- .2 Section 01 74 21 Construction/Demolition Waste Management and Disposal.
- .3 Section 31 22 13 Rough Grading.
- .4 Section 31 23 33.01 Excavating, Trenching and Backfilling.
- .5 Section 31 53 13 Treated Timber Cribwork.

1.3 REFERENCES

- .1 ASTM Society for Testing and Materials (ASTM)
 - .1 ASTM D4491-99a(2004)e1, Standard Test Methods for Water Permeability of Geotextiles by Permittivity.
 - .2 ASTM D 4595-05, Standard Test Method for Tensile Properties of Geotextiles by the Wide-Width Strip Method.
 - .3 ASTM D 4716-04, Standard Test Method for Determining the (In-Plane) Flow Rate Per Unit Width and Hydraulic Transmissivity of a Geosynthetic Using a Constant Head.
 - .4 ASTM D 4751-04, Standard Test Method for Determining Apparent Opening Size of a Geotextile.
- .2 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-4.2-M88, Textile Test Methods.
 - .2 CAN/CGSB-148.1, Methods of Testing Geotextiles and Geomembranes.
 - .1 No.2-M85, Mass per Unit Area.
 - .2 No.3-M85, Thickness of Geotextiles.
 - .3 No.7.3-92, Grab Tensile Test for Geotextiles.

Slipway Reconstruction River of Ponds, NL PN: 722303			Sect 31 32 19.01 Page 2 April 2019
1.3 REFERENCES (Cont'd)	.2	(Cont'd) .2 (Cont'd) .4 No. 6.1-93, Bursting Str	
	.3	Geotextiles Under No Compress Canadian Standards Association (CS.1 CAN/CSA-G40.20-04/G40.21-04, Requirements for Rolled or Welded Quality Steel2 CAN/CSA-G164-M92(R2003), Hot of Irregularly Shaped Articles.	A) General Structural
1.4 SAMPLES	.1	Submit samples in accordance with - Submittal Procedures.	Section 01 33 00
	.2	Submit to Departmental Representat following samples at least 2 weeks commencing work. 1 Minimum length of 6 m of roll geotextile.	prior to
1.5 MILL CERTIFICATES	.1	Submit to Departmental Representat mill test data and certificate at prior to start of work.	
1.6 DELIVERY AND STORAGE	.1	During delivery and storage, prote from direct sunlight, ultraviolet heat, mud, dirt, dust, debris and	rays, excessive
1.7 WASTE MANAGEMENT AND DISPOSAL	.1	Separate waste materials for reuse in accordance with Section 01 74 2 Construction/Demolition Waste Mana Disposal.	1 -
	.2	Remove from site and dispose of al materials at appropriate recycling	
	.3	Collect and separate for disposal polystyrene, corrugated cardboard, material, in appropriate on-site be recycling in accordance with Waste Plan.	and packaging oins, for
	. 4	Fold up metal banding, flatten and designated area for recycling.	l place in

Slipway Reconstruction	GEOTEXTILES	Sect 31 32 19.01
River of Ponds, NL		Page 3
PN: 722303		April 2019

1.8 MEASUREMENT FOR .1 PAYMENT

Geotextiles: Measurement for payment under this section will be measured by the square metre (m²). Include cost in unit price of all plant, labour, equipment required to complete the work as specified.

PART 2 - PRODUCTS

2.1 MATERIAL

- .1 Non-woven, mechanically bounded, needle punched polyester membrane, suitable for use in seawater environment.
- .2 Physical properties:
 - .1 Thickness: to CAN/CGSB-148.1, No.3, minimum 4.7 mm.
 - .2 Mass per unit area: to CAN/CGSB-148.1, No.2, minimum 400 g/m 2 .
 - .3 Tensile strength and elongation (in any principal direction): to ASTM D4595.
 - .1 Tensile strength: minimum 1180 N, wet condition.
 - .2 Elongation at break: 50 to 100 percent.
 - .3 Seam strength: equal to or greater than tensile strength of fabric.
 - .4 Mullen burst strength: to CAN/CGSB-4.2, method 11.1, minimum 3850 kPa.
 - .5 Tear propagation (CAN-12-2) 530N.
- .3 Hydraulic properties:
 - .1 Apparent opening size (AOS): to ASTM D4751, 50 to 150 micrometres.
 - .2 Permittivity: to ASTM D4491, 0.25 cm per second.
- .4 Securing pins and washers: to CAN/CSA-G40.21, Grade 300W, hot-dipped galvanized with minimum zinc coating of 600 q/m^2 to CAN/CSA G164.

PART 3 - EXECUTION

3.1 INSTALLATION

- .1 Place one (1) layer of geotextile material as indicated on drawings.
- .2 Place geotextile material by unrolling onto graded surface in orientation, manner and locations indicated and retain in position with securing pins and washers.

		_	
Slipway Reconstruction River of Ponds, NL PN: 722303		GEOTEXTILES	Sect 31 32 19.01 Page 4 April 2019
3.1 INSTALLATION (Cont'd)	.3	Place geotextile material on sloping surfaces in one continuous length from toe of slope to upper extent of geotextile.	
	. 4	Place geotextile material smooth and free of tension stress, folds, wrinkles and creases.	
	.5	Overlap each successive strip of over previously laid strip.	geotextile 600 mm
	.6	Join successive strips of geotext	ile by sewing.
	.7	Pin successive strips of geotextipins at 300 mm interval at mid poindicated.	3
	.8 Protect installed geotextile m displacement, damage or deteri during and after placement of		tion before,
	.9	After installation, cover with ov within 4 hours of placement.	erlying layer
	.10	Replace damaged or deteriorated g approval of Departmental Represen	
	.11	Place and compact soil layers in Section 31 23 33.01 - Excavating, Backfilling.	
3.2 CLEANING	.1	Remove construction debris from P dispose of debris in an environme responsible and legal manner.	
3.3 PROTECTION	.1	Vehicular traffic not permitted degeotextile.	irectly on

Slipway Reconstruction TIMBER CRIBWORK Section 31 53 13
River of Ponds, NL Page 1
PN: 722303 April 2019

PART 1 - GENERAL

1.1 DESCRIPTION

.1 This section specifies requirements for supply and installation of treated timber and necessary fastenings for fabrication, placing, and ballasting of timber cribwork.

1.2 RELATED SECTIONS

- .1 Section 01 74 21 Construction/Demolition Waste Management and Disposal.
- .2 Section 06 05 73 Wood Treatment.

1.3 MEASUREMENT FOR PAYMENT

- Treated Timber Cribwork (Supply and Install): to be measured in cubic metres (m³) of completed work which include ballast stone, gravel, treated timber, end of wharf blocking, fastenings, and all plant, labour, materials and equipment to perform work.
- .2 Measure timber cribwork in cubic metres determined by product. Use following dimensions measured in place:
 - .1 Height: average of measurements taken at each vertical from bottom of lowest timber to top side of uppermost course of timber.
 - .2 Width: average of measurements between outside faces of exterior longitudinal timbers, each width measured on top ties of each row of cross ties.
 - .3 Length: measured horizontally along centre-line of crib between outside faces of exterior cross ties.
- .3 Cribwork below step will be determined by product of following dimensions measured in place:
 - .1 Height: average of measurements taken at each vertical from bottom of lowest timber to top side of uppermost course of timber.
 - .2 Width: average of measurements between outside faces of exterior longitudinal timbers, measured at each crosstie at low water elevations.
 - .3 Length: measured horizontally along centre-line of crib and parallel to level water surface between outside faces of exterior cross ties.
- .4 Cribwork above step will be determined by product of following dimensions measured in place:

Slipway Reconstruction River of Ponds, NL PN: 722303	n	TIMBER CRIBWORK	Section 31 53 13 Page 2 April 2019
1.3 MEASUREMENT FOR .4 PAYMENT (Cont'd)		faces of exterior longitudin measured on top tier of each	rements between outside al timbers, each width row of crossties. Intally along centre-line al water surface between
	.5	Measurements of the vertical lengths of cribwork, will be of both the Contractor and to Representative and will be wooth parties on the site to	taken in the presence the Departmental verified and signed by
1.4 SAFETY REQUIREMENTS	.1	Worker protection: .1 Workers must wear glove masks, long sleeved clothing protective clothing when han cutting or sanding preservat applying preservative materi. 2 Workers must not eat, dapplying preservative materi. 3 Clean up spills of presimmediately with absorbent mof absorbent material to san	d, eye protection, dling, drilling, sawing, live treated wood and als. drink or smoke while al. ervative materials saterial. Safely discard
1.5 REFERENCES .1		American Society for Testing International) .1 ASTM A307-12, Specifical Bolts and Studs, 60,000 PSI .2 ASTM C136-06, Standard Analysis of Fine and Coarse .3 ASTM-A123/A123M-13, Stazinc (Hot-Dip Galvanized) Coproducts)4 ASTM F1667-13, Standard Driven Fasteners: Nails, Spi	Tensile. Tensile. Test Method for Sieve Aggregates. Indard Specification for Patings on Iron and Steel
	. 2	American Wood-Preserver's As .1 AWPA M4-11, Standard fo Preservation - Treated Wood	or the Care of
	.3	Canadian Standards Associati	

.1 CSA B111-1974(R2003), Wire Nails, Spikes and Staples.

Slipway Reconstructi River of Ponds, NL PN: 722303	.on	TIMBER CRIBWORK	Section 31 53 13 Page 3 April 2019
1 5 00000000	_		
1.5 REFERENCES (Cont'd)	.3	(Cont'd) .2 CAN/CSA-G40.20-13/G40.21-13, Requirements for Rolled or Welded Steel/Structural Steel3 CAN/CSA-O80 Series-00 (R2012 Preservation.	Structural Quality
	. 4	Canadian Wood Council .1 Wood Design Manual.	
	.5	National Lumber Grades Authority .1 Standard Grading Rules for C edition.	•
1.6 SUBMITTALS	.1	Ballast: .1 Submit proposed placing meth Representative for approval, prio ballast.	_
1.7 WASTE MANAGEMENT	.1	Remove from site and dispose of pat appropriate recycling faciliti	
	.2	Dispose of all corrugated cardboa plastic packaging material in app bin for recycling.	
	.3	Place materials defined as hazard designated containers.	lous or toxic in
	. 4	Ensure emptied containers are sea safely.	led and stored
	.5	Do not dispose of preservative trincineration.	reated wood through
	.6	Do not dispose of preservative trother materials destined for recy	
	.7	Dispose of treated wood, end piece sawdust at a sanitary landfill.	es, wood scraps and
	.8	Dispose of unused preservative made official hazardous material collections of unused preservative made system, streams, lakes, on ground location where they will pose a helicontent of the control of t	ctions site. Do not terial into sewer lor in any other

Slipway Reconstruction TIMBER CRIBWORK Section 31 53 13
River of Ponds, NL Page 4
PN: 722303 April 2019

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Timber: Use timber graded and stamped in accordance with applicable grading rules and standards of associations or agencies approved to grade lumber by Canadian Lumber Standards Accreditation Board of
- .2 Species: Douglas Fir, Pacific Coast Hemlock and Eastern Hemlock.
- .3 Grade: No. 1 Structural.
- .4 Grading authority: NLGA.
- .5 Preservative treatment: To CSA 080 for coastal waters and Section 06 05 73 Wood Treatment. Supply timbers in lengths required. Cut and field treat timbers only as may be necessary to suit site conditions. Contractor will have on site sufficient lengths and thickness of treated timber to permit levelling of cribs after ballasting operations.
- .6 Miscellaneous steel: Medium structural steel conforming to CSA Specification G40.21 "Structural Quality Steels".
 - .1 Hot dip galvanized: to ASTM A123/A123M. Minimum weight of zinc coating as stated in Table 1 of this Standard. Fabricator to adhere to recommendations of Standard.
 - .2 Wire nails, spikes, staples: to CSA-B111 or ASTM F1667.
 - .3 Bolts, nuts, washers: to ASTM A307.
 - .4 Drift Bolts: to G40.21 from round stock, button head and diamond or wedge point.
 - .5 Washers:
 - .1 Round Plate Washers: for 19 mm diameter machine bolts, 79 mm diameter by 7.9 mm thick, with hole diameter of 21 mm. Washers to G40.21.
 - .2 Square washers not permitted to be used.
 - .6 All hardware galvanized.
- .7 Ballast for filling cribs to following requirements:
 - .1 Stone, consisting of hard durable particles free from clay lumps, organic material and other deleterious materials.
 - .2 Dry density in place: minimum 2600 kg per cubic metre.
 - .3 Ballast stone to be well graded with maximum sizes not exceeding 400 mm on any side and minimum size of not less than 250 mm on any side.

Slipway Reconstruction		TIMBER CRIBWORK	Section 31 53 13
River of Ponds, NL			Page 5
PN: 722303			April 2019
2.1 MATERIALS (Cont'd)	.8	Gravel: Evenly graded pit r maximum size, 50 mm, with n the 0.075 mm sieve.	
PART 3 - EXECUTION			
3.1 PREPARATION	.1	Excavate area of crib base drawings or to hard bottom, Representative.	
	.2	Contractor to confirm with Representative that excavat for cribwork placement.	
	.3	Before construction, stockp completely fill cribs. Prov equipment to keep crib in p alignment during sinking op	ride suitable plant and proper position and
	. 4	Take closely spaced accurate centre to centre or less, per template, to determine acturate area of crib. Construct cribe configuration. Scribe cribe required.	recisely located by lal configuration of base bottom to match base
	.5	Cribs out of alignment or n be replaced in correct posi	
3.2 CRIB CONSTRUCTION	.1	bottom timbers to conform to .2 Place levelling pieces	s horizontally. Ses at intersections of posts, and other
	.2	to form bottom three course .2 Crosswise bottom timbe .3 Lengthwise bottom timb	ers to be of one piece. Ders to be of one piece. Def bottom timbers together To intersection with each

.3

Ballast floor:

Slipway Reconstruction	TIMBER CRIBWORK	Section 31 53 13
River of Ponds, NL		Page 6
PN: 722303		April 2019

3.2 CRIB CONSTRUCTION (Cont'd)

.3 (Cont'd)

- .1 Place ballast floor on pockets on bottom or middle course of bottom timbers.
- .2 Ballast floor timber to be spaced evenly with no space greater than 100 mm.
- .3 Secure each ballast floor timber to bottom timbers with drift bolts securing adjacent ballast floor timbers to same bottom timber.

.4 Longitudinals:

- .1 Longitudinals one length for individual cribs.
- .2 Longitudinals minimum 6100 mm long.
- .3 Where cribs are married together, longitudinals of sufficient length to span a minimum of a half a bay of one crib and one and a half bays of the adjacent crib.
- .4 Butt join exterior and interior longitudinals a minimum distance of 600 mm from crosstie with joint in centre of a 1200 mm long joiner block.
- .5 Secure block to lower timber with drift bolt at centre and secure longitudinals and splice at ends to block with drift bolts.
- .6 Stagger joints in longitudinal timbers. Do not join in same bay or on same vertical post.
- .7 Secure longitudinals to intersection of cross ties with drift bolt and to intersection of vertical posts with machine bolt every third course of longitudinals, along with the top course.
- .8 Countersink machine bolts on exterior face.
- .5 Cross ties: one length across cribs.
 .1 Secure cross ties to intersection of longitudinals with drift bolt and to intersection of vertical posts with machine bolt every third course of cross tie, along with the top course.
- .6 Vertical posts: one length from bottom of cribwork to top of cribwork. Locate one vertical post at corner of each crib and at intersection of crossties with longitudinals.
- .7 Blocking: install treated timber filler blocking as indicated on drawings.
 - .1 Cut blocking exact length to completely fill spaces and such that the total thickness of crossties and longitudinals carrying the bearing weight of the deck be a minimum of 600 mm if cribwork ends on a crosstie.
 - .2 If cribwork ends on a longitudinal one additional tier of blocking is required.
 - .3 Blocking of same size and material as crossties or longitudinals and fastened with 2 drift bolts into timber immediately below it.

Slipway Reconstruct: River of Ponds, NL PN: 722303	ion	TIMBER CRIBWORK Section 31 53 13 Page 7
PN: 722303	=	April 2019
3.2 CRIB CONSTRUCTION (Cont'd)	.8	Levelling: treated timber required for levelling of cribwork after ballasting, must be full width continuous over entire length to be levelled.
	.9	Bolt Sizing and Holing: .1 Drift Bolts: length of drift bolts equal to thickness of timbers fastened less 50 mm, unless otherwise specified. Bore holes for drift bolts 2 mm smaller diameter than bolt and for full length of bolt2 Machine Bolts: length of machine bolts equal to
		thickness of timbers fastened plus thickness of washers plus 40 m. Where bolts are countersunk, the length, as noted above, less depth of countersink. Thread machine bolts for 64 mm. Bore holes for machine bolts to same diameter as bolts.
3.3 HANDLING TREATED TIMBER	.1	Handle treated material without damaging original treatment1 Replace treated timber with major damage to original treatment, as instructed by Departmental Representative.
	.2	Field treatment: to CAN/CSA-080. Apply and saturate cuts, minor surface damage, abrasions, and nail and spike holes with preservative.
	.3	Ripping of treated timber not permitted without prior approval of Departmental Representative.
3.4 BALLAST	.1	Place ballast to avoid damage to timber cribwork.
	.2	Place ballast so that differential height of fill between adjacent cells, at any time, will be less than 1 m.
	.3	Pockets of cribs ballasted within 150 mm of top of crib timbers.
3.5 TOLERANCES	.1	1 in 300 in overall dimensions.
	.2	Locate cribs within 100 mm of location as indicated. Horizontal misalignment within 100 mm along the outside faces.
	.3	Space between ballasted cribs within 200 mm. No payment for this space will be made.

Slipway Reconstruction River of Ponds, NL PN: 722303		TIMBER CRIBWORK	Section 31 53 13 Page 8 April 2019
3.6 PROTECTION	.1	Protect work from damage other sections and from denvironmental conditions.	lamage resulting from
	.2	Repair or replace portion additional cost if damage	
3.7 END OF WHARF	.1	Install end of wharf bloc	king as detailed on the

drawings.

BLOCKING

PART 1 - GENERAL

1.1 DESCRIPTION

- .1 This section specifies requirements for supply and installation of structural timber as follows:
 - .1 Supply and installation of treated dimension timber wheelguard, wheelguard blocking, and associated painting.
 - .2 Supply and installation of treated dimension timber support beams and associated blocking.
 - .3 Supply and installation of untreated dimension hardwood slipway runners and wood decking c/w associated fasteners.

1.2 RELATED WORK

- .1 Section 02 41 16 Sitework, Demolition and Removal.
- .2 Section 03 30 00 Cast-in-Place Concrete.
- .3 Section 06 05 73 Wood Treatment.
- .4 Section 31 53 13 Timber Cribwork.

1.3 REFERENCES

- .1 American Society for Testing and Materials (ASTM International)
 - .1 ASTM A307-12, Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile.
 - .2 ASTM-A123/A123M-13, Standard Specification for Zinc (Hot Dip Galvanized) Coatings on Iron and Steel Products.
 - .3 ASTM F1667-13, Standard Specification for Driven Fasteners: Nails, Spikes, and Staples.
- .2 American Wood-Preserver's Association (AWPA)
 - .1 AWPA M4-11, Standard for the Care of Preservation Treated Wood Products.
- .3 Canadian Standards Association (CSA International)
 - .1 CSA B111-1974(R2003), Wire Nails, Spikes and Staples.
 - .2 CAN/CSA-G40.21-04, General Requirements for Rolled or Welded Structural Quality Steel/Structural Steel.
 - .3 CAN/CSA-080 Series-08 (R2012), Wood Preservation.
- .4 Canadian Wood Council
 - .1 Wood Design Manual.

Slipway Reconstruct River of Ponds, NL PN: 722303	ion	STRUCTURAL TIMBER	Section 31 53 16 Page 2 April 2019
1.3 REFERENCES (Cont'd)	.5	National Lumber Grades Authorit .1 Standard Grading Rules for edition.	
1.4 DIMENSIONS	1	Check existing site dimensions discrepancies to Departmental Ecommencing work.	-
1.5 PROTECTION	.1	Avoid dropping, bruising or bre	eaking of wood fibres.
•	.2	Avoid breaking surfaces of trea	ated timber.
	.3	Do not damage surfaces of treat holes or driving nails or spike support temporary material or s	es into them to
	. 4	Treat cuts, breaks or abrasions treated timber with 3 brush cos CSA 080.	
	. 5	Treat bolt holes, cutoffs and accordance with CSA 080.	field cuts in
1.6 DELIVERY AND STORAGE	.1	Store timber horizontally, ever piled permit circulation when a period.	
	.2	When handling long timber, prosufficient number of points, proprevent damage due to excessive	roperly located to
	.3	Handle treated timber with hem rope slings or other approved will not damage surface.	
	. 4	Do not use sharp pointed tools timber. Any timber so handled to be replaced at Contractor's exp	will be rejected and

Slipway Reconstruction	STRUCTURAL TIMBER	Section 31 53 16
River of Ponds, NL		Page 3
PN: 722303		April 2019

1.7 MEASUREMENT FOR .1 PAYMENT

- Structural Timber (Supply and Install):

 .1 <u>Treated Dimension Timber:</u> The supply and installation of treated dimension timber for wheelguard, wheelguard blocking, support beams and decking will be measured by the cubic metre (m³) of timber secured in place, including all timber, fastenings, plant, material, equipment, labour, wheelguard bolt hole levelling sealant, painting of wheelguard and wheelguard blocking.
- <u>.2</u> <u>Untreated Dimension Hardwood Timber:</u> The supply and installation of untreated dimension hardwood timber for hardwood runners, as specified will be measured by the cubic metre (m³) of timber secured in place including all timber, fastenings, plant, material, equipment, and labour.
- .2 Payment for all dimension timber will be made on volume calculated from nominal sizes as indicated on drawing and specified, eq. 200mm x 200mm.

PART 2 - PRODUCTS

2.1 TIMBER MATERIALS

- .1 Timber: Use timber graded and stamped in accordance with applicable grading rules and standards of associations or agencies approved to grade lumber by Canadian Lumber Standards Administration Board of CSA.
- .2 Species
 - .1 Wheelguard, wheelguard blocks, decking and beams: Hemlock or Douglas Fir (CCA or ACA treated).
 - .2 Hardwood runners: Birch or Maple untreated).
- .3 Grade: No. 1 Structural Grade
- .4 Grading Authority: NLGA
- .5 Preservative Treatment: Treat to CSA 080, for coastal waters and Section 06 05 73 Wood Treatment. Timbers will be treated in the lengths required. Unnecessary field cutting will not be permitted.
- .6 Primer: Alkyd undercoat, exterior oil wood primer, similar to Pittsburgh 6-9.
- .7 Paint: Alkyd/Oil Resin paint similar to Pittsburgh Paints "Safety Yellow" Product ID 7-808. Paint to conform to CAN/CGSB-1.61-2004.

Slipway Reconstruction	STRUCTURAL TIMBER	Section 31 53 16
River of Ponds, NL		Page 4
PN: 722303		April 2019

2.2 MISCELLANEOUS STEEL AND FASTENINGS

- .1 Miscellaneous Steel: All steel and fastenings to be CSA G40.21, Grade 300 W, galvanized.
- .2 Nails and Spikes: to CSA B111 or ASTM F1667.
- .3 Machine Bolts and Nuts: to ASTM A307. All machine bolts and nuts to be galvanized.
- .4 Drift Bolts: to G40.21 from round stock button head and diamond or wedge point. All drift bolts to be galvanized.

.5 Washers:

- .1 Round Plate Washers: for 16 mm machine bolts will be 76 mm diameter by 6.4 mm thick, for 19 mm machine bolts will be 79 mm diameter by 7.9 mm thick and have a hole diameter of 18 mm and 21 mm diameter respectively. Washers to conform to G40.21. All washers to be galvanized.
- .2 Plain Washers: to CSA B19.1, Class 2. All washers to be galvanized.
- .3 Square washers are not permitted.
- .6 Galvanizing: will conform to ASTM A123/A123M. Unless otherwise specified, minimum weight of zinc coating will be as stated in this standard. Fabricator is to adhere to recommendations of standard.
- .7 Lag Screws: to CSA B34, galvanized lag screw washers will conform to CSA B19.1
- .8 Welding in accordance with CSA Standards. The welders will be qualified to the appropriate classification as stated in CSA W47.1 "Certification of Companies for Fusion Welding of Steel Structures." Conform welding to all appropriate requirements and recommendations of CSA Standard W59 "Welded Steel Construction" (metal arc welding).

2.3 ANCHOR BOLTING SYSTEM

- .1 Anchor bolts, where required, for anchoring beams and/or wheelguard to concrete footings, piers will be 19mm diameter resin cartridge anchors or heavy duty expansion anchors to required embedment.
- .2 Anchor rods where required for anchor beams to concrete support piers to be 19 mm diameter galvanized steel rods c/w galvanized nuts and washers.
- .3 Submit shop drawings and manufacturer's specification for anchor bolts for approval.

Slipway Reconstruction River of Ponds, NL		STRUCTURAL TIMBER	Section 31 53 16 Page 5
PN: 722303			April 2019
2.3 ANCHOR BOLTING SYSTEM (Cont'd)	. 4	Anchor bolts to be installed w to manufacture specifications.	
PART 3 - EXECUTION			
3.1 PREPARATION	.1	Install structural timbers to drawings or as specified.	details shown on
3.2 WHEELGUARD AND WHEELGUARD BLOCKING	· · · · · · · · · · · · · · · · · · ·		lengths of 6100 mm or t joints made over d timbers to be
	.2	Wheelguard blocks will be inst centre or as required to suppo	
	.3 Wheelguard will be secured through wheelguble blocking, with two (2) 19 mm diameter bolt on detail drawings.		
	. 4	The installation of wheelguard blocking as per detail.	and wheelguard
3.3 BEAMS	.1	Timber beams to be 200 mm x 20 minimimum lengths of 6100 mm o required to fit. Beam lengths indicated on drawings.	r as specially
	.2	Timber beams will be installed at the upper portion of the sl spacing at the lower section.	
	.3	Timber beams to be secured to piers as detailed on drawings, down brackets, anchor bolts and	which includes hold
	. 4	Timber beam to be secured to t diameter x 750 mm long galvani Countersink heads and see deta	zed drift bolts.

Slipway Reconstructi	.on	STRUCTURAL TIMBER	Section 31 53 16
River of Ponds, NL PN: 722303			Page 6 April 2019
			1023
3.4 DECKING .1		Decking timber to be 75 mm x 150 minimum lengths of 6100 mm or as Butt joints to alternate on timb	s specially required.
	.2	Secure decking with 2 - 150 mm l spikes at each beam location.	ong galvanized
	.3	Treat all saw cut butt joints.	
3.5 HARDWOOD RUNNERS	.1	Hardwood runners to be 100 mm x in minimum lengths of 6100 mm or required to fit. Hardwood runner ontop 25 mm on each side as show	as specially stocks to be chamfered
	.2	Hardwood runners will be install centre.	ed at 900 mm on
	.3	Hardwood runners will be secured beamswith 2 - 12 mm diameters x galvanized lag screw at each bea	200 mm long
	. 4	Countersink lag screw head flush	n with top of runner.
			•
3.6 PAINTING	.1	Paint four (4) sides of wheelguawheelguard blocking, as directed Representative.	
	.2	Use one (1) coat of exterior oil (2) coats of alkyd/oil resin pair Paint materials for each coat to single manufacturer as specified coat of primer or paint is dry kapplied.	Int as specified. b be product of a d. Ensure previous
3.7 BOLT SIZING		Anchor Bolts: Anchor bolts used have a length as shown on drawin specified. Holes for anchor bolt smaller diameter than size of st full length of bolts.	ngs unless otherwise ts will be bored 2 mm
	.2	Machine Bolts: Machine bolts use a length equal to thickness of t fastened plus thickness of washe bolts are countersunk, the lengt less depth of countersinking. Ma threaded for 64 mm. Holes will be diameter as bolt.	cimbers being ers plus 40 mm. Where th will be as above achine bolts will be

Slipway Reconstruction	STRUCTURAL TIMBER	Section 31 53 16
River of Ponds, NL		Page 7
PN: 722303		April 2019

3.7 BOLT SIZING (Cont'd)

- Lag Screws: All lag screws used in the work will have a length equal to thickness of timbers being fastened less 50 mm and depth of countersinking. Holes for lag screws to be drilled same diameter as shank portion of screw and to inside thread diameter for threaded portion of screw and for full length. All lag screws will be countersunk, screwed, not driven in place, and will have one (1) standard washer under the head.
- .4 Countersink bolts in beams, runners, wheelguard, and slipway runners to the extent that the minimum distance from face of timber to head of bolt is 12 mm.
- .5 Bolting of timbers without properly drilled bolt holes will not be accepted.

PART 1 - GENERAL

1.1 RELATED SECTIONS

- .1 Section 01 45 00 Quality Control.
- .2 Section 01 74 21 Construction/Demolition Waste Management and Disposal.
- .3 Section 31 05 17 Aggregate Materials.

1.2 MEASUREMENT PROCEDURES

- Type 1 Granular Base: will be measured in cubic metres (m³). Supply, placement and compaction of Type 1 granular base including the cost of all plant, labour, equipment and materials required to complete the work as specified.
- .2 Type 2 Granular Sub Base: will be measured in cubic meters (m³). Supply, placement and compaction of Type 2 granular sub base including the cost of all plant, labour, equipment and materials required to complete the work as specified.

1.3 REFERENCES

- .1 American Society for Testing and Materials (ASTM)
 .1 ASTM C117-13, Standard Test Method for Material
 Finer Than 0.075 mm Sieve in Mineral Aggregates by
 - Finer Than 0.075 mm Sieve in Mineral Aggregates by Washing.
 - .2 ASTM C131-06, Standard Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine.
 - .3 ASTM C117-06, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregate.
 - .4 ASTM D698, Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort $(12,400\text{ft-lbf/ft}^3)$ (600kN-m/m^3) .
 - .5 ASTM D1557, Test Method for Laboratory Compaction Characteristics of Soil Using Modified Effort $(56,000ft-lbf/ft^3)$ $(2,700kN-m/m^3)$.
 - .6 ASTM D1883, Standard Test Method for CBR (California Bearing Ratio) of Laboratory Compacted Soil.
 - .7 ASTM D4318, Standard Test Methods for Liquid Limit, Plastic Limit and Plasticity Index of Soils.
- .2 Canadian General Standards Board (CGSB)
 .1 CAN/CGSB-8.1-88, Sieves, Testing, Woven Wire,
 Inch Series.

Slipway Reconstruction River of Ponds, NL PN: 722303		AGGREGATE BASE COURSES	Section 32 11 23 Page 2 April 2019 ves, Testing, Woven Wire,	
1.3 REFERENCES (Cont'd)	.2 (Cont'd) 2 CAN/CGSB-8.2-M88, Sie Metric.			
1.4 DELIVERY, .1 STORAGE AND HANDLING		Deliver and stockpile aggregate Section 31 05 17 - Aggregate minimum 50% of total aggregate beginning operation.	Materials. Stockpile	
	.2	.2 Divert unused granular material from landfill local facility as approved by Departmental Representative.		
PART 2 - PRODUCTS				

2.1 MATERIALS

- . 1 Type 1 Granular Base: Material to the following requirements:
 - Granulations to be within following limits when . 1 tested to ASTM C136-84a and ASTM C117-87. The gradings shall not show marked fluctuations from opposite extremes of the limiting sizes, and giving a smooth curve without sharp breaks when plotted on a semi-log grading chart to ASTM.

ASTM Sieve Designation	% Passing
19.0 mm	100
12.5 mm	70-100
9.5 mm	_
4.75 mm	40-70
2.00 mm	23-50
0.425 mm	7-25
0.180 mm	_
0.075 mm	3-8

- .2 Type 2 Granular Sub-Base Material to the following requirements:
 - Gradation to be within following limits when tested to ASTM C136-82 and ASTM C117-80. The gradings shall not show marked fluctuations from opposite extremes of the limiting sizes, having a smooth curve without sharp breaks when plotted on a semi-log grading chart to ASTM E11-87.

ASTM Sieve Designation	%Passing			
50.8 mm	75-100			
15.9 mm	45-80			
4.76 mm	25-55			
1.20 mm 12-35				
0.300 mm	7-20			
0.075 mm 3-6	(Pit Source) 3-8 (Rock Source)			

Slipway Reconstruction	AGGREGATE BASE COURSES	Section 32 11 23
River of Ponds, NL		Page 3
PN: 722303		April 2019

2.1 MATERIALS (Cont'd)

.2 (Cont'd)

- .2 Other properties as follows:
 - .1 Liquid Limit ASTM D423-66 (1972) Maximum 25.
 - .2 Plasticity Index ASTM D424-59 (1971) Maximum 0.
 - .3 Los Angeles Abrasion ASTM C131-81 Maximum % Loss by Weight: 35.
 - .4 Crushed fragments: 50%. The percent of crushed particles will be determined by examining the fraction retained on the 4.76 mm sieve and dividing the weight of the crushed particles by the total weight retained on the 4.76 mm sieve.
 - .5 CBR: AASHTO T180-74 Method D.

.3 Other properties as follows:

- .1 Liquid Limit: to ASTM D4318 (1972) maximum 25.
- .2 Plasticity Index: to ASTM D4318-59 (1971) maximum 0.
- .3 Los Angeles Abrasion: to ASTM C131-06. Maximum % loss by weight: 35.
- .4 Crushed Fragments: 50%. The percent of crused particles will be determined by examining the fraction retained on the 4.76 mm sieve and dividing the weight of the crushed particles by the total weight retained on the 4.76 mm sieve.
- .5 CBR:AASSHTO T 193-10 (2010) Min 100 when compacted to 100% of AASSHTO T 180-10 Method D.

PART 3 - EXECUTION

3.1 SEQUENCE OF OPERATIONS

.1 Place granular base after common backfill is inspected and approved by Departmental Representative.

.2 Placing

- .1 Construct granular base to depth and grade in areas indicated.
- .2 Ensure no frozen material is placed.
- .3 Place material only on clean unfrozen surface, free from snow and ice.
- .4 Place material to full width in uniform layers not exceeding 150mm compacted thickness. Department Representative may authorize thicker lifts (layers) if specified compaction can be achieved.
- .5 Shape to smooth contour and compact to specified density before succeeding layer is placed.
- .6 Remove and replace that portion of layer in which material becomes segregated during spreading.

Slipway Reconstruction River of Ponds, NL PN: 722303		AGGREGATE BASE COURSES	Section 32 11 23 Page 4 April 2019
3.1 SEQUENCE OF OPERATIONS (Cont'd)	.3	Compaction Equipment .1 Compaction equipment to be required material densities. Compacting	capable of obtaining
		.1 Compact to density not les maximum dry density ASTM D6982 Shape and roll alternately even and uniformly compacted ba .3 Apply water as necessary dobtain specified density4 In areas not accessible to compact to specified density wi approved by Department Representations.	to obtain smooth, se. uring compacting to rolling equipment, th mechanical tampers
3.2 SITE TOLERANCES	.1	Finished base surface to be wit mm of established grade and crouniformly high or low.	-
3.3 PROTECTION	.1	Maintain finished base in condi this Section until succeeding m until acceptance by Departmenta	aterial is applied or

Slipway Reconstructi River of Ponds, NL PN: 722303	Lon	VEHICLE W-BEAM GUIDE RAIL	Section 34 17 39 Page 1 April 2019
PART 1 - GENERAL			
1.1 RELATED	.1	Section 01 33 00 - Submittal Pro	cedures.
SECTIONS	.2	Section 01 74 21 - Construction/ Management and Disposal.	Demolition Waste
1.2 REFERENCES	.1 American Association of State Highway and Transportation Officials (AASHTO) .1 AASHTO M180-12, Standard Specification f Corrugated Sheet Steel Beams for Highway Guardrails.		ecification for
	.2	American Society for Testing and International) .1 ASTM A307-12, Standard Spectarbon Steel Bolts Studs and Thr. PSI Tensile Strength.	ification for
	.3	ASTM A123/A123M-13, Standard Spe Zinc (Hot-Dip Galvanized) Coatin Steel Products.	
	. 4	Canadian Standards Association (.1 CAN/CSA-080 Series-08(R2012 Preservation.	,
1.3 SAMPLES	.1	Submit samples in accordance wit - Submittal Procedures.	h Section 01 33 00
	.2	Inform Departmental Representati weeks prior to beginning Work, o of guide rail and components.	
1.4 WASTE MANAGEMENT AND DISPOSAL	.1	Separate and recycle waste mater with Section 01 74 21 - Construct Waste Management and Disposal.	
	.2	Collect and separate for disposa polystyrene corrugated cardboard material in appropriate on-site in accordance with Waste Managem	l packaging bins for recycling
	.3	Place materials defined as hazar designated containers.	dous or toxic in

Slipway Reconstructi	OR	VEHICLE M-DEAM CHILD DAIL	Soution 24 17 20
River of Ponds, NL PN: 722303		VEHICLE W-BEAM GUIDE RAIL	Section 34 17 39 Page 2 April 2019
1.4 WASTE MANAGEMENT AND DISPOSAL	. 4	Divert unused metal materials from landfill to metal recycling facility as approved by Departmental Representative.	
(Cont'd)	.5	Unused paint or coating material of at an official hazardous mate site as approved by Departmental	rial collections
	.6	Fold up metal banding, flatten and place in designated area for recycling.	
	.7	Do not dispose of unused paint may system, into streams, lakes, onto other location where it will posenvironmental hazard.	o ground or in any
	.8	Do not dispose of preservative t through incineration.	reated wood
	.9	Do not dispose of preservative to other materials destined for rec	
	.10	Dispose of treated wood, end pie and sawdust at a sanitary landfi	
	.11	Dispose of unused preservative m official hazardous material coll not dispose of unused preservati the sewer system, streams, lakes any other location where they wi or environmental hazard.	ections site. Do ve material into , on ground or in
1.5 MEASUREMENT FOR PAYMENT	.1	Guide Rail: Measure supply and e roadside steel W-beam guide rail and necessary hardware in lin. m rail installed and measured from steel W-beam guide rail. Include plant, labour, equipment and mat complete work as specified on ac drawings.	including posts eters of guide outer tips of the cost of all erials required to
PART 2 - PRODUCTS			
2.1 MATERIALS	.1	Steel W-beam guide rail as indic following requirements: .1 Steel rail and terminal sec	tions: to AASHTO

M180-78, class A Type 1 zinc coated.

Slipway Reconstruction River of Ponds, NL	VEHICLE W-BEAM GUIDE RAIL	Section 34 17 39 Page 3
PN: 722303		April 2019

2.1 MATERIALS (Cont'd)

- .1 (Cont'd)
 - .2 Bolts, nuts and washers: to ASTM A307, hot dip galvanized to ASTM A123/A123M (CSA G-164M).
- .2 Organic zinc-rich coating: to CAN/CGSB-1.181.
- .3 Sawn timber posts and offset blocks:
 - .1 Species: Hemlock or Douglas Fir.
 - .2 Type: pressure treated in accordance with CAN/CSA-080 Series.
 - .3 Grade: No 1 Structural Grade.
 - .4 Dimensions: as indicated 200 mm \times 200 mm \times 2440 mm.

PART 3 - EXECUTION

3.1 ERECTION

- .1 Set posts by instrument for alignment, and locations as indicated and as directed by Departmental Representative.
- .2 Excavate post holes to depths as indicated and to diameter of 360 mm plus or minus 20 mm. Compact bottom to provide firm foundation. Set post plumb and square in hole.
- .3 Backfill around posts using excavated material and compact in uniform layers not exceeding 150 mm compacted thickness.
- .4 Cut off tops of posts as indicated, with tops parallel to grade of concrete apron edge.
- .5 Worker protection: workers must wear gloves respirators dust masks long sleeved clothing eye protection protective clothing when handling, drilling, sawing, cutting or sanding preservative treated wood and applying preservative materials.
- .6 Construct anchorages to details as indicated.
 Place and compact backfill for anchors as directed
 by Departmental Representative.
- .7 Erect steel W-beam components to details as indicated. Lap joints in direction of traffic. Tighten nuts to 100 N.m torque. Maximum protrusion of bolt 12 mm beyond nut.

Slipway Reconstruction RUBBLE MOUND BREAKWATER Sect 35 31 23.13
River of Ponds, NL Page 1
PN: 722303 April 2019

PART 1 - GENERAL

1.1 RELATED SECTIONS

- .1 Section 01 33 00 Submittal Procedures.
- .2 Section 01 74 21 Construction/Demolition Waste Management And Disposal.

1.2 REFERENCES

- .1 American Society for Testing and Materials (ASTM)
 .1 ASTM C117-13, Standard Test Method for
 Material Finer than 0.075 mm Sieve in Mineral
 Aggregates by Washing.
 - .2 ASTM C136-06, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates.
- .2 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-8.1-88, Sieves, Testing, Woven Wire.
 - .2 CAN/CGSB-8.2-M88, Sieves, Testing, Woven Wire, Metric.

1.3 SUBMITTALS

.1 Submit to Departmental Representative for approval, 4 weeks before blasting, details of proposed blasting operations showing types and quantities of explosives, loading charges and patterns, type of blasting caps, blasting techniques, blast protection measures, time of blasting and other pertinent details. Submit subsequent changes to Departmental Representative before proceeding.

.2 Samples

- .1 Submit samples in accordance with Section 01 33 00 Submittal Procedures.
- .2 Inform Departmental Representative of proposed source of materials and provide access for sampling at least 2 weeks prior to commencing Work.
- .3 Submit samples representative of quarry, minimum 2 weeks prior to beginning Work.
- .4 Ship samples prepaid to Departmental Representative for approval.
- .3 Submit for approval of review by Departmental Representative proposed method of handling armour stone. Submission to cover phases of handling, from removal from form to final position.

Slipway Reconstruction	RUBBLE MOUND BREAKWATER	Sect 35 31 23.13
River of Ponds, NL		Page 2
PN: 722303		April 2019

1.4 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate and recycle waste materials in accordance with Section 01 74 21 Construction/Demolition Waste Management And Disposal.
- .2 Collect and separate for disposal paper, plastic, polystyrene, and corrugated cardboard packaging material in appropriate on-site bins for recycling in accordance with Waste Management Plan.
- .3 Divert unused geotextiles from landfill to plastic recycling facility as approved by Departmental Representative.
- .4 Divert unused metal materials from landfill to metal recycling facility as approved by Departmental Representative.
- .5 Divert unused concrete materials from landfill to local quarry facility as approved by Departmental Representative.
- .6 Fold up metal banding, flatten and place in designated area for recycling.

1.5 INTERFERENCE TO NAVIGATION

- .1 Be familiar with vessel movements and fishery activities in area affected by construction operations.
 - .2 Plan and execute work, in a manner that will not impede navigation, including movement of vessels at the facility.
 - .3 Plan and execute work, in a manner that will not interfere with fishing operations or access to marine structures by land and water.
 - .4 Departmental Representative will not be responsible for loss of time, equipment, material or any other charges related to interference with moored vessels in the harbour or other Contractor's operations.
 - .5 Keep the Marine Communications and Traffic Services' Centre, Fisheries and Oceans Canada, informed of construction operations, in order that necessary Notices to Mariners may be issued.

1.6 REGULATORY REQUIREMENTS

.1 Comply with municipal, provincial and national codes and regulations relating to project.

Slipway Reconstructi	on	RUBBLE MOUND BREAKWATER	Sect 35 31 23.13
River of Ponds, NL			Page 3
PN: 722303			April 2019
1.7 MEASUREMENT FOR PAYMENT	.1	Armour Stone (3.0 - 5.0 tonne) metres (m³) of material and su this work within the limits sp	applied and placed in
	.2	There will be no payment made stone placed beyond limits ind drawings. The final contract g 200 mm of the specific elevati be based on a as-built survey. outside the lines and grades a drawings will not be measured.	dicated on the grade must be within on. Quantities will Any material placed as shown on the
	.3	There will be no additional paresulting from fishing operati	
	. 4	There will be no additional pa	yment for downtime.
	.5	Mobilization/demobilization of lump sum will not be measured in the above pay items.	
	.6	Construction and maintenance on not be measured for payment.	of haul roads will
PART 2 - PRODUCTS			
2.1 ROCK MATERIAL	.1	Hard, angular rock free from cother defects which may impair	·
	.2	Relative density, 2.65 minimum	1.
	.3	Absorption, 1.5 to 2.0% maximu ASTM C127 test procedure.	um as determined by
	. 4	Durability, less than 35% abratest procedure.	asion Wear, ASTM C535
	.5	Sulphate Soundness Determinati ASTM C88.	on maximum 12% by
2.2 ARMOUR STONE	.1	Hard, dense with relative dens	

- specific gravity) not less than 2.65, durable quarry stone, free from seams, cracks or other structural defects, to meet following size distribution for use intended.
- Material for armour stone to be blasted rock or field stone.

Slipway Reconstructi River of Ponds, NL PN: 722303	.on	RUBBLE MOUND BREAKWATER	Sect 35 31 23.13 Page 4 April 2019
2.2 ARMOUR STONE (Cont'd)	.3	Stone sizes to be in the range in categories specified, well g category.	· ·
	. 4	Greatest dimension of each stor (2) times least dimension.	e not to exceed two
	.5	Supply rock spalls to fill open	joints.
PART 3 - EXECUTION			
3.1 GENERAL	.1	Contractors will not be permitt existing wharf deck. No equipme operate from the structure.	
3.2 PREPARATION	.1	Haul roads: construct and maint	ain haul roads.
3.3 PLACING	.1	Place armour stone to lines, grindicated on the drawings. Contrealize the distance required to stone out into the water, supple equipment to complete as shown	ractor should o place the armour y necessary
	.2	Dumping of armour stone will no Each stone will be lifted and i	
	.3	Side slopes to be 1.5 horizonta unless otherwise indicated on t	
	. 4	Place armour stone to a total lindicated on the drawings.	ayer thickness as
	.5	Choose stones and place them in the whole structure will be bor consolidated to as great an ext rock will allow. Rocks should we don't grade lines as indicated	ded and ent as nature or ary in size so they
	. 6	Do not transport different cate in the same truckload. If rocks different sizes are present in Departmental Representative reshave each rock measured separat prior to installing in structure	of markedly the same load, erves the right to ely and sorted

Slipway Reconstruction River of Ponds, NL		RUBBLE MOUND BREAKWATER	Sect 35 31 23.13 Page 5
PN: 722303			April 2019
3.3 PLACING	.7	Contractor to provide cross s	
(Cont'd)		Departmental Representative a to show that lines and grades	t 10 metre stations

3.4 ROCK MATERIAL WASHED OUT OF WORK

.1 Should during the progress of the Work, any rock material be washed out of the Work, or through neglect or carelessness of the Contractor or their employees or from any other cause, be dumped into the water near the Work or anywhere within the harbour or channel so as to interfere in the opinion of the Departmental Representative with actual depths of water and/or impede navigation, it will be removed by the Contractor when ordered to do so by the Departmental Representative. Any material washed out of the Work or displaced beyond the contract limits will be replaced by the Contractor at no cost to Canada.

as shown on the drawings. Measurement for payment for this work will be included in the cost of the

supply and installing the above item.

3.5 TOLERANCES

- .1 Note: These tolerances are not to be considered pay limits but are specified to ensure contractor keeps within acceptable lines and grades.
- .2 Completed component layers to be within the following tolerances of lines and grades as indicated:
 - .1 Armour stone $\pm 1/-300$ mm.

FISHERIES AND OCEANS CANADIAN ENVIRONMENTAL ASSESSMENT ACT (CEAA) 2012 PROJECT EFFECTS DETERMINATION REPORT

GENERAL INFORMATION

1.	Project Title: Slipway Demolition & Reconstruction, River of Ponds, NL					
2	Proponent: Fisheries and Oceans Canada, Small Craft	Harbours (DFO SCH)				
3.	Other Contacts (Other Proponent, Consultant or Contractor):	4. Role:				
	Public Works and Government Services Canada	OGD Consultant				
5.	Source of Project Information: Paul Curran, Chief En	gineer, DFO – Small Craft Harbours				
6.	Project Review Start Date: September 7, 2018					
7.	PATH No.: NA	8. PWGSC File No:				
9.	TC File No.: NPP #8200-02-1253 / TC NEATS: 48947					

BACKGROUND

10. Background about Proposed Development (including a description of the proposed development):

The scope of work includes the removal and replacement of the existing slipway and installation of a new concrete boat launch at the DFO-SCH facility in River of Ponds, NL (see appendix A).

PROJECT REVIEW

11. DFO's rationale for the project review:
Project is on federal land ⊠ <u>and;</u>
DFO is the proponent
☐ DFO to issue Fisheries Act Authorization or Species at Risk Act Permit
☐ DFO to provide financial assistance to another party to enable the project to proceed
☐ DFO to lease or sell federal land to enable the project to proceed
Other
12. Fisheries Act Sections (if applicable):
n/a

13. Other Authorities

 Transport Canada – Navigation Protection Program (NPP) and Environmental Affairs and Aboriginal Consultation Unit

14. Other Authorities rationale for involvement:

Navigation Protection Act

15. Other Jurisdiction:

Department of Municipal Affairs and Environment, Pollution Prevention Division (NLDMAE PP)

16. Other Expert Departments Providing Advice:

17. Areas of Interest of Expert Departments:

N/A

N/A

18. Other Contacts and Responses: n/a

19. Scope of Project (details of the project subject to review):

Project Description

The proposed project involves removing dilapidated sections of an existing slipway and the installation of a new slipway, complete with rock filled timber cribs, concrete levelling pad, dowelled bars, reinforced concrete deck topping and timber beam runners. The slipway component is approximately 50 m wide by 31 m long. The new footprint will follow the same alignment as the existing. Treated timber will have to be disposed of in an approved landfill.

The majority of the rehabilitation work will take place outside of the water, however, for removal and replacement of the concrete toe it is likely that an excavator will work from the shoreline to manipulate existing cobble and boulder to accommodate the new concrete slabs.

A new concrete boat launch way will be installed east of the existing slipway. The boat launch is approximately 5 m wide by 41 m long. Existing material will be excavated from the shoreline in order to place the new boat launch way. Construction debris will be disposed of appropriately as per regulatory approvals. All rock crib ballast material will be obtained from a local licensed quarry and trucked to the site.

Refer to the site plans in Appendix B.

Operation/Maintenance

The Environmental Management System with an integrated Environmental Management Plan for the Harbour Authority of River of Ponds will cover operational aspects of environmental management at the harbour (fuelling, waste disposal, activities on the property and water). As such, environmental effects resulting from the SCH operations are not considered further in this project effects determination.

Decommissioning

This facility is not presently planned to be decommissioned. At the time of decommissioning, Small Craft Harbours will develop a site-specific re-use or reclamation plan that is appropriate for the applicable environmental legislation and Fisheries and Oceans Canada policies.

Scheduling

Commencement of this project is subject to DFO SCH operational priorities and funding, as well as regulatory approval, but will likely proceed during the 2018-2019 fiscal year.

20. Location of Project:

River of Ponds is a community located off Route 430, 40 km northeast of Daniels Harbour, NL at coordinates 50° 31′ 18″ N, 57° 23′ 28″ W.

21. Environment Description:

The proposed project site is located in River of Ponds, NL. River of Ponds is located in the Northern Peninsula Forest Ecoregion. This ecoregion differs from most other forested parts of the Island by the shortness of the vegetation season, 110-150 days compared to 145-170 days for other areas. The frost-free period is comparable to most other areas and somewhat better than in Central Newfoundland. Precipitation is lower, however, because of low summer temperatures and shorter vegetation season, soil moisture supply is probably adequate at most times.

The soils are comparable to those of Western Newfoundland. Limestone underlies most of the region, with acidic rocks more common on the eastern side of the peninsula.

Balsam Fir is the dominant forest cover except at high elevations (300-400m) on the eastern side of the peninsula where Black Spruce appears to be a natural component of the stands. There is very little fire history in this ecoregion. White Pine, Red Maple, Yellow Birch and Trembling Aspen are conspicuous by their absence. There are approximately 100 species of plants that are excluded from this ecoregion presumably because of the difference of climate (Damman 1965, 1976, and 1983). One of the most conspicuous changes is the replacement of Alnus rugosa by Alnus crispa, Salix pellita and Salix planifolia in swamps. Tall shrubs such as Nemopanthus mucronata, Viburnum cassinoides and Rhododendron canadense are sparse or lacking in the scrub bog-border forests. Silviculturally, they are similar to Western Newfoundland with hardwoods rather than ericaceous shrubs being the most common brush problem on understocked cutovers. Ribes glandulosum, Ribes triste and Cornus stolonifera appear to be a much more conspicuous component of seral vegetation on cutovers. Raspberry is also very abundant in the early years of succession.

Water depth at the proposed project site ranges between 0.9 – 2.0 metres.

Species at Risk (Aquatic and Terrestrial)

A search of the Atlantic Canada Conservation Data Centre (ACCDC) database was conducted. The ACCDC provided a list of rare/unique species (i.e. plants and animals) within a 5 km buffer zone (standard ACCDC procedure) of the site. All species were cross-referenced with Schedule 1 of the Species at Risk Act (SARA) listed as extirpated, endangered, threatened, or special concern. No species were identified within this buffer.

22. Scope of Effects Considered (sections 5(1) and 5(2)):

Table 1: Potential Project / Environment Interactions Matrix

	As	per Se	ection	S	ection	5(1c)		ection 5	(2)	6.10	Due Dii	liaano	
		5(1)		Abo	riginal	Inter	est		ection of	2)		Due Dii	igence	
Project Phase / Physical Work/Activity	Fish (Fisheries Act)	Aquatic Species (SARA)	Birds (MBCA)	Health and Socio economic	Physical and cultural heritage	Land use	*HAPA Significance	Health and Socio economic	Physical and cultural heritage	*HAPA Significance	Water (ground, surface, drainage, etc)	Terrestrial / Aquatic Species	Soil/Marine Sediments	Air Quality
Construction/Installation		- Hree	HIVE	4	14 11			al lo		est with		10		
Slipway Demolition/Reconstruction	Р	Р	-	-	-	-	-	-	-		Р	-	-	Р
Boat Launch Installation	Р	Р	-	-	-	-		-	-	-	Р	_=	-	Р
Operation / Maintenance	-	777	-		·	÷		÷		-	-	ing:	-	-11
Decommissioning / Abandonment	-		31 =		-		•	. III	Q.	-	-	-	-	-

*structure, site or thing that is of historical, archaeological, paleontological or architectural significance.

Legend: P = Potential Effect of Project on Environment; ' - ' = No Interaction

23. Environmental Effects of Project:

In the table above, potential environmental effects were identified. Scoped project activities such as dredging, disposal, wharf construction and infilling have the potential to effect the environment. Each of the potential effects are addressed here:

Fish / Fish Habitat

- Sedimentation and/or increased turbidity as a result of construction activities may negatively
 impact fish and quality of potential fish habitat.
- Potential fish habitat within the project footprint will be eliminated during construction activities.
- Accidental discharge of heavy machinery fuel/fluids will negatively impact fish and potential fish habitat.

Effects for Aquatic Species

- Sedimentation and/or increased turbidity as a result of placement of slipway/boat launch materials may negatively impact aquatic species near project site.
- Accidental discharge of heavy machinery fuel/fluids may negatively impact aquatic species near project site.

Water

- Sedimentation and/or increased turbidity as a result of construction activities may decrease
 marine water quality at immediate project site.
- Accidental discharge of heavy machinery fuel/fluids will result in a decrease of marine water quality.

Air Quality / Noise

Some minor disruptions and annoyance to facility users and residents who live in close
proximity to the project site can be anticipated from project activities and the use of heavy
equipment.

Navigation

Potential for direct effects to navigation.

24. Mitigation Measures for Project (including Habitat Compensation):

Minimize duration of in water work.

Conduct instream work during periods of low flow, or at low tide, to further reduce the risk to fish and their habitat or to allow work in water to be isolated from flows.

Schedule work to avoid wet, windy and rainy periods that may increase erosion and sedimentation. Plan activities near water such that materials such as paint, primers, blasting abrasives, rush solvents, degreasers, grout, or other chemicals do not enter the watercourse.

Develop a response plan that is to be implemented immediately in the event of a sediment release or spill of a deleterious substance and keep an emergency spill kit on site.

Remove all construction materials from site upon project completion and dispose of at appropriately approved facilities.

Ensure that machinery arrives on site in a clean condition and is maintained free of fluid leaks, invasive species and noxious weeds.

Whenever possible, operate machinery on land above the high water mark, on ice, or from a floating barge in a manner that minimizes disturbance to the banks and bed of the waterbody.

Wash refuel and service machinery and store fuel and other materials for the machinery in such a way as to prevent any deleterious substances from entering the water.

Several environmental approvals / permits have been obtained on behalf of SCH. These include:

- 1. Pollution Prevention Division provided approval to dispose of creosote treated timber material to an approved landfill.
- 1. Transport Canada may provide approval under the Navigation Protection Act (NPA).

These approvals are attached in Appendix C and all conditions/mitigation measures must be reviewed and implemented by the contractor. Results of the timber analysis is available in Appendix D.

The project is covered under NL DMAE Terms & Conditions, and the conditions associated with Transport Canada's, Navigation Protection Act authorization. Fisheries and Oceans Canada, Fisheries Protection Program determined that the project would likely not result in Serious Harm to fish or fish habitat and prescribed several mitigation measures to help mitigate potential environmental impacts (Included above).

The proponent should ensure that copies of all regulatory approvals are available on-site during project activities.

Workers in contact with hazardous materials (e.g. wastes) must be provided with and use appropriate personal protective equipment;

Proper safety procedures must be followed during the duration of the project as per applicable municipal, provincial, and federal regulations;

Employees will be trained in health and safety protocols (e.g. safe work practices, emergency response).

Environmental effects of the project on navigation are taken into consideration as part of the Project Effects Determination (PED) only when the effects are indirect, i.e. resulting from a change in the environment affecting navigation. Direct effects on navigation are not considered in the PED, but any measures necessary to mitigate direct effects will be included as terms and conditions associated with the work approved or permitted pursuant to the Navigation Protection Act.

25. Significance of Adverse Environmental Effects of project:

Significant adverse environmental effects are unlikely, taking into account mitigation measures.

26, Other Considerations (Public Consultation, Aboriginal Consultation, Follow-up)

Public Consultation

The proposed project will provide more adequate and secure access for vessels utilizing this facility. No negative public concern was received as a result of this project. SCH consulted the local harbor users and Harbour Authority on all aspects of the project to ensure all requirements at the site were considered during design.

Aboriginal Consultation

Aboriginal fishers are not known to utilize the River of Ponds SCH facility, nor are there any known aboriginal groups in the surrounding area. As such, aboriginal consultation was not deemed necessary as part of this determination.

Government Consultation

Federal and provincial authorities likely to have an interest in the project were consulted by Public Works & Government Services Canada, Environmental Services, during the course of this assessment. A project description was distributed to the following authorities:

- Transport Canada Navigation Protection Program and Environmental Affairs and Aboriginal Consultation Unit
- NL Department of Municipal Affairs and Environment Pollution Prevention Division

Accuracy and Compliance Monitoring

A follow-up program (as defined in S. 2(1) and as applicable to non-designated projects on federal lands) is a program for determining the effectiveness of any mitigation measures. Site monitoring (accuracy and compliance monitoring) may be conducted to verify whether required mitigation measures were implemented. The proponent must provide site access to Responsible Authority officials and/or its agents upon request.

27. Other Monitoring and Compliance Requirements (e.g. Fisheries Act or Species at Risk Act requirements)

n/a

CONCLUSION

28. Conclusion on Significance of Adverse Environmental Effects:

The Federal Authorities have evaluated the project in accordance with Section 67 of Canadian Environmental Assessment Act (CEAA), 2012. On the basis of this evaluation, the departments have determined that the project is not likely to cause significant adverse environmental effects with mitigation and therefore can proceed as outlined.

29. Prepared by:

National Proposer

30. Date: November 13, 2018

31. Name:

Natasha Warren

32. Title:

Environmental Specialist, PWGSC-ES

DECISION

33.	Decision I ake	n
	project is no	ercise its power, duty or function, i.e. may issue the authorization - where the t likely to cause significant adverse environmental effects. Confirm below the er, duty or function that may be exercised.
	DFO to	issue Fisheries Act Authorization or Species at Risk Act Permit proceed with project (as proponent) provide financial assistance for project to proceed provide federal land for project to proceed
	to cause sig ☐ DFO to ask	cided not to exercise its power, duty or function because the project is likely nificant adverse environmental effects. the Governor in Council to determine if the significant adverse environmental ustified in the circumstances
34.	Approved by:	Paul Cur 35. Date: Dec 18/18
36.	Name:	Paul Curran
37.	Title:	Regional Engineer, DFO-SCH, NL
38.	References:	n/a

39. TRANSPORT CANADA RECOMMENDATION

Project Title:	DFO-SCH River of Ponds, NL - Slipway I	Demolition and Reconstruction					
TC File No.:	48947						
NPP File No.:	NPP #8200-02-1253						
Environmental Review Decision:	Taking into account the implementation of any mitigation measures that Transport Canada considers appropriate, the project is not likely to cause significant adverse environmental effects and, as such, Transport Canada may exercise any power or perform any duty or function that would permit the project to be carried out in whole or in part.						
Prepared by:	Melissa Ginn Environmental Officer Environmental Affairs and Aboriginal Consultation Unit						
Signature:	Date: Dec. 19, 2018						
Mailing Address:	10 Barter's Hill, St. John's, NL						
Tel:	709-772-3088 / 709-351-3200						
Fax:	709-772-3072						
Email:	melissa.ginn@tc.gc.ca						
Recommended by:	J. Jason Flanagan Senior Environmental Assessment Office Environmental Affairs and Aboriginal Cor						
Signature:	J-18-	Date: December 19, 2018					
Approved by:	Kevin LeBlanc Regional Manager Environmental Affairs and Aboriginal Cor	nsultation Unit					
Signature:	Kevin LeBlanc	Date: December 20, 2019					

Appendix A FIGURES

-Topo Map - Aerial Photographs




Figure 1: Topographic Map indicating project site.




Figure 2: Location of proposed project (DFO Aerial Photograph 2015).

Appendix B SITE PLANS




Figure 3: Existing structures and demolition site plan.




Figure 4: Site Plan of Proposed Construction Project.

Appendix C REGULATORY APPROVALS



Wed 07/11/2018 2:49 PM

Hann, Joan <joanhann@gov.nl.ca>

FW: Service NL Referral for Treated Timber Disposal - DFO SCH Western Area - River of Ponds, NL

To Satasha N. Warren

CE Goosney, Dubbie; Mark McNal

Message Reann Timber disposal in River of Ponds.pdf

Hello Natasha

Based upon the results above the TWW can be disposal of at an approved WDS. Please ensure all disposal documents are forwarded to the department. Debtie (EPO with SNL) can provide the location of WDS Thanks

Joan Hann Environmental Scientist Finizionmental Scientist
Pollution Prevention Division
Department of Municipal Affairs and Environment
4th Floor, Confederation Building, West Block
P.O. flox 8700
St. John's, NL, Canada A18 416
Email: Joanhannelgov.nl.ca
Phone: 709-729-1771

Appendix D TIMBER RESULTS



Your P.O. #: 700419969

Site Location: River of Ponds, NL

Your C.O.C. #: n/a

Attention: Mark McNeil

Public Works & Government Services Canada PO Box 4600 10 Barter's Hill St. John's , NL CANADA A1C 5T2

> Report Date: 2018/11/01 Report #: R5467138

Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B856477 Received: 2018/10/29, 09:12

Sample Matrix: Solid # Samples Received: 3

		Date	Date		210		
Analyses	Quantity	Extracted	Analyzed	Laboratory Method	Reference		
Semivolatile Organic Compounds (TCLP) (1)	3	2018/10/31	2018/11/01	CAM SOP-00301	EPA 8270D m		
TCLP - % Solids (1)	3	2018/10/31	2018/11/01	CAM SOP-00401	EPA 1311 Update ! m		
TCLP - Extraction Fluid (1)	3	N/A	2018/11/01	CAM SOP-00401	EPA 1311 Update (m		
TCLP - Initial and final pH (1)	3	N/A	2018/11/01	CAM SOP-00401	EPA 1311 Update I m		

Remarks:

Maxxam Analytics' laboratories are accredited to ISO/IEC 17025:2005 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by Maxxam are based upon recognized Provincial, Federal or US method compendia such as CCME, MDDELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in Maxxam's profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and Maxxam in writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported; unless indicated otherwise, associated sample data are not blank corrected. Where applicable, unless otherwise noted, Measurement Uncertainty has not been accounted for when stating conformity to the referenced standard.

Maxxam Analytics' liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. Maxxam has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by Maxxam, unless otherwise agreed in writing. Maxxam is not responsible for the accuracy or any data impacts, that result from the information provided by the customer or their agent.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested. When sampling is not conducted by Maxxam, results relate to the supplied samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

- * RPOs calculated using raw data. The rounding of final results may result in the apparent difference.
- (1) This test was performed by Maxxam Analytics Mississauga



Your P.O. #: 700419969

Site Location: River of Ponds, NL

Your C.O.C. #: n/a

Attention: Mark McNell

Public Works & Government Services Canada PO Box 4600 10 Barter's Hill St. John's , NL CANADA A1C 5T2

> Report Date: 2018/11/01 Report #: R5467138 Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B8S6477 Received: 2018/10/29, 09:12

Encryption Key



Hannad

01 Nov 2018 19:00:16

Please direct all questions regarding this Certificate of Analysis to your Project Manager, Maryann Comeau, Project Manager Email: MComeau@maxxam.ca
Phone# (902) 420-0203

This report has been generated and distributed using a secure automated process,

Maxim has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025 2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



Maxxam Job #: B856477 Report Date: 2018/11/01 Public Works & Government Services Canada Site Location: River of Ponds, NL

Your P.O. #: 700419969 Sampler Initials: SSC

RESULTS OF ANALYSES OF SOLID

Maxxam ID		IDL530	IDL531	IDL532		Tool
Sampling Date		2018/10/22 14:00	2018/10/22 14:00	2018/10/22 14:00		H
COC Number	100	n/a	n/a	n/a		Magest 1
	UNITS	RIVER OF PONDS #1	RIVER OF PONDS #2	RIVER OF PONDS #3	ROL	QC Batch
Inorganics					211	194
Final pH	рН	4.95	5.01	5.05		5810877
Initial pH	pH	8.33	8.07	7.89		5810877
		······				5810875
TCLP - % Solids	%	100	100	100	0.2	2910912



Maxxam Job #; B856477 Report Date: 2018/11/01 Public Works & Government Services Canada

Site Location: River of Ponds, NL

Your P.O. #; 700419969 Sampler Initials; SSC

SEMI-VOLATILE ORGANICS BY GC-MS (SOLID)

Maxxam ID	_	IDLS30	ID1531	IDL532		
Sampling Date		2018/10/22 14:00 n/a RIVER OF PONDS #1	2018/10/22 14:00	2018/10/22 14:00	ROL	QC Batch
COC Number			n/a	n/a		
	UNITS		RIVER OF PONDS #2	RIVER OF PONDS		
Semivolatile Organics	F2 19	Series - Land			mgalu	
Leachable Benzo(a)pyrene	ug/L	o ND	ND	ND	0.80	5813867
Leachable m/p-Cresol	ug/L	ND	ND	ND	20	5813867
Leachable o-Cresol	ug/L	ND	ND	ND	20	5813867
Leachable Cresol Total	ug/L	ND	ND	ND	20	5813867
Leachable Pentachlorophenol	ug/L	ND	ND ND	ND	20	5813867
Surrogate Recovery (%)						
Leachable 2,4,6-Tribromophenol	%	83	85	79		5813867
Leachable 2-Fluoroblphenyl	%	72	62	55		5813867
Leachable 2-Fluorophenol	%	49	28	28		5813867
Leachable D14-Terphenyl (FS)	%	98	101	93		5813867
Leachable D5-Nitrobenzene	%	82	51	46		5813867
Leachable D5-Phenol	%	23	16	15	Î	5813867

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

ND = Not detected



Maxxam Job #: B8S6477 Report Date: 2018/11/01 Public Works & Government Services Canada Site Location: River of Ponds, NL Your P.O. #: 700419969 Sampler Initials: SSC

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	4.6°C

Sample IDL530 (RIVER OF PONDS #1): ABN Leachate ANALYSIS: Due to the nature of the sample, a smaller amount was used for the analysis. Detection limits were adjusted accordingly.

Sample IDL531 [RIVER OF PONDS #2]: ABN Leachate ANALYSIS: Due to the nature of the sample, a smaller amount was used for the analysis. Detection limits were adjusted accordingly.

Sample IDL532 [RIVER OF PONDS #3]: ABN Leachate ANALYSIS: Due to the nature of the sample, a smaller amount was used for the analysis. Detection limits were adjusted accordingly.

Results relate only to the items tested.



Maxxam Job #: 8856477 Report Date: 2018/11/01 Public Works & Government Services Canada

Site Location: River of Ponds, NL

Your P.O. #: 700419969 Sampler Initials: SSC

QUALITY ASSURANCE REPORT

QA/QC Batch	Init	QC Type	Parameter	Date Analyzed	Value	Recovery	UNITS	QC Umits
5813867	WZ	Matrix Spike	Leachable 2,4,6-Tribromophenol	2018/11/01	72,20	85	%	10-130
SOLUBOY WE WINDOWS	Tratrin opine	Leachable 2-Fluorobiphenyl	2018/11/01		70	%	30 - 130	
	Leachable 2-Fluorophenol	2018/11/01		53	%	10 - 130		
	Leachable 014-Terphenyl (FS)	2018/11/01		100	%	30 - 130		
			Leachable DS-Nitrobenzene	2018/11/01		91	%	30 - 130
	Leachable D5-Phenol	2018/11/01		30	%	10-130		
	Leachable Benzo(a)pyrene	2018/11/01		97	%	30 - 130		
	Leachable m/p-Cresol	2018/11/01		64	%	10-130		
	Leachable o-Cresol	2018/11/01		80	%	10 - 130		
		Leachable Cresol Total	2018/11/01		72	%	10 - 130	
			Leachable Pentachlorophenol	2018/11/01		84	%	30 - 130
5813867	wz	Spiked Blank	Leachable 2,4,6-Tribromophenol	2018/11/01		81	%	10-130
201200) AAS 2bivEd plank	Spine a ciain	Leachable 2-Fluorobiphenyl	2018/11/01		65	%	30 - 130	
	Leachable 2-Fluorophenol	2018/11/01		50	76	10 - 130		
			Leachable D14-Terphenyl (FS)	2018/11/01		96	%	30 - 130
	Leachable D5-Nitrobenzene	2018/11/01		83	%	30 - 130		
		Leachable D5 Phenol	2018/11/01		29	%	10-130	
			Leachable Benzo(a)pyrene	2018/11/01		93	%	30 - 130
	Leachable m/p-Cresol	2018/11/01		61	%	10 - 130		
	Leachable o-Cresol	2018/11/01		76	%	10 - 130		
	Leachable Cresol Total	2018/11/01		68	%	10 - 130		
	Leachable Pentachlorophenol	2018/11/01		79	%	30 - 130		
5813867	5813867 WZ Method Blank	Method Blank	Leachable 2,4,6-Tribromopheno)	2018/11/01		77	%	10 - 130
2012001		Leachable 2-Fluorobiphenyl	2018/11/01		69	%	30 - 130	
		Leachable 2-Fluorophenol	2018/11/01		44	%	10 - 130	
		Leachable D14-Terphenyl (FS)	2018/11/01		96	%	30 - 130	
		Leachable D5-Nitrobenzene	2018/11/01		82	%	30 - 130	
	Leachable D5-Phenol	2018/11/01		27	%	10 - 130		
	Leachable Benzo(a)pyrene	2018/11/01	ND,		ug/L			
		centinale principles ene	2010/11/01	ROL=0.10		- 100		
		Leachable m/p-Cresol	2018/11/01	ND, ROL=2 S		ug/L		
	Leachable o-Cresol	2018/11/01	ND, RDL=2.5		ug/L			
	Leachable Cresol Total	2018/11/01	ND, RDL=2.5		ug/L			
	Leachable Pentachlorophenol	2018/11/01	ND, RDL=2.5		ug/L			
5813867 WZ RPD	RPD	Leachable Benzo(a)pyrene	2018/11/01	NC		%	40	
	Leachable m/p-Cresol	2018/11/01	NC		%	40		
	Leachable o-Cresol	2018/11/01	NC		%	40		
	Leachable Cresol Total	2018/11/01	NC		%	40		
		Leachable Pentachlorophenol	2018/11/01	NC		-%	40	

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

Surrogate: A pure or isotopically labeled compound whose behavior mirrors the analytes of interest. Used to evaluate extraction efficiency,

NC (Ouplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (absolute difference <= 2x RDL).



Maxxam Job #: B8\$6477 Report Date: 2018/11/01 Public Works & Government Services Canada Site Location: River of Ponds, NL Your P.O. #: 700419969

Sampler Initials: SSC

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).



Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

Navigation Protection Program 95 Foundry Street, 6th Floor Moncton N.B. E1C 8K6 Your file

Our file 8200-02-1253

December 21, 2018

Fisheries and Oceans Canada - SCH 10 Barter's Hill P.O. Box 5667 St. John's, NL A1C 5X1

Attention: Mr. Paul Curran

RE: Notice to the Minister under the Navigation Protection Act for review existing slipway removal and re-construction at River of Ponds in the Province of Newfoundland and Labrador

Our assessment of your work has determined that it is not likely to substantially interfere with navigation.

Therefore your work is permitted under section 9(1) of the *Navigation Protection Act* (NPA) and you may proceed per the attached plan(s) in accordance with the following terms and conditions:

- Construction material and debris are not allowed to become waterborne.
- A notice to shipping is to be issued prior to commencement and upon completion of work. To issue a notice to shipping the proponent is to contact Canadian Coast Guard Traffic Services at 709 695 2168 or via email at: notshippax@dfo-mpo.gc.ca.
- 3. The project is to be constructed in accordance with the approved plans.
- 4. 0.4 meter yellow cautionary floats are to be placed and maintained to mark the outer seaward leading limits of the work during slipway removal and re-construction. When construction is completed these are to be removed.
- 5. During construction and slipway removal any floating debris must be contained in the immediate area and removed from the water in a timely manner.
- 6. If a containment device is placed in the water it must be market at 15-meter intervals by 0.4 meter yellow cautionary floats
- All cables, equipment or temporary hazards resulting from the construction activities
 are to be clearly marked so they are visible to vessels operating in the area.
- 8. Barges and equipment used in the construction must be visible at all times and be marked in accordance with the Collision Regulations of the Canada Shipping Act.



Please note that permission relates only to the effect of your work on navigation under the NPA. It is the owner's responsibility to comply with any other applicable laws and regulations.

Should you have any questions, please do not hesitate to contact our office in Moncton by phone at (506) 851-3113, by fax at (506) 851-7542 or by e-mail at NPPATL-PPNATL@tc.gc.ca.

Respectfully,

William Bennett

Officer

Navigation Protection Program

Programs Group Transport Canada Atlantic Region

CC: Natasha Warren PWGSC DFO- CHS