




1. It is the Contractor's responsibility to refer to all information in the Specification Document.
2. It is the Contractor's responsibility to read this drawing in conjunction with all other drawings in this package. Report any discrepancies between drawings to prior to commencing with Construction.
3. Contractor will be held responsible for any damage done to existing partitions, ceiling, finishes and all other components to remain and to adjacent spaces.
4. Refer to Mechanical and Electrical drawings for extent of demolition.
5. Contractor to remove and turn over to Departmental Representative all items not being used for new construction, unless otherwise noted.
6. Extend existing suspended T-bar grid ceiling as required where slab to slab partitions were removed. Supply and install new acoustical tiles as required. Style and colour to match existing. Secure new existing T-bar ceiling grid as required.
7. Contractor to remove and re-install existing suspended T-bar ceiling grid and acoustical tiles as required for mechanical demolition to Mechanical drawings. Contractor to avoid cutting main T-bar suspension "T" whenever possible.



project	projet
---------	--------

300 Laurier West, Ottawa, ON

drawing	dessin
---------	--------

Reflected Ceiling

Reflected Ceiling  
Demolition Plan  
17th Floor

Scale: As Noted

Designed By	RB & MB	Conçu par
Date	2018-01-26	(yyyy/mm/dd)

Drawn By	MB	Dessiné par
Date	2018-03-09	(yyyy/mm/dd)

Reviewed By *Bryan Allen* Examiné par

Date	2018-01-26	(yyyy/mm/dd)
Approved By	BW	Approuvé par

Date	2018-01-26	(yyyy/mm/dd)
Tender	Soumission	

Brent Cheff	
Project Manager	Administrateur de projets
Project no.	No. du projet

R.088901.013 (17096)

Drawing no.	No. du dessin
ID11	

1511
------