



1 Wall Finish Plan - 20th Floor
Scale: 1:100

Wall Finish Legend:

- P1 Paint - General
Colour: White
Finish: Gloss Level 3
- P2 Paint - Accent
Colour: Chartruese Yellow
Finish: Gloss Level 3
- P3 Paint - Accent
Colour: Teal Blue
Finish: Gloss Level 3
- P4 Paint - Accent
Colour: Medium Grey
Finish: Gloss Level 5
- F1 Felt Panel
Colour: Light Grey
Thickness: 27mm
- F2 Felt Panel
Colour: Teal Green
Thickness: 27mm
- L4 Demountable Wall Finish (White)
Colour: White
- T1 Ceramic Tile Backsplash (White)
Pattern/Colour: White Ceramic Mosaic
Grout: Departmental Representative to pick from standard colour range.
Width of grout line: 3mm
- G1 Back-painted Glass Board (White)
Colour: White
Notes:
- Back-painted glass from 914mm A.F.F. to 2260mm A.F.F. Refer to Elevation 6 on ID33.
- CG Supply and install new surface mounted stainless steel corner guard where shown.
Material: 16 gauge stainless steel no. 304
Finish: #4 Satin
Dimension: 51mm x 51mm x 1220mm H
Mounting Height: Install above baseboard
Notes:
- Install per Manufacturer's instructions.
- Adhere to partition and install straight.
- Ensure all edges are secured to partition. Ensure no edges protrude to prevent harm to someone or something. If top edges cannot be adhered to partition, provide clear caulking and ensure smooth edges.

Wall Finish Drawing Notes:

- 1 Felt panels suspended from ceiling. See elevations on ID33.
- 2 Existing base building doors and frames to be painted P4.
- 3 Elevator doors and frames on all exposed surfaces to be painted P3, lobby side only.
- 4 Metal Edge Trim
Contractor to finish edge of ceramic tiles with metal trim as indicated.
Finish: Brushed stainless steel
Note:
Thickness of trim to suit application.

Wall Finish General Notes:

1. It is the Contractor's responsibility to refer to all information in the Specification Document.
2. It is the Contractor's responsibility to read this drawing in conjunction with all other drawings in this package. Report any discrepancies between drawings to prior to commencing with Construction.
3. Contractor will be held responsible for any damage done to existing partitions, ceiling, finishes and all other components to retrain and to adjacent spaces.
4. Contractor to provide samples of all finishes for Departmental Representative's approval prior to ordering any materials.
5. Patch, sand, repair and make good to level 4 ready to receive new partition finish all existing gypsum board and plaster surfaces throughout the space prior to painting. Contractor to ensure finished partition is smooth, straight and true.
6. All wall finishes to be supplied and installed by Contractor unless otherwise noted.
7. Except where noted otherwise, all existing partitions, core walls, columns and new partitions to be painted P1.
8. L4 typical wall finish for demountable partitions unless otherwise noted.
9. Remove door hardware and signage prior to painting of existing doors and frames. Reinstall once final paint coat has thoroughly dried.
10. All closet interiors to be painted P1, unless otherwise noted.
11. All doors to be primed and painted P4 unless otherwise noted. Refer to Door Hardware Schedule on ID34 for further details.
12. All perimeter convactor units to be painted to match wall finish P1, refer to Specification Documents.
13. Refer to Elevations on drawing ID35 for wall tile pattern.
14. Unless otherwise noted, all movable partition glazing to receive window film on room interior side. Refer to Elevation 4 on ID33 for details.

Public Works and Government Services Canada / Travaux publics et services gouvernementaux Canada

Canada

LWG
ARCHITECTURAL INTERIORS
211-2141 Thurston Drive
Ottawa, ON K1G 0G3
F 613-739-3699
F 613-739-3965
info@LWG-ai.com LWG-ai.com

This drawing is the property of the designer. Copyright is reserved. No reproduction may be made without prior consent of the designers and each copies must bear their names.
This drawing shall not be used for construction purposes until signed by the designer.
The contractor is to verify dimensions and data noted herein with the conditions on the site and report any discrepancy to the designer. Do not scale this drawing.

Key Plan

Project North

ARIDO
David Gibeau
Member of the Board of Directors
Architectural Interiors Inc.

I, the undersigned, have reviewed and shall be responsible for this design and content of this plan. The contractor and the firm is required to file appropriate insurance coverage.

David Gibeau
25033
3005

REGISTRATION INFORMATION
No. License: 11474
Firm Name: ARIDO
LWG Architectural Interiors Inc.
42667
2018

Contractor to verify all dimensions & conditions on site and immediately notify the engineer of all discrepancies.

03	Issued for Tender	2019-01-15
02	Issued for 99% Client Review	2018-03-09
01	Issued for 86% Client Review	2018-02-16

revisions	description	date
A	A detail no. no. du detail	
B	B location drawing no. sur dessin no.	
C	C drawing no. dessin no.	

project LEL Generic Swing Space
300 Laurier West, Ottawa, N

drawing ID30

Scale: As Noted

Designed By	RB & MB	Compu par
Date	2018-01-26	(yyyy/mm/dd)
Drawn By	MB	Dessiné par
Date	2018-03-09	(yyyy/mm/dd)
Reviewed By	[Signature]	Examiné par
Date	2018-03-09	(yyyy/mm/dd)
Approved By	BW	Approuvé par
Date	2018-01-26	(yyyy/mm/dd)
Tender		Soumission
Project Manager	Brent Cheff	Administrateur de projets
Project no.	R.088901.013 (17096)	No. du projet
Drawing no.	ID30	No. du dessin