

3.02 TEMPORARY IRRIGATION

- .1 The Contractor shall install the temporary irrigation system immediately upon construction completion.
- .2 The Contractor shall provide water to all plants during construction, upon construction completion and during the Maintenance Period.
- .3 Watering provided shall be conducted using a temporary irrigation system. The watering system shall deliver water to all seeded and planted areas.
 - .1 Contractor to obtain a Temporary Diversion Permit to draw water from the river. Any other watering methods may be used only once approved by the Departmental Representative. Contractor is responsible for water source. These include: water truck, ATV with water tank, or other methods as approved.
 - .2 The irrigation system may remain in place onsite throughout the maintenance period; however, shall be winterized by October 15 and re-initiated for spring by May 15.
 - .3 Watering required prior to installation of the temporary irrigation system shall be supplied by the Contractor.
 - .1 Water shall be free of impurities.
 - .2 Method of watering shall be discussed and approved by the Departmental Representative prior to initiating watering.