

**LPH SOIL REMEDIATION
FORMER LANDFILL
AND ASPHALT PLANT
OTTER CREEK
HAPPY VALLEY-GOOSE BAY
NEWFOUNDLAND AND LABRADOR
PROJECT NO. R.082578.001**

1 GENERAL

1.01 REFERENCES

- .1 Canadian Construction Documents Committee (CCDC)
 - .1 CCDC 2-94, Stipulated Price Contract.

1.02 PROJECT CLEANLINESS

- .1 Maintain Work in tidy condition, free from accumulation of waste products and debris, other than that caused by Owner or other contractors.
- .2 Remove waste materials from site at daily regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials on site, unless approved by Departmental Representative.
- .3 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .4 Provide on-site containers for collection of waste materials and debris.
- .5 Provide and use marked separate bins for recycling. Refer to Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .6 Dispose of waste materials and debris off site.
- .7 Store volatile waste in covered metal containers, and remove from premises at end of each working day.

1.03 FINAL CLEANING

- .1 When Work is Substantially Performed remove surplus products, tools, construction machinery and equipment not required for performance of remaining Work.
- .2 Remove waste products and debris other than that caused by others, and leave Work clean and suitable for occupancy.
- .3 Prior to final review remove surplus products, tools, construction machinery and equipment.
- .4 Remove waste products and debris other than that caused by Owner or other contractors.
- .5 Remove waste materials from site at regularly scheduled times or dispose Of as directed by Departmental Representative. Do not burn waste materials on site, unless approved by Departmental Representative.
- .6 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.

LPH SOIL REMEDIATION
FORMER LANDFILL
AND ASPHALT PLANT
OTTER CREEK
HAPPY VALLEY-GOOSE BAY
NEWFOUNDLAND AND LABRADOR
PROJECT NO. R.082578.001

1.04 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

2 PRODUCTS

2.01 NOT USED

- .1 Not Used.

3 EXECUTION

3.01 NOT USED

- .1 Not Used.

END OF SECTION