



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada - Pacific
Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet Babine Fence Site New Staff Bldg.	
Solicitation No. - N° de l'invitation F1700-195680/A	Amendment No. - N° modif. 001
Client Reference No. - N° de référence du client F1700-195680	Date 2019-05-23
GETS Reference No. - N° de référence de SEAG PW-\$PWY-028-8595	
File No. - N° de dossier PWY-9-42008 (028)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2019-06-11	Time Zone Fuseau horaire Pacific Daylight Saving Time PDT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Lam (PWY), Tian	Buyer Id - Id de l'acheteur pwy028
Telephone No. - N° de téléphone (604) 363-7968 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: DFO - Babine Fence Site - Bulkley Nechako, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation
F1700-195680/A

Amd. No. - N° de la modif.
001

Buyer ID - Id de l'acheteur
pwy028

Client Ref. No. - N° de réf. du client

File No. - N° du dossier CCC No./N°

CCC - FMS No./N° VME

Les documents français seront disponibles sur demande.

The Solicitation Amendment 001 is raised to issue Addendum 001.

Please see Addendum 001 herein.

Les autres conditions ne changent pas.

THE FOLLOWING ADDENDUM SUPERCEDES INFORMATION CONTAINED IN DRAWINGS AND SPECIFICATIONS ISSUED FOR THE PROJECT TO THE EXTENT REFERENCED. THE FOLLOWING CHANGES IN THE TENDER DOCUMENTS ARE EFFECTIVE IMMEDIATELY. THIS ADDENDUM WILL FORM PART OF THE CONTRACT DOCUMENTS.

Question(s) and Answer(s) from Bidder(s)

Question 1 - Could you please tell me how is the access to site? I noticed it is on a forestry road, can I send there a large delivery truck with all materials?

Answer 1 - The access to site is well maintained during the summer and fall months to accommodate logging trucks that frequently use the road. Any truck the same size or smaller than a typical logging truck should be able to make the trip with no issues.

Question 2 - What would be the closest accommodation for the crew? Can we set campers on site?

Answer 2 – There are a few local accommodation options in the area, Fort Babine is likely the closest. Campers cannot stay on the site, but there are local campsites in the area that could accommodate a site crew.

Question 3 - What is involved in hooking up the services, how deep is existing water and sewer and how are we connecting power?

Answer 3 – The existing water and septic services are capped just below ground level and will need to be uncapped and connected to the proposed plumbing below the building. This will need to include a way to drain the lines to prevent freezing in the winter as per code. The power will be connected via the existing utility pole just East of the proposed building location shown on drawing A101; power was terminated at the pole during a recent site electrical upgrade to be reconnected at completion of the new building.