

PART 1 - GENERAL

- | | | |
|---|----|---|
| <u>1.1 GENERAL</u> | .1 | Conduct cleaning and disposal operations to comply with local ordinances and anti-pollution laws. |
| | .2 | Store volatile waste in covered metal containers, and remove from premises at end of each working day. |
| | .3 | Prevent accumulation of wastes which create hazardous conditions. |
| | .4 | Provide adequate ventilation during use of volatile or noxious substances. |
| <u>1.2 MATERIALS</u> | .1 | Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer. |
| <u>1.3 CLEANING DURING CONSTRUCTION</u> | .1 | Maintain project grounds and public properties in a tidy condition, free from accumulations of waste material and debris. Clean areas on a daily basis. |
| | .2 | Provide on-site garbage containers for collection of waste materials and debris. |
| | .3 | Remove waste materials and debris from site on a daily basis. |
| <u>1.4 FINAL CLEANING</u> | .1 | In preparation for acceptance of the Work perform final cleaning. |
| | .2 | Inspect finishes, fitments and equipment. |

	CLEANING	Section 01 74 11
PSPC		
R.098430.002		Page 2
Northside Landfill B Erosion Control		
Argentia, NL		2019-05-05

Ensure specified workmanship and operation.

- .3 Broom clean exterior paved and concrete surfaces; rake clean other surfaces of grounds.