



**RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:**

PWGSC/TPSGC Acquisitions Bid
Receiving/Réception des Soumissions
126 Prince William Street/
126, rue Prince William
Suite 14B
Saint John
New Brunswick
E2L 2B6
Bid Fax: (506) 636-4376

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works Government Services Canada-Bid
Receiving / Réception des soumissions
126 Prince William Street/
126, rue Prince William
Suite 14B
Saint John
New Bruns
E2L 2B6

Title - Sujet Campsite Construction-Wolfe Lake NB	
Solicitation No. - N° de l'invitation EC015-200436/A	Amendment No. - N° modif. 001
Client Reference No. - N° de référence du client EC015-200436	Date 2019-06-28
GETS Reference No. - N° de référence de SEAG PW-\$PWB-013-4449	
File No. - N° de dossier PWB-9-42012 (013)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2019-07-04	Time Zone Fuseau horaire Atlantic Daylight Saving Time ADT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Johnston, Edward PWB	Buyer Id - Id de l'acheteur pwb013
Telephone No. - N° de téléphone (506) 343-6382 ()	FAX No. - N° de FAX (506) 636-4376
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

This Solicitation Amendment No. one (1) is raised to include the following Addendum No. one (1).

The following Addendum to the tender is effective immediately. This addendum shall form part of the contract documents.

All other terms and conditions remain the same.

EXTENSION OF TIME

Notice is hereby given that the time for the reception of tenders previously due July 03, 2019 is hereby extended to 14:00 hours, July 04, 2019.

QUESTIONS AND ANSWERS

Q1. The two way entrance into to the campground, shows that trees on the west side will need to be cut down. While at the site visit it was discussed that the road alignment will have to be changed in order prevent cutting those trees down. Please confirm if this is still the plan for construction?

A1. No change to road alignment. Price as per current layout.

SPECIFICATION

1. SECTION 01 10 10

Page 1, item 1.1.1.2, DELETE:

11 full service RV campsites, Five (5) "Oasis" serviced sites, and five (5) unserviced tent campsites.

and REPLACE WITH:

Twelve (12) RV Campsites with electrical service, five (5) "Oasis" sites with electrical service, and five (5) unserviced tent campsites.

DRAWINGS

1. C02

SITE CONDITIONS AND REMOVAL NOTES, Note 1, DELETE and REPLACE WITH:

1. Oasis Sites have been cleared by others. Remove fallen trees, smaller trees (as needed), shrubs, and stumps. Flag large trees that need to be cut, if site layout cannot be modified to avoid cutting large trees obtain approval of departmental representative and clear trees.

2. C02

SITE CONDITIONS AND REMOVAL NOTES, ADD:

3. Route electrical conduits and cables to avoid cutting large trees.

4. Existing shed near the existing well to remain. The new water line from the well will connect to the equipment in the shed.

3. E01

Note 3, ADD:

Route conduits and locate pullboxes as necessary to minimize tree cutting. (On the attached sketch, ESK-001, the red lines illustrate the preferred routing of major conduits to avoid tree cutting).

4. E01

Minimum Conductor Table, ADD:

MINIMUM CONDUCTOR SIZING TABLE FOR 120V, 20A, BRANCH CIRCUITS			
Branch Circuit Length of Run	Phase Wire Size	Neutral Wire Size	Bond Wire Size
77.9m - 126.3m	#4AWG	#4AWG	#8AWG
126.4m – 159m	#3AWG	#3AWG	#6AWG

5. E01

Note 6, ADD:

Provide sufficient cable to connect to the underside of the Oasis frame near the center of the unit. The cable shall be buried and tied to the frame from the ground to the junction box near the center of the unit.

6. E02

Detail 4, DELETE:

Concrete Encased

and REPLACE WITH:

Typical Ductbank Detail A, Sheet E01

7. E02

Detail 5, ADD:

Note: Stainless Steel Backplate to be 316 grade, 6mm thick, with a matte finish. Remove sharp edges and round corners.