



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada - Pacific
Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet Marker Pile Installation	
Solicitation No. - N° de l'invitation EZ899-200403/B	Amendment No. - N° modif. 001
Client Reference No. - N° de référence du client	Date 2019-07-09
GETS Reference No. - N° de référence de SEAG PW-\$PWY-019-8619	
File No. - N° de dossier PWY-9-42025 (019)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2019-07-12	Time Zone Fuseau horaire Pacific Daylight Saving Time PDT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Ngan, Ken (PWY)	Buyer Id - Id de l'acheteur pwy019
Telephone No. - N° de téléphone (604) 671-0219 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: PWGSC - Lake Windermere Groyne - Invermere, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation
EZ899-200403/B
Client Ref. No. - N° de réf. du client

Amd. No. - N° de la modif.
001
File No. - N° du dossier
pwy-9-42025

Buyer ID - Id de l'acheteur
pwy019
CCC No./N° CCC - FMS No/ N° VME

This Solicitation Amendment 001 is raised to incorporate Addendum No. 1, Addendum No. 2, and Addendum No. 3.

Please find following Addendum No. 1, Addendum No. 2, and Addendum No. 3.

All other terms and conditions remain unchanged.

The following changes in the tender documents are effective immediately. This addendum will form part of the contract documents

Tender Questions

During the tender period PSPC has received various questions from Contractors. The following section lists the questions received and the responses. The cost implications of the responses provided are to be included in the tender price.

1. Are you expecting the contractor to drive the pile through the builder base?

The piles may be driven through the boulders based on the typical cross section of the drawing Sheet 2 of 2. It also depends on the actual boulder thickness at each marker pile location. The boulder thickness may vary at each marker pile location.

2. Are we driving piles through the wood cribbing or where it is?

The piles will be driven through around the centre of the cross section of the boulders as indicated in the drawing Sheet 2 of 2. The coordinates of the proposed thirteen piles to be installed are indicated in the drawing Sheet 2 of 2.

3. What is a brush mattress and are we driving piles through this?

Brush mattress is the base of the boulders. Please read the responses to the questions 1 and 2.

4. It appears by the sketch the piles are to be 10 meters in length. Is this correct?

Yes, the piles are to be 10 meters in length. Each pile will be installed, as indicated in the drawing, 5 meters below the boulder surface and 5 meters above the boulder surface.

5. How many piles are to be removed?

There are no piles to be removed.

6. I assume this work has to be done from a barge. As the work has to happen in the summer. What is the water level at construction time?

During the summer construction time, the water level is considered to be in around the middle water level. Actual water level should be confirmed on site by the contractor.

END OF ADDENDUM No.1

The following changes in the tender documents are effective immediately. This addendum will form part of the contract documents

Tender Questions

During the tender period PSPC has received various questions from Contractors. The following section lists the questions received and the responses. The cost implications of the responses provided are to be included in the tender price.

- 1. As a pile driver, we cannot drive a wooden pile through boulders or a boulder field. Either the pile will have to be drilled or the boulders removed prior to installation. Is that how we are to price this??**

We have the test pit information by Hemmera and photos showing the boulders at the surface. We expect to be able to drive wood piles, and those should provide more information. If there are issues during the construction, Departmental Representative will deal with the issues.

Further Clarification to the Answer in Question 4 in Addendum No. 1

- 2. It appears by the sketch the piles are to be 10 meters in length. Is this correct?**

Pile length consists of 5 meters penetration plus the distance from the ground surface to the pile cut-off elevation. All the piles are to be installed 5 meters above the low water level to the top of the piles. The average length of each pile may be close to 10 meters but for some piles 10 meters maybe too short. The plan Sheet 1 of 2 shows the ground surface elevation.

END OF ADDENDUM No.2

The following changes in the tender documents are effective immediately. This addendum will form part of the contract documents

Tender Questions

During the tender period PSPC has received various questions from Contractors. The following section lists the questions received and the responses. The cost implications of the responses provided are to be included in the tender price.

Section 01 11 05 1.18 Environmental Factors

1.18.3 PSPC will retain an environmental monitor (EM). The Contractor will be responsible to coordinate and communicate with the EM. Contractor employees and employees of sub-contractors will be required to attend an environmental awareness briefing. This briefing may be tied into the Contractors site health and safety training. The EM will be responsible for such tasks as pre-construction and during construction bird nest surveys, water quality monitoring, acoustic monitoring and general monitoring of the Contractor activities.

END OF ADDENDUM No.3