



Addendum

Project FORT LENNOX NHS
Saint-Paul-de-l'Île-aux-Noix, Québec
MEN'S BARRACK CONSERVATION
PROJECT LOT 2
Project no. PRO-1396

Solicitation No.
Addendum No.
Date

5P201-19-0037/A
A-02
2019.07.03

ADMINISTRATIVE

1. PARKS CANADA CALL FOR TENDERS DOCUMENT

- .1 In Appendix 1 - Combined Price Form, page 12 of 48, item 4.9 New Staircase Procedures, amend the number of units (18 units shown) to 8 units.

ARCHITECTURE

2. GENERAL PRECISION

- .1 For various repairs and stone replacements for the exterior staircase leading to the ramparts, provide for sizing according to images 1 and 2 attached as well as the total dimensions provided in sheet A-004. The stones to be replaced or repaired must be the subject of workshop drawings as mentioned in specification section 04 03 43, paragraph 1.6 and must therefore be measured on site by the subcontractor for identical reproduction.

3. SPECIFICATIONS SECTION 01 00 00 00 GENERAL REQUIREMENTS - ARCHITECTURE

- .1 Add the following paragraph at the end of Part 1 – GENERAL :

1.18 FIRE SAFETY PLAN

1. Construction site safety must also comply with the requirements of Part 8 of the National Building Code of Canada 2015 and Section 5.6 of the National Fire Code of Canada 2015.
2. Before commencing the work, the Contractor must prepare and obtain Parks Canada approval of a fire safety plan for the site.
3. Plan to coordinate the fire safety plan with Parks Canada and the municipal fire department.

Prepared by : Catherine Richard, M.ARCH
For : Sylvie St-Martin, architect

Attached files : Picture 1 and picture 2

END OF ADDENDUM A-02

Image 1 / Picture 1



Image 2 / Picture 2

