

Addendum

Project FORT LENNOX NHS

Saint-Paul-de-l'Île-aux-Noix, Québec MEN'S BARRACK CONSERVATION

PROJECT LOT 2 Project no. PRO-1396 Solicitation No. Addendum No.

Date

5P201-19-0037/A

A-03 2019.07.08

ARCHITECTURE

1. PAGE A-004

.1 The stone wall of the ramparts (located behind the stairs on elevation 2) is not to be dismantled. Keep as existing but plan to protect when the staircase is completely dismantled.

2. PAGE R-100

.1 For specific note 21, refer to the submission form item 5.3, for the number of murder window to be provided.

3. PAGE R-800

.1 Precision for wooden batten floors: All existing wooden batten flooring must be removed and sandblasted on the ground floor. Refer also to drawing A-800 for the new sections to be provided as well as the technical specifications, section 06 20 00 - Carpentry/ Cabinetmaking and section 09 91 23 - Painting and Interior Works. Do not take into account the dotted lines around the different floor finishes in the legend.

Prepared by: Catherine Richard, M.ARCH

Catheline Libral

For : Sylvie St-Martin, architect

Attached files: N/A

END OF ADDENDUM A-03