



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada - Pacific
Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet Window Replacement	
Solicitation No. - N° de l'invitation F1700-195600/A	Amendment No. - N° modif. 001
Client Reference No. - N° de référence du client F1700-195600	Date 2019-07-25
GETS Reference No. - N° de référence de SEAG PW-\$PWY-031-8618	
File No. - N° de dossier PWY-9-42043 (031)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2019-07-29	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Leung, Janie	Buyer Id - Id de l'acheteur pwy031
Telephone No. - N° de téléphone (778) 919-3273 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: DFO - Pacific Biological Station - Nanaimo, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Les documents français seront disponibles sur demande.

This Amendment 001 is raised to address questions:

Questions and Answers

Q1. The aluminum panels between the first and second floor will need a seam as 48 x 120 is the largest sheet of aluminum available – please confirm this is acceptable.

A1. Sheet should be available up to 72 x 144

Q2. Glazing contractors have requested if the vertical mullions could run through instead of stopping at the first floor ceiling and continuing from the second floor. Please confirm.

A2. See above; this would be an aesthetic change to proposed design.

Q3. Please provide dimensions for window shown on Dwg. A3.2 Northwest Elevation, located at bottom right of wall.

A3. See attached original drawings. Dimensions not clear. Bidders should attend site to confirm and take all necessary measurements.

Q4. Scope in the Tender Notice state “- Remove and dispose of the interior guard rails, retain the handrails and reinstall the handrails with code compliant guard rails. Provide metal closure angles along the stairs and landings.”

- what is the detail for installation of retained handrails that are to be reinstalled? There are many handrail connections into the existing curtain wall

– is the intention that the new handrail connections are only into concrete? Please advise and provide detail.

- since the contractor is to remove and dispose of the interior guard rails, what is the detail for new “code compliant guard rails”? This is a general statement that could result in various installations for the new guard rails? And since the guard rails are not currently installed at all of the opening, just a select few, is the intention to match the same locations as existing? Or do the new guard rails get installed at all openings on all floors? Please review and advise and provide drawings/details for new guard rails

A4. Please refer to Summary of Work: “Remove and dispose of the existing interior guardrails but retain the handrails. Provide metal closure angles along the stairs and landings.” The handrails are not to be removed; the handrails do not provide the guardrail function; the curtain wall will function as the guardrail as it is to be designed to resist guardrail loads.

All other terms and conditions remain unchanged.