

ADDENDUM #1
Small Boat Basin Development - Brighton, NL
F5211-190293

CORRECTION TO ENGLISH VERSION ONLY

PLEASE DELETE

DELIVERABLES / SCOPE OF WORK

The work covered under this contract consists of the furnishing of all plant, labour, equipment, and material for paving at Fogo NL, in strict accordance with the specifications and accompanying drawings and subject to all terms and conditions of the contract.

In general, work under this contract will consist of but will not necessarily be limited to the following:

- Re-grading the existing uplands area, as noted on the drawings (existing asphalt is to be removed, as noted on the drawings).
- Supply and installation of class “A/B” granulars, in the area noted on the drawings.
- Paving, as noted on the drawings (2-lifts of 40mm asphalt, for a total thickness of 80mm).

PLEASE INSERT

DELIVERABLES / SCOPE OF WORK

The work covered under this contract consists of the furnishing of all plant, labour, equipment, and material for small boat basin development at Brighton, NL, in strict accordance with the specifications and accompanying drawings and subject to all terms and conditions of the contract.

In general, work under this contract will consist of but will not necessarily be limited to the following:

- Demolition of the existing wharf, as noted on the drawings.
- Construction of one (1) new treated timber crib, to the dimensions as indicated on the drawings.
- Supply and installation of a new wooden gangway, as shown on the drawings.
- Supply and installation of floating docks as noted on the drawings, including anchor chains and concrete mooring blocks.
- Construction of a gravel launch and uplands development including granulars, geotextile/filter stone/armour stone on side slopes, as indicated on the drawings.