



## RETURN BIDS TO:

## RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government  
Services Canada/Réception des soumissions Travaux  
publics et Services gouvernementaux Canada  
800 Burrard Street, Room 219  
800, rue Burrard, pièce 219  
Vancouver  
British Columbia  
V6Z 0B9  
Bid Fax: (604) 775-9381

## SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise  
indicated, all other terms and conditions of the Solicitation  
remain the same.

Ce document est par la présente révisé; sauf indication contraire,  
les modalités de l'invitation demeurent les mêmes.

### Comments - Commentaires

Vendor/Firm Name and Address  
Raison sociale et adresse du  
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution  
Public Works and Government Services Canada - Pacific  
Region  
800 Burrard Street, Room 219  
800, rue Burrard, pièce 219  
Vancouver  
British C  
V6Z 0B9

<b>Title - Sujet</b> STF Soil Turning	
<b>Solicitation No. - N° de l'invitation</b> EZ897-200716/A	<b>Amendment No. - N° modif.</b> 003
<b>Client Reference No. - N° de référence du client</b>	<b>Date</b> 2019-08-07
<b>GETS Reference No. - N° de référence de SEAG</b> PW-\$PWY-039-8627	
<b>File No. - N° de dossier</b> PWY-9-42049 (039)	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin</b> <b>at - à 02:00 PM</b> <b>on - le 2019-08-12</b>	<b>Time Zone</b> <b>Fuseau horaire</b> Pacific Daylight Saving Time PDT
<b>F.O.B. - F.A.B.</b> <b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input checked="" type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> Park (PWY), Isabell	<b>Buyer Id - Id de l'acheteur</b> pwy039
<b>Telephone No. - N° de téléphone</b> (604) 365-0073 ( )	<b>FAX No. - N° de FAX</b> (604) 775-9381
<b>Destination - of Goods, Services, and Construction:</b> <b>Destination - des biens, services et construction:</b> PWGSC - Various Locations - Alaska Highway, BC	

Instructions: See Herein

Instructions: Voir aux présentes

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address</b> <b>Raison sociale et adresse du fournisseur/de l'entrepreneur</b>	
<b>Telephone No. - N° de téléphone</b> <b>Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm</b> <b>(type or print)</b> <b>Nom et titre de la personne autorisée à signer au nom du fournisseur/</b> <b>de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

## Amendment 003

### Questions and Answers

Q: Contact information for people who run and maintain Iron Creek Maintenance Camp, JJJ Gravel Pit and Km 713 Gravel Pit

A: Contact information will be provided to the contractor upon contract award.

Q: According to Section 02 61 00.07 "Contaminated Sites Onsite STF Operation 3.3.6 – Movement of treated soil to final treated stockpile area is located within 100 meters of the soil treated facility. But according to the Site Plan -JJJ Gravel Pit DWG No: 636200-1009 the distance from the STF 1,2,3,4 to Compliant soil stock pile is much greater than 100 meters.

A: For JJJ STF, movement of treated soil to final treated stockpile area is located within 600 meters of the soil treated facility.

Q: Do we require a wash station and an office facilities for each location in Iron Creek Maintenance Camp, JJJ Gravel Pit and Km 713 Gravel Pit?

A: Yes

Q: Where are the treated soils being relocated to for each of the sites?

A: For Iron Creek STF and Mile 713 STF, as per Division 02 61 00.07, Part 3.3.6. Following in-situ sampling and confirmation by Departmental Representative, move treated soil from Soil Treatment Facility to the final treated soil stockpile area located within 100 m of the Soil Treatment Facility as directed by the Departmental Representative. For JJJ STF, movement of treated soil to final treated stockpile area is located within 600 meters of the soil treated facility.

Q: For the treated soil relocation quantities found in the Price Form, are these firm quantities for how much treated soil will be relocated or might the quantities vary?

A: No anticipated changes to the quantities at this time.

Q: How many pieces of equipment are required at JJJ STF?

A: Refer to Division 02 61 00.07, Part 2.2.1 Add: For JJJ STF, minimum of two tillers to be one or more tractor and/ or excavator to achieve efficient aeration of each 400 mm lift.

Q: Although the soil quantities at each work site varies from one site to another the total hours allocated for tilling are equal for all three sites (420 hrs). Can you confirm the duration of tilling that is expected at each facility?

A: Duration will be as indicated in unit price table. Tilling duration may not be dependent on volume.

Q: Is there a duration of tilling per m2 of lift that is expected for this work scope for each STF?

A: Per Division 02 61 00.07, Part 3.3.3 Aerate Till the upper 400 mm of the contaminated soil within Soil Treatment Facility based on field observations by Departmental Representative. This process will be repeated for additional lifts as the upper layer is deemed treated by the Departmental Representative.

All other terms and conditions remain unchanged.