

1 Floor Finish Plan - 21st Floor
Scale: 1:100

Floor Finish Legend:

-  Carpet Plank - General
Colour: Light grey, dark grey and black linear pattern
Installation: Brick
Size: 457mm x 914mm
-  Carpet Plank - Accent
Colour: Teal, navy and light grey linear pattern
Installation: Brick, as shown on plan
Size: 457mm x 914mm
-  Carpet Tile - Accent
Colour: Solid yellow
Installation: Brick
Size: 457mm x 915mm, tile size not shown
-  Luxury Vinyl Tile (LVT)
Pattern: Wood Grain
Colour: Taupe
Size: 152mm x 219mm
-  Indicates direction of flooring pattern.

Floor Finish Drawing Notes:

- ① Starting point of flooring installation (full tile)

Floor Finish General Notes:

1. It is the Contractor's responsibility to refer to all information in the Specification Document.
2. It is the Contractor's responsibility to read this drawing in conjunction with all other drawings in this package. Report any discrepancies between drawings prior to commencing work.
3. Contractor will be held responsible for any damage done to existing partitions, ceiling, finishes and all other components to remain and to adjacent spaces.
4. Contractor to provide samples of all finishes for Departmental Representative's approval prior to ordering any material.
5. Existing slab to be prepped, holes patched and made ready to receive new floor finish. Refer to Specification Document for further instructions.
6. When two flooring finishes meet at a doorway, joint to be covered when door is in closed position.
7. Supply and install 108mm high resilient baseboard on all existing new gypsum board partitions, perimeter walls, core wall, columns, etc.
8. Where LVT meets carpet, supply and install slim line vinyl transition strip. Departmental Representative to select from standard colour range.
9. Where LVT and carpet flooring installed, supply and install 108mm high resilient baseboard only at gypsum board partitions. Departmental Representative to select from standard colour range.
10. Contractor to protect new and existing floor finishes using POLY 6 mil (minimum).
11. Contractor to level floor with latitecrete or equal to accept floor finish material as required.
12. Carpet accents and other flooring patterns to be chalked for Departmental Representative's approval prior to commencing work.
13. Contractor to continue carpet baseboard under perimeter convactor units.
14. New flooring to continue wall to wall, under millwork, lockers, sinks, etc.
15. Provide 5% site stock for carpet C1, 5% for carpet C2, 5% for carpet C3 and 1m² for LVT V1.




Canada



211-2141 Thurston Drive
Ottawa, ON K1G 1G3
T 613-739-3690
F 613-739-3665
info@LWG-ai.com LWC-ai.com

This drawing is the property of the designer. Copyright is reserved. No reproduction may be made without prior consent of the designers and each issuer must bear their names. This drawing shall not be used for construction purposes until signed by the designer. The contractor is to verify dimensions and data noted herein with the conditions on the site and report any discrepancy to the designer. Do not scale this drawing.



Key Plan



Project North



ARIDO
David Gibbons
Member of the Order of Architects of Ontario

I, the undersigned, have reviewed and have responsibility for this design work on behalf of the firm, I am qualified, and the firm is registered in the appropriate design category.

QUALIFICATION INFORMATION		
David Gibbons	David Gibbons	25000
REGISTRATION INFORMATION		
LWG Architectural Interiors Inc.		42687

Contractor to verify all dimensions & conditions on site and immediately notify the engineer of all discrepancies.

revisions	description	date
04	Issued for Addendum 01	2018-07-16
03	Issued for Tender	2018-01-15
02	Issued for 90% Client Review	2018-03-09
01	Issued for 60% Client Review	2018-02-16

A

B

C

project project

LEL Generic Swing Space

300 Laurier West, Ottawa, N

drawing dessin

Floor Finish Plan 21st Floor

Scale: As Noted

Designed By	BB & MB	Conçu par
Date	2018-01-26	(yyyy/mm/dd)
Drawn By	MB	Dessiné par
Date	2018-03-09	(yyyy/mm/dd)
Reviewed By	<i>[Signature]</i>	Examiné par
Date	2018-01-26	(yyyy/mm/dd)
Approved By	BB	Approuvé par
Date	2018-01-26	(yyyy/mm/dd)
Tender	Brent Cheff	Soumission
Project Manager	Brent Cheff	Administrateur de projets
Project no.	R.088901.013 (17096)	No. du projet
Drawing no.	ID27	No. du dessin