

1  
11 11  
Reflected Ceiling Demolition Plan - 17th Floor  
Scale: 1:100

Reflected Ceiling Demolition Legend:


- Fluorescent light fixture to be removed and retained for reuse. Refer to Electrical drawings.
- Fluorescent light fixture to be removed and discarded. Refer to Electrical drawings.
- Downlight fixture to be removed discarded. Refer to Electrical drawings.
- Existing suspended T-bar ceiling grid to remain. Contractor to remove and discard existing ceiling tiles.
- Suspended T-bar ceiling grid, acoustical tiles and related components to be removed and discarded.
- Suspended gypsum board ceiling and related components to remain.

Reflected Ceiling Demolition Notes:


- Existing elevator lobby ceiling finish to remain.

Reflected Ceiling Demolition General Notes:

- It is the Contractor's responsibility to refer to all information in the Specification Document.
- It is the Contractor's responsibility to read this drawing in conjunction with all other drawings in this package. Report any discrepancies between drawings to prior to commencing with Construction.
- Contractor will be held responsible for any damage done to existing partitions, ceiling, finishes and all other components to remain and to adjacent spaces.
- Refer to Mechanical and Electrical drawings for extent of demolition.
- Contractor to remove and turn over to Departmental Representative all items not being used for new construction, unless otherwise noted.
- Extend existing suspended T-bar grid ceiling as required where slab to slab partitions were removed. Supply and install new acoustical tiles as required. Style and colour to match existing. Secure new and existing T-bar ceiling grid as required.
- Contractor to remove and re-install existing suspended T-bar ceiling grid and acoustical tiles as required for mechanical demolition. Refer to Mechanical drawings. Contractor to avoid cutting main T-bar suspension "T" whenever possible.



Key Plan



Project North



I, the undersigned have reviewed and take responsibility for this design work on behalf of the firm. I am qualified and the firm is registered, in the appropriate design discipline.

David Gibbons *David Gibbons* 25000  
P.Eng. (Mechanical) 2010

REGISTRATION INFORMATION  
The undersigned is a member of the following organization:  
LLWJ Architectural Interiors Inc. 42887  
2010

Contractor to verify all dimensions & conditions on site and immediately notify the engineer of all discrepancies.


04	Issued for Addendum 01	2019-07-16
03	Issued for Tender	2019-01-14
02	Issued for 90% Client Review	2018-03-09
01	Issued for 60% Client Review	2018-02-16

revisions	description	date
A	A detail no. no. 01 detail	A
B	B location drawing no. sur design no.	B
C	C drawing no. design no.	C

project project

LEL Generic  
Swing Space

300 Laurier West, Ottawa, ON

drawing dessin

Reflected Ceiling  
Demolition Plan  
17th Floor

Scale: As Noted

Designed By RB & MB Conçu par  
Date 2018-01-26 (yyyy/mm/dd)

Drawn By MB Dessiné par  
Date 2018-03-09 (yyyy/mm/dd)

Reviewed By *BW* Examiné par  
Date 2018-01-26 (yyyy/mm/dd)

Approved By BW Approuvé par  
Date 2018-01-26 (yyyy/mm/dd)

Tender Soumission

Project Manager Brent Cheff Administrateur de projets

Project no. No. du projet

R.088901.013 (17096)

Drawing no. No. du dessin

ID11