

1 Demolition Plan - 17th Floor
Scale: 1:100

Demolition Legend:

- Interior walls of suspended T-bar partition to be removed and discarded.
- Interior walls of suspended T-bar partition w/ plenum barrier and/or slab to be removed and discarded.
- Existing door, door frame, hardware and related components to be removed and discarded.
- Existing door, door frame w/ sidelight(s), hardware and related components to be removed and discarded.
- Existing sliding door, door frame, hardware and related components to be removed and discarded.
- Existing double door, door frame, hardware and related components to be removed and discarded.
- Existing carpet tile and related components to be removed and discarded throughout project area unless noted otherwise. Symbol not shown at all locations. Contractor to patch, repair and prepare floor to receive new floor finish per Floor Finish Plan on ID24, 25, 26, 27.
- Existing marmoleum flooring and related components to be removed and discarded. Contractor to patch, repair and prepare floor to receive new floor finish per Floor Finish Plan on ID24, 25, 26, 27.

Demolition Drawing Notes:

- 1 Repair gypsum board at columns where partitions have been removed to Level 4.
- 2 Patch and repair to Level 4 all core partitions where demolition has occurred.
- 3 Existing millwork service counter and related components to be removed and discarded.
- 4 Contractor to remove existing field applied vinyl wall covering, skim coat, and prepare to Level 4 ready to receive new wall finish.
- 5 Remove existing elevator lobby directory signage with care and retain for reinstallation.
- 6 Slab mounted projector mount to be removed and discarded.
- 7 Projector screen and existing hardware to be removed and discarded.
- 8 Rolling security grill and existing hardware to be removed and discarded.
- 9 Plastic corner guards to be removed and discarded.
- 10 Contractor to remove existing roller blind mounted to partition with care. Supply and install new "L" bracket to mount blind to window mullion.
- 11 Contractor to remove existing wall sconce. Supply and install new cover plate.
- 12 Contractor to remove existing gypsum board from floor to u/s of suspended ceiling. Replace with new and prepare to Level 4 ready to receive new wall finish.
- 13 Contractor to protect existing plastic laminate drinking fountain and fire hose cabinet surround from damage during demolition and construction activities.


Demolition General Notes:

1. It is the Contractor's responsibility to refer to all information in the Specification Document.
2. It is the Contractor's responsibility to read this drawing in conjunction with all other drawings in this package. Report any discrepancies between drawings prior to commencing with Construction.
3. Contractor will be held responsible for any damage done to existing partitions, ceiling, finishes and all other components to remain and to adjacent spaces.
4. Refer to Mechanical and Electrical drawings for extent of demolition.
5. Unless otherwise noted, all existing partitions, door sidelight assembly, floor finish, etc. to remain.
6. Contractor to remove and turn over to Departmental Representative all items not being used for new construction, unless otherwise noted.
7. Contractor to remove and discard all floor finishes and baseboards as indicated.
8. Contractor to remove all existing carpet tile.
9. All existing floor mounted door stops to be removed and discarded.
10. Contractor to remove all non-essential data and communication wiring within plenum.
11. All existing perimeter convectors to remain. Refer to Mechanical drawings. Refer to Wall Finish Plan on ID28, 29, 30, 31.
12. Cut, cap and fire stop plumbing lines flush with concrete slab. Refer to Mechanical Drawings.
13. Contractor to remove/clean all glue/2-way tape residue on perimeter window mullion where partition was removed and throughout the space where required.
14. All existing perimeter blinds/window treatment to remain. Contractor to bundle and wrap blinds/window shades adequately for dust protection prior to Construction. Contractor to include for the removal and replacement of 50% of the existing roller shades with new. Width from centreline of mullion is 1525mm. Height of glazing 2667. Refer to Specification.



211-2141 Thurston Drive
Ottawa ON K1G 1G3
info@LWG-ai.com LWG-ai.com
T 613-739-3690 F 613-739-3665

This drawing is the property of the designer. Copyright is reserved. No reproduction may be made without prior consent of the designers and each owner must bear their names. This drawing shall not be used for construction purposes until signed by the designer. The contractor is to verify dimensions and data noted herein with the conditions on the site and report any discrepancy to the designer. Do not scale this drawing.



Key Plan



Project North




I, the undersigned, have reviewed and have responsibility for this design with the exception of the items noted, and the firm is registered in the appropriate provincial jurisdiction.

David Gibbons *David Gibbons* 25000
Architect
REGISTRATION INFORMATION
Professional Member of the Order of Architects of Ontario
LWG Architectural Interiors Inc. 42687
Ottawa, Ontario

Contractor to verify all dimensions & conditions on site and immediately notify the engineer of all discrepancies.

revisions	description	date
04	Issued for Addendum 01	2018-07-16
03	Issued for Tender	2018-01-15
02	Issued for 90% Client Review	2018-03-06
01	Issued for 60% Client Review	2018-02-16



project
LEL Generic Swing Space
300 Laurier West, Ottawa, ON

drawing
Demolition Plan 17th Floor

Scale: As Noted

Designed By	BB & MB	Conçu par
Date	2018-01-26	(yyyy/mm/dd)
Drawn By	MB	Dessiné par
Date	2018-02-16	(yyyy/mm/dd)
Reviewed By	<i>[Signature]</i>	Examiné par
Date	2018-01-26	(yyyy/mm/dd)
Approved By	BW	Approuvé par
Date	2018-01-26	(yyyy/mm/dd)
Tender		Soumission
Project Manager	Brent Cheff	Administrateur de projets
Project no.		No. du projet
	R.088901.013 (17096)	
Drawing no.		No. du dessin
	ID07	