

Wall Finish Legend:

- P1 Paint - General
Colour: White
Finish: Gloss Level 3
- P2 Paint - Accent
Colour: Chateau Yellow
Finish: Gloss Level 3
- P3 Paint - Accent
Colour: Teal Blue
Finish: Gloss Level 3
- P4 Paint - Accent
Colour: Medium Grey
Finish: Gloss Level 5
- F1 Felt Panel
Colour: Light Grey
Thickness: 12mm
- F2 Felt Panel
Colour: Teal Green
Thickness: 12mm
- L4 Demountable Wall Finish (White)
Colour: White
- T1 Ceramic Tile Backsplash (White)
Pattern/Colour: White Ceramic Mosaic
Grout: Departmental Representative to pick from standard colour range.
Width of grout line: 3mm.
- G1 Back-painted Glass Board (White)
Colour: White
Notes:
- Back-painted glass from 814mm A.F.F. to 2135mm A.F.F. Refer to Elevation 3 on ID33.
- CG Stainless steel corner guard where shown.
Material: 16 gauge stainless steel
Notes:
- Dimension: 51mm x 51mm x 1220mm H
- Mounting Height: Install above baseboard
- Notes:
- Install per Manufacturer's instructions
- Adhere to partition and install straight
- Ensure all edges are secured to partition. Ensure no edges protrude to prevent harm to someone or something. If top edges cannot be adhered to partition, provide clear caulking and ensure smooth edges.

Wall Finish Drawing Notes:


- 1 Felt panels suspended from ceiling. See elevations on ID33.
- 2 Existing base building doors and frames to be painted P4.
- 3 Elevator doors and frames on all exposed surfaces to be painted P3, lobby side only.
- 4 Metal Edge Trim
Contractor to finish edge of ceramic tiles with metal trim as indicated.
Finish: Brushed stainless steel
Note:
Thickness of trim to suit application.

Wall Finish General Notes:

1. It is the Contractor's responsibility to refer to all information in the Specification Document.
2. It is the Contractor's responsibility to read this drawing in conjunction with all other drawings in this package. Report any discrepancies between drawings to prior to commencing with Construction.
3. Contractor will be held responsible for any damage done to existing partitions, ceiling, finishes and all other components to remain and to adjacent spaces.
4. Contractor to provide samples of all finishes for Departmental Representative's approval prior to ordering any materials.
5. Patch, sand, repair and make good to level 4 ready to receive new partition finish all existing gypsum board and plaster surfaces throughout the space prior to painting. Contractor to ensure finished partition is smooth, straight and even.
6. All wall finishes to be supplied and installed by Contractor unless otherwise noted.
7. Except where noted otherwise, all existing partitions, core walls, columns and new partitions to be painted P1.
8. L4 typical wall finish for demountable partitions unless otherwise noted.
9. Remove door hardware and signage prior to painting of existing doors and frames. Reinstall once final paint coat has thoroughly dried.
10. All closet interiors to be painted P1, unless otherwise noted.
11. All doors to be primed and painted P4 unless otherwise noted. Refer to Door Hardware Schedule on ID34 for further details.
12. All perimeter convactor units to be painted to match wall finish P1, refer to Specification Document.
13. Refer to Elevations on drawing ID35 for wall tile pattern.
14. Unless otherwise noted, all movable partition glazing to receive window film on room interior side. Refer to Elevation 4 on ID33 for details.



This drawing is the property of the designer. Copyright is reserved. No reproduction may be made without prior consent of the designers and each owner must bear their names. This drawing shall not be used for construction purposes until signed by the designer. The contractor is to verify dimensions and data noted herein with the conditions on the site and report any discrepancy to the designer. Do not scale this drawing.




I, the undersigned, have reviewed and take responsibility for this design with the exception of the items noted, and the firm is registered in the appropriate design category.

David Gibbons Architectural Designer No. 25030, Ontario

REGISTRATION INFORMATION
The Professional Designation of Architectural Designer
LWG Architectural Interiors Inc. 42687, Ontario

Contractor to verify all dimensions & conditions on site and immediately notify the engineer of all discrepancies.

revisions	description	date
04	Issued for Addendum 01	2018-07-04
03	Issued for Tender	2018-01-15
02	Issued for 90% Client Review	2018-03-09
01	Issued for 60% Client Review	2018-02-16



project		project
LEL Generic Swing Space		
300 Laurier West, Ottawa, N		
drawing		dessin
Wall Finish Plan 17th Floor		
Scale: As Noted		
Designed By	BB & MB	Conçu par
Date	2018-01-26	(yyyy/mm/dd)
Drawn By	MB	Dessiné par
Date	2018-03-09	(yyyy/mm/dd)
Reviewed By	BYW	Examiné par
Date	2018-01-26	(yyyy/mm/dd)
Approved By	BYW	Approuvé par
Date	2018-01-26	(yyyy/mm/dd)
Tender		Soumission
Project Manager	Brent Cheff	Administrateur de projets
Project no.		No. du projet
R.088901.013 (17096)		
Drawing no.		No. du dessin
ID28		