



1 Reflected Ceiling Demolition Plan - 21st Floor
Scale: 1:100

- Reflected Ceiling Demolition Legend:**
- Fluorescent light fixture to be removed and retained for reuse. Refer to Electrical drawings.
 - Fluorescent light fixture to be removed and discarded. Refer to Electrical drawings.
 - Downlight fixture to be removed and discarded. Refer to Electrical drawings.
 - Existing suspended T-bar ceiling grid to remain. Contractor to remove and discard existing ceiling tiles.
 - Suspended T-bar ceiling grid, acoustical tiles and related components to be removed and discarded.
 - Suspended gypsum board ceiling and related components to remain.

- Reflected Ceiling Demolition Drawing Notes:**
- 1 Existing elevator lobby ceiling finish to remain.
 - 2 Existing aggregate diffusers and slab mounted light fixtures to be removed. Refer to Electrical drawings for details.

- Reflected Ceiling Demolition General Notes:**
1. It is the Contractor's responsibility to refer to all information in the Specification Document.
 2. It is the Contractor's responsibility to read this drawing in conjunction with all other drawings in this package. Report any discrepancies between drawings to prior to commencing with Construction.
 3. Contractor will be held responsible for any damage done to existing partitions, ceiling, finishes and all other components to remain and to adjacent spaces.
 4. Refer to Mechanical and Electrical drawings for extent of demolition.
 5. Contractor to remove and turn over to Departmental Representative all items not being used for new construction, unless otherwise noted.
 6. Extend existing suspended T-bar grid ceiling as required where slab to slab partitions were removed. Supply and install new acoustical tiles as required. Style and colour to match existing. Secure new and existing T-bar ceiling grid as required.
 7. Contractor to remove and re-install existing suspended T-bar ceiling grid and acoustical tiles as required for mechanical demolition. Refer to Mechanical drawings. Contractor to avoid cutting main T-bar suspension "T" whenever possible.

Public Works and Government Services Canada / Travaux publics et Services gouvernementaux Canada

Canada

LWG ARCHITECTURAL INTERIORS
211-2141 Thurston Drive, Ottawa, ON K1G 1G3
T 613-739-3690, F 613-739-3665, info@LWG-ci.com, LWG-ci.com

This drawing is the property of the designer. Copyright is reserved. No reproduction may be made without prior consent of the designers and each owner must bear their names. This drawing shall not be used for construction purposes until signed by the designer. The contractor is to verify dimensions and data noted herein with the conditions on the site and report any discrepancy to the designer. Do not scale this drawing.

Key Plan

Project North

I, the undersigned, have reviewed and take responsibility for this design with the exception of the items noted, and the firm is registered in the appropriate federal province.

David Gibbons, Ontario Professional Engineer No. 25000

LWG Architectural Interiors Inc., 42687

Contractor to verify all dimensions & conditions on site and immediately notify the engineer of all discrepancies.

03	Issued for Tender	2018-01-14
02	Issued for 90% Client Review	2018-03-09
01	Issued for 60% Client Review	2018-02-16

revisions	description	date
A	A detail no. no. 00 detail	
B	B location drawing no. sur dessin no.	
C	C drawing no. dessin no.	

project project

LEL Generic Swing Space
300 Laurier West, Ottawa, N

drawing dessin

Reflected Ceiling Demolition Plan 21st Floor
Scale: As Noted

Designed By	BB & MB	Conçu par
Date	2018-01-26	(yyyy/mm/dd)
Drawn By	MB	Dessiné par
Date	2018-03-09	(yyyy/mm/dd)
Reviewed By	BW	Examiné par
Date	2018-01-26	(yyyy/mm/dd)
Approved By	BW	Approuvé par
Date	2018-01-26	(yyyy/mm/dd)
Tender	Brent Cheff	Soumission
Project Manager	Brent Cheff	Administrateur de projets
Project no.	R.088901.013 (17096)	No. du projet
Drawing no.	ID14	No. du dessin