

1 Reflected Ceiling Demolition Plan - 20th Floor
 13 13 Scale: 1:100

Reflected Ceiling Demolition Legend:

- Fluorescent light fixture to be removed and retained for reuse. Refer to Electrical drawings.
- Fluorescent light fixture to be removed and discarded. Refer to Electrical drawings.
- Downlight fixture to be removed and discarded. Refer to Electrical drawings.
- Existing suspended T-bar ceiling grid to remain. Contractor to remove and discard existing ceiling tiles.
- Suspended T-bar ceiling grid, acoustical tiles and related components to be removed and discarded.
- Suspended gypsum board ceiling and related components to remain.

Reflected Ceiling Demolition Drawing Notes:

- 1 Existing elevator lobby ceiling finish to remain.
- 2 Existing aggregate diffusers and slab mounted light fixtures to be removed. Refer to Electrical drawings for details.

Reflected Ceiling Demolition General Notes:

1. It is the Contractor's responsibility to refer to all information in the Specification Document.
2. It is the Contractor's responsibility to read this drawing in conjunction with all other drawings in this package. Report any discrepancies between drawings to prior to commencing with Construction.
3. Contractor will be held responsible for any damage done to existing partitions, ceiling, finishes and all other components to remain and to adjacent spaces.
4. Refer to Mechanical and Electrical drawings for extent of demolition.
5. Contractor to remove and turn over to Departmental Representative all items not being used for new construction, unless otherwise noted.
6. Extend existing suspended T-bar grid ceiling as required where slab to slab partitions were removed. Supply and install new acoustical tiles as required. Style and colour to match existing. Secure new and existing T-bar ceiling grid as required.
7. Contractor to remove and re-install existing suspended T-bar ceiling grid and acoustical tiles as required for mechanical demolition. Refer to Mechanical drawings. Contractor to avoid cutting main T-bar suspension "T" whenever possible.

Canada

LWG
 ARCHITECTURAL INTERIORS
 211-2141 Thurston Drive
 Ottawa, ON K1G 1G3 (OCC)
 info@LWG-ci.com LWG-ci.com
 T 613-739-3690 F 613-739-3665

This drawing is the property of the designer. Copyright is reserved. No reproduction may be made without prior consent of the designers and each owner must bear their names. This drawing shall not be used for construction purposes until signed by the designer. The contractor is to verify dimensions and data noted herein with the conditions on the site and report any discrepancy to the designer. Do not scale this drawing.



Key Plan

Project North




I, the undersigned, have reviewed and have responsibility for this design with the exception of the items noted, and the firm is registered in the appropriate provincial jurisdiction.

QUALIFICATION INFORMATION
 David Gibbons License No. 25030
 REGISTRATION INFORMATION
 LWG Architectural Interiors Inc. 42687

Contractor to verify all dimensions & conditions on site and immediately notify the engineer of all discrepancies.

revisions	description	date
04	Issued for Addendum 01	2018-07-14
03	Issued for Tender	2018-01-14
02	Issued for 90% Client Review	2018-03-09
01	Issued for 60% Client Review	2018-02-16



project project

LEL Generic Swing Space

300 Laurier West, Ottawa, N

drawing		dessin
Reflected Ceiling Demolition Plan 20th Floor		
Scale: As Noted		
Designed By	BB & MB	Conçu par
Date	2018-01-26	(yyyy/mm/dd)
Drawn By	MB	Dessiné par
Date	2018-03-09	(yyyy/mm/dd)
Reviewed By	<i>[Signature]</i>	Examiné par
Date	2018-07-14	(yyyy/mm/dd)
Approved By	BIW	Approuvé par
Date	2018-01-26	(yyyy/mm/dd)
Tender		Soumission
Project Manager	Brent Cheff	Administrateur de projets
Project no.		No. du projet
	R.088901.013 (17096)	
Drawing no.		No. du dessin
	ID13	