

Project: PSPC CSC CCC Kitchen Washroom Renovations, ET025-200608

Addendum forms part of the Contract Documents and modifies the Bidding Documents dated 2019-05-17, with amendments and additions noted below. Where inconsistent with the drawings and specification, this Addendum shall govern. The same conditions of Contract and General Requirements shall apply to this Addendum as to the original drawings and specifications. Bidders are to review the entire Addendum to confirm all work affecting their Section.

Electrical:

1. Drawings:

.1 E2.5 Main Floor – Renovation Power Plan:

.1 Revise Keynote 1 as follows:

- .1 Provide two new kitchen panelboards '1B-1' (replaces existing panelboard 1B) and '1B-2' (new), 120/240V 1PH 3W 60CCT, 125A. Provide new 3C # 1 AWG, #6 bond, 35MMC feeders from distribution panel 'MD' located in the basement for each new panelboard. Utilise existing 125A/2P breaker from distribution panel 'MD' for new panelboard '1B-1'. Provide a new 125A/2P breaker from distribution panel 'MD' for panelboard '1B-2'. Connect all new kitchen loads to the new panelboard '1B-1'. Reroute/Extend/Refeed all existing loads from the old panelboard 1B to the new panelboard '1B-2'. Confirm total number of circuit breakers and circuit ratings required prior to demolishing existing panelboard 1B

.2 E2.9 Electrical Schedules:

- .1 Revise Panelboard 1B Schedule to Panelboard 1B-1.