

PART 1 - GENERAL

1.1 DESCRIPTION

- .1 This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed.
- .2 Demolition and removal will consist of, but not necessarily be limited to, the following:
 - .1 Removal of existing armour stone to facilitate new work, as shown on the drawings. Reinstall armour stone on the uplands slope, as shown on the drawings.
 - .2 Removal and reinstall existing scour protection as required to facilitate new work, as shown on the drawings.
 - .3 Remove and reinstall existing stone barricades, as shown on the drawings.
 - .4 Refer to electrical drawings for all electrical related items to be removed, temporarily disconnected and reinstated.

1.2 PROTECTION

- .1 Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Canada.
- .2 Place a floating boom around entire demolition side to prevent loss of any materials. Remove all floating debris from water on a routine and timely basis.

1.3 MEASUREMENT FOR PAYMENT

- .1 No separate measure for payment shall be made for items under this section. Include costs for Sitework, Demolition and Removal in the lump sum price arrangement.

PART 2 - PRODUCTS

N/A

PART 3 - EXECUTION

3.1 EXECUTION

- .1 Inspect site and verify with the Departmental Representative objects designated for removal.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.

3.2 REMOVAL

- .1 Remove in their entirety all materials and objects specified for removal.
- .2 Do not disturb adjacent work designated to remain in place.

3.3 DISPOSAL OF MATERIAL

- .1 All demolished materials, except materials designated to be salvaged for the Departmental Representative or reused on the project, will be property of Contractor and will be removed from site and disposed of at a provincially approved waste disposal facility as per the attached Regulatory Approvals.
- .2 Contractor to dispose of all demolished materials at a provincially approved waste disposal facility as per the attached Regulatory Approvals. Ensure that disposal site is approved and willing to accommodate any materials disposed of from work site.
- .3 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal facility.
- .4 Excavated material from below water to be transported using watertight dump trucks to a provincially approved waste disposal facility.

3.4 RESTORATION

- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.