



SMALL CRAFT HARBOURS


PROBES WERE COMPLETED ON MAY 25, 2016 BY BAILEYS MARINE SERVICE LTD. PRIOR TO ANY CONSTRUCTION ACTIVITY AT SITE (i.e. PHASE 1 CONSTRUCTION). SITE FEATURES HAVE SINCE CHANGED AND ARE NOT REFLECTED ON THIS PARTIAL PROBE PLAN. REFER TO SHEET C1 FOR ALL EXISTING SITE FEATURES.
REFUSAL DEPTH OF PROBES ARE NOT NECESSARILY INDICATIVE OF BEDROCK OR DENSE HARD BOTTOM ELEVATIONS.
PROBES WERE COMPLETED USING A STEEL ROD, 1.5m LONG WHICH WAS DRIVEN TO REFUSAL INTO THE SEA FLOOR BY THE DIVER STRIKING IT WITH A 5kg HAMMER.

PROBE #	BOTTOM TYPE	PENETRATION DEPTH (mm)
12	FRACTURED BEDROCK	0
13	FRACTURED BEDROCK	0
28	SOFT SEDIMENT	600
29	FRACTURED BEDROCK	0
30	FRACTURED BEDROCK	0
43	SOFT SEDIMENT	1500+
46	SOFT SEDIMENT	900
47	FRACTURED BEDROCK	0
50	SOFT SEDIMENT	300
51	SOFT SEDIMENT	350
52	FRACTURED BEDROCK	0
57	FRACTURED BEDROCK	0

GENERAL LEGEND:

— — — — — OUTLINE OF NEW FINGER
PIER TO BE CONSTRUCTED

APPROXIMATE PROBE
LOCATION (7.62m x 7.62m
GRID)



				date
C	ISSUED FOR TENDER	19/06/20		
B	ISSUED FOR 99% REVIEW	19/07/24		
A	ISSUED FOR 66% REVIEW	19/06/21		

FINGER PIER
PHASE 2

CHARLOTTETOWN
LABRADOR

Following **design**

SEA BOTTOM
PROBE INFORMATION

[illegible]

1) EXISTING SITE PLAN WITH APPROXIMATE PROBE LOCATIONS

